

stowa

VERKENNING ZUIVERENDE KASSEN



RAPPORT

2017
45



ISBN 978.90.5773.772.5



stowa@stowa.nl www.stowa.nl
TEL 033 460 32 00
Stationsplein 89 3818 LE Amersfoort
POSTBUS 2180 3800 CD AMERSFOORT

Publicaties van de STOWA kunt u bestellen op www.stowa.nl

COLOFON

UITGAVE Stichting Toegepast Onderzoek Waterbeheer
 Postbus 2180
 3800 CD Amersfoort

UITVOERING EN RAPPORTAGE

A. Otte, Bioniers
D. Schellekens, Waterschap De Dommel

BEGELEIDINGSCOMMISSIE

K. Dieleman, Waterschap Vallei en Veluwe
A. Grent, Hoogheemraadschap Hollands Noorderkwartier
O. Kluiving, Waterschap Hunze en Aa's
I. Koller, Waterschap De Dommel
J. Koop, Waterschap Hunze en Aa's
D. Koot, Hoogheemraadschap Hollands Noorderkwartier
B. Roelfzema, Waterschap Zuiderzeeland
D. Roes, Waterschap Rijn en IJssel
A. Sengers, Hoogheemraadschap van Schieland en de Krimpenerwaard
C. Uijterlinde, STOWA
M. Verhoeven, Hoogheemraadschap De Stichtse Rijnlanden

DRUK Kruyt Grafisch Adviesbureau
STOWA STOWA 2017-45
ISBN 978.90.5773.772.5

COPYRIGHT Teksten en figuren uit dit rapport mogen alleen worden overgenomen met bronvermelding.
DISCLAIMER Deze uitgave is met de grootst mogelijke zorg samengesteld. Niettemin aanvaarden de auteurs en de uitgever geen enkele aansprakelijkheid voor mogelijke onjuistheden of eventuele gevolgen door toepassing van de inhoud van dit rapport.

TEN GELEIDE

Zuiverende kassen lijken een aantal voordelen te hebben boven conventionele actiefslib installaties. Echter belangrijke vragen blijven open die alleen met een of meer (pilot-)projecten beantwoord kunnen worden.

Op 23 maart 2014 zond de VPRO een Tegenlicht aflevering uit met de titel De kracht van water. In deze aflevering werd een “revolutionair” waterzuiveringssysteem getoond, waarbij communaal afvalwater werd gezuiverd in kassen. In de kassen zorgen planten, die met hun wortels in het water hangen, samen met de aan de wortels gehechte bacteriën en andere micro-organismen voor een efficiënte zuivering. Volgens de bedenker en leverancier van dit systeem, Organica, gevestigd in Hongarije, heeft een zuiverende kas vele voordelen ten opzichte van een conventionele rwzi. Als de claims van de leverancier kloppen, zou het systeem energiezuiniger en efficiënter zijn, minder slib produceren, minder plaats innemen en een (veel) kleinere geurcirkel hebben dan een conventionele rwzi. Na de Tegenlicht uitzending ontstond ook in Nederland bij de waterschappen interesse in dit systeem.

Waterbeheerders hebben echter meer (onafhankelijke) informatie nodig om de levensvatbaarheid van het concept voor Nederland in te kunnen schatten en wellicht pilots uit te kunnen voeren. Na een aantal bijeenkomsten van medewerkers van waterschappen uit Noord-Nederland werd besloten om een nadere verkenning van het concept te starten onder de vlag van STOWA.

In deze verkenning worden de achtergronden en de werking van de systemen van de twee Hongaarse leveranciers beschreven en vergeleken met conventionele actiefslib systemen. Hierbij is geprobeerd zoveel mogelijk onafhankelijke informatie te verzamelen, maar deze informatie bleek helaas beperkt. Door middel van ontwerpvragen aan de leveranciers is meer informatie boven water gehaald, waardoor een betere vergelijking met conventionele systemen mogelijk werd.

De systemen lijken een aantal voordelen te hebben boven conventionele actiefslib installaties. Papier is echter geduldig. Ook na deze verkenning blijven er vragen open die alleen met een of meer (pilot-)projecten beantwoord kunnen worden.

Joost Buntsma

Directeur STOWA

SAMENVATTING

Op 23 maart 2014 zond de VPRO een Tegenlicht aflevering uit met de titel De kracht van water. In deze aflevering werd een revolutionair waterzuiveringssysteem getoond, waarbij communaal afvalwater werd gezuiverd in kassen. In de kassen zorgen planten, die met hun wortels in het water hangen, samen met de aan de wortels gehechte bacteriën en andere micro-organismen voor een efficiënte zuivering. Volgens de bedenker en fabrikant van dit systeem, Organica, gevestigd in Hongarije, heeft een zuiverende kas vele voordelen ten opzichte van een conventionele rwzi. Bestaande zuiverende kassen in het buitenland voldoen aan de daar geldende effluentnormen en functioneren soms al vele jaren naar verwachting. Als de claims van de fabrikant kloppen, zou het systeem energiezuiniger en efficiënter zijn en bovendien minder plaats innemen dan een conventionele rwzi.

Na de Tegenlicht uitzending ontstond ook in Nederland bij de waterschappen interesse in dit systeem. Sommige geïnteresseerde waterschapsmedewerkers hebben zuiverende kassen in het buitenland bezocht.

Het idee van zuiverende kassen is niet nieuw. Al in de jaren 70 van de vorige eeuw legde John Todd in de VS de fundamenteen voor zijn zuiverende kassen, die hij Living Machines noemde. In Hongarije is sinds 1998 het bedrijf Organica actief. Dit bedrijf maakte oorspronkelijk conventionele waterzuiveringssystemen voor de Hongaarse markt. Het bedrijf ontwikkelde een nieuw systeem: een combinatie van een Fixed Film Activated Sludge systeem en een Living Machine. Het resultaat is sinds 2007 op de markt en werd door Organica de Food Chain Reactor genoemd. Een van de grondleggers van dit systeem begon een eigen bedrijf om dit systeem verder te ontwikkelen en dit bedrijf is actief onder de naam Biopolus.

Deze studie is opgezet om de werking van zuiverende kassen te verduidelijken en de claims van de fabrikanten te verifiëren. Er zal een vergelijking gemaakt worden tussen de zuiverende kassen van Organica en Biopolus en conventionele rwzi's. Een aantal bestaande installaties is onder de loep genomen. Om een goede vergelijking te kunnen maken en om te bekijken of de installaties ook aan de in Nederland geldende normen zouden kunnen voldoen, is de fabrikanten gevraagd om ontwerpen te maken voor twee bestaande situaties: rwzi Vriescheloo (10.000 I.E.) en rwzi Epe (50.000 I.E.). Aangezien beide rwzi's zijn onderbelast, zijn met de Ontwerp- en Terugrekentool van Tauw en de participerende waterschappen (OTW) nieuwe ontwerpen gemaakt voor deze rwzi's.

Zuiverende kassen lijken een visueel aantrekkelijk alternatief te zijn voor conventionele rwzi's, die serieuze aandacht verdienen in Nederland. Uit deze verkenning komt naar voren dat zuiverende kassen beter in de bebouwde omgeving of groene structuur eromheen passen dan conventionele rwzi's en goed te combineren zijn met sociale functies, zoals recreatie, horeca en educatie.

Uit de casestudies en ontwerpen die Organica en Biopolus hebben gemaakt voor twee rwzi's komen de volgende conclusies:

1. Zuiverende kassen nemen minder ruimte in beslag dan conventionele rwzi's.
2. Het is aan de hand van deze ontwerpen nog niet duidelijk of het systeem energiezuiniger is.

De systemen met chemische fosfaatverwijdering zijn dat wel, maar bij de systemen met biologische fosfaatverwijdering is er verschil in ontwerp en energieverbruik.

3. De slibproductie is in zuiverende kassen in het buitenland hoger dan die van actiefslib installaties in Nederland. Uit de ontwerpberekeningen van de fabrikanten en met OWT blijkt deze vergelijkbaar met of lager te zijn dan die van conventionele actiefslib installaties.
4. De constructiekosten voor zuiverende kassen zijn lager dan die voor een conventionele rwzi.
5. De jaarlijkse kosten van de chemische fosfaatverwijderingsinstallaties zijn hoger dan die van het conventionele ontwerp. Dit wordt hoofdzakelijk veroorzaakt door de kosten van metaalzouten. De Bio-P ontwerpen zijn bij het scenario Vriescheloo wel goedkoper in jaarlijks terugkerende kosten. In het scenario Epe is dit voor het ontwerp van Organica niet te zeggen, dit hoofdzakelijk door de keuze om methanol te doseren.

Zuiverende kassen hebben een aantal voordelen boven conventionele rwzi's. Het verdient dan ook de aanbeveling om een of meer zuiverende kassen in Nederland te realiseren om de werking onder Nederlandse omstandigheden goed in kaart te brengen en te bestuderen of de door de fabrikanten opgegeven eigenschappen en kosten daadwerkelijk zijn zoals in dit rapport weergegeven.

AFKORTINGEN

Bio-P	Biologische fosfaatverwijdering
Chem-P	Chemische fosfaatverwijdering
FCR	Food Chain Reactor
MBR	Membraan Bio-Reactor
MNR	Metabolic Network Reactor
OTW	Ontwerp- en terugrekentool van Tauw
RAS	Return Activated Sludge

DE STOWA IN HET KORT

STOWA is het kenniscentrum van de regionale waterbeheerders (veelal de waterschappen) in Nederland. STOWA ontwikkelt, vergaart, verspreidt en implementeert toegepaste kennis die de waterbeheerders nodig hebben om de opgaven waar zij in hun werk voor staan, goed uit te voeren. Deze kennis kan liggen op toegepast technisch, natuurwetenschappelijk, bestuurlijk-juridisch of sociaalwetenschappelijk gebied.

STOWA werkt in hoge mate vraaggestuurd. We inventariseren nauwgezet welke kennisvragen waterschappen hebben en zetten die vragen uit bij de juiste kennisleveranciers. Het initiatief daarvoor ligt veelal bij de kennisvragende waterbeheerders, maar soms ook bij kennisinstellingen en het bedrijfsleven. Dit tweerichtingsverkeer stimuleert vernieuwing en innovatie.

Vraaggestuurd werken betekent ook dat we zelf voortdurend op zoek zijn naar de ‘kennisvragen van morgen’ – de vragen die we graag op de agenda zetten nog voordat iemand ze gesteld heeft – om optimaal voorbereid te zijn op de toekomst.

STOWA ontzorgt de waterbeheerders. Wij nemen de aanbesteding en begeleiding van de gezamenlijke kennisprojecten op ons. Wij zorgen ervoor dat waterbeheerders verbonden blijven met deze projecten en er ook ‘eigenaar’ van zijn. Dit om te waarborgen dat de juiste kennisvragen worden beantwoord. De projecten worden begeleid door commissies waar regionale waterbeheerders zelf deel van uitmaken. De grote onderzoekslijnen worden per werkveld uitgezet en verantwoord door speciale programmacommissies. Ook hierin hebben de regionale waterbeheerders zitting.

STOWA verbindt niet alleen kennisvragers en kennisleveranciers, maar ook de regionale waterbeheerders onderling. Door de samenwerking van de waterbeheerders binnen STOWA zijn zij samen verantwoordelijk voor de programmering, zetten zij gezamenlijk de koers uit, worden meerdere waterschappen bij één en hetzelfde onderzoek betrokken en komen de resultaten sneller ten goede van alle waterschappen.

De grondbeginselen van STOWA zijn verwoord in onze missie:

Het samen met regionale waterbeheerders definiëren van hun kennisbehoeften op het gebied van het waterbeheer en het voor één met deze beheerders (laten) ontwikkelen, bijeenbrengen, beschikbaar maken, delen, verankeren en implementeren van de benodigde kennis.

VERKENNING ZUIVERENDE KASSEN

CONTENTS

TEN GELEIDE		
SAMENVATTING		
AFKORTINGEN		
DE STOWA IN HET KORT		
1	ACHTERGRONDEN	1
1.1	Zuiverende kassen	1
1.2	Focus van dit onderzoek	1
2	DE WERKING VAN ZUIVERENDE KASSEN	3
2.1	Ecological Engineering	3
2.2	Living Machines	5
2.3	Zuiverende kassen	6
2.3.1	Slib op plantenwortels	7
2.3.2	Minder restslib	10
2.3.3	Kleiner oppervlak	11
2.3.4	Belevingseffecten: geur en visueel	11
2.4	Operationele eigenschappen	12

3	BESTAANDE SYSTEMEN	15
3.1	Overzicht	15
3.2	Providence, Rhode Island	15
3.2.1	Zuiveringseigenschappen	15
3.3	Dierenpark Emmen	16
3.3.1	Zuiveringseigenschappen	17
3.3.2	Operationele eigenschappen	18
3.4	South Pest (Boedapest, Organica)	18
3.4.1	Zuiveringseigenschappen	20
3.4.2	Operationele eigenschappen	21
3.5	Etyek	21
3.5.1	Zuiveringseigenschappen	23
3.5.2	Operationele eigenschappen	23
3.6	Telki	24
3.6.1	Zuiveringseigenschappen	25
3.6.2	Operationele eigenschappen	26
3.7	Melbourne	26
3.7.1	Zuiveringseigenschappen	27
3.7.2	Operationele eigenschappen	27
3.8	Le Lude	28
3.8.1	Zuiveringseigenschappen	28
3.9	Living Machines	29
4	VERGELIJKING MET CONVENTIONELE SYSTEMEN	30
4.1	Ontwerpvaag	30
4.2	Resultaten	30
4.2.1	Vriescheloo	30
4.2.2	Vergelijkingen scenario Vriescheloo	35
4.2.3	Epe	40
4.2.4	Vergelijking scenario Epe	43
4.2.5	Discussie	46
4.2.6	Conclusie	47
4.3	Case: Strijp-S	48
4.3.1	Achtergrond	48
4.3.2	Vergelijking	49
4.3.3	Conclusies	49
5	CONCLUSIES	50
6	LITERATUUR	52
BIJLAGE 1	Vragenlijst	53
BIJLAGE 2	Ontwerpen Biopolus Vriescheloo	56
BIJLAGE 3	Ontwerpen Biopolus Epe	76
BIJLAGE 4	Ontwerpen Organica Vriescheloo	96
BIJLAGE 5	Ontwerpen Organica Epe	131

1

ACHTERGRONDEN

Op 23 maart 2014 zond de VPRO een Tegenlicht aflevering uit met de titel *De kracht van water*. In deze aflevering werd een revolutionair waterzuiveringssysteem getoond, waarbij communaal afvalwater werd gezuiverd in kassen. In de kassen zorgen planten, die met hun wortels in het water hangen, samen met de aan de wortels gehechte bacteriën voor een efficiënte zuivering. Volgens de bedenker en fabrikant van dit systeem, Organica, gevestigd in Hongarije, heeft een zuiverende kas vele voordelen ten opzichte van een conventionele rwzi.

Na de Tegenlicht uitzending ontstond ook in Nederland bij de waterschappen interesse in dit systeem. Sommige geïnteresseerde waterschapsmedewerkers hebben zuiverende kassen in het buitenland bezocht. Door hun bezoeken en enthousiaste verhalen groeide de belangstelling. Als de claims van de fabrikant kloppen, zou het systeem energiezuiniger en efficiënter zijn en bovendien minder plaats innemen dan een conventionele rwzi.

1.1 ZUIVERENDE KASSEN

Het idee van zuiverende kassen is niet nieuw. Al in de jaren 70 van de vorige eeuw legde John Todd in de VS de fundamenten voor zijn zuiverende kassen, die hij *Living Machines* noemde. Zijn idee was om een compleet ecosysteem in compartimenten te bouwen dat in staat is om afvalwater te zuiveren. Het water doorloopt verschillende compartimenten met elk een eigen ecosysteem. Door de veelheid aan organismen ontstaat een robuust en efficiënt systeem. Todd heeft met zijn bedrijf Ocean Arks ondertussen vele Living Machines gebouwd. Deze staan voornamelijk in de VS.

In Hongarije is sinds 1998 het bedrijf Organica actief. Dit bedrijf maakte oorspronkelijk conventionele waterzuiveringssystemen voor de Hongaarse markt. De R&D-afdeling van het bedrijf kwam in de loop van de tijd met een nieuw systeem: een combinatie van een *Fixed Film Activated Sludge* systeem en een *Living Machine*. Het resultaat is sinds 2007 op de markt en werd door Organica de *Food Chain Reactor* genoemd. Het bedrijf opereert internationaal en heeft tientallen installaties gerealiseerd in Europa en Azië.

Een van de R&D mensen en grondleggers van het systeem, István Kenyeres heeft Organica verlaten en heeft zijn bedrijf Biopolus opgericht. Biopolus heeft als doel het systeem verder te ontwikkelen en daarnaast te focussen op het creëren van nieuwe grondstoffen uit afvalwater in de door hun zo genoemde *metabolic network reactor*, die deel uitmaakt van zogenaamde *Biomakeries*. En zo zijn er nu twee Hongaarse bedrijven die vergelijkbare systemen produceren.

1.2 FOCUS VAN DIT ONDERZOEK

Voordat waterschappen de nieuwe technologie omarmen, dienen er vele vragen beantwoord te worden. Hierbij dienen zij af te gaan op harde data en dient er een verdere onderbouwing plaats te vinden.

Er is een vragenlijst opgesteld voor de fabrikanten (zie Bijlage 1). Hierbij ligt de nadruk op het verkrijgen van ruwe meetgegevens van bestaande systemen, zodat de werking geverifieerd en geanalyseerd kan worden. Met de verkregen data kunnen de werking, de kosten en de baten van zuiverende kassen vergeleken worden met conventionele technieken.

Hierbij gaat het niet alleen om gegevens over het functioneren van het systeem, maar ook om ‘randzaken’, zoals voor- en nabehandeling, slibproductie, benodigde menskracht, kosten en baten. Er moet een beeld gevormd worden of zuiverende kassen een volwaardig of beter alternatief zijn voor conventionele actief slib rwzi’s. De sterke en zwakke punten moeten duidelijk worden.

Tijdens de loop van het onderzoek werd duidelijk dat onafhankelijke meetgegevens van zuiverende kassen niet vorhanden zijn. Nagenoeg alle informatie in deze rapportage is derhalve afkomstig van de fabrikanten van zuiverende kassen. Hierdoor is het lastig om een objectief beeld te krijgen van de voor- en nadelen van zuiverende kassen. Dit is deels ondervangen door de fabrikanten ontwerpen te laten maken voor twee bestaande rwzi’s en de resultaten van deze ontwerpen te vergelijken met ontwerpen van conventionele rwzi’s. Vervolgens zijn aan de hand van de uitkomsten van deze ontwerpen nadere vragen gesteld aan de fabrikanten over hun ontwerpen om meer inzicht te krijgen in hun ontwerpproces en de parameters waarmee zij rekenen. Houd bij het lezen van dit rapport dus rekening met de beperkte objectiviteit van de gepresenteerde gegevens.

2

DE WERKING VAN ZUIVERENDE KASSEN

2.1 ECOLOGICAL ENGINEERING

John Todd en zijn vrouw Nancy mogen gezien worden als de grondleggers van de Living Machines. Todd bouwde voort op het werk van H.T. Odum, de grondlegger van *Ecological Engineering* ([9]). Living Machines zijn door de mens ontworpen ecosystemen die een of meerdere taken verrichten ten nutte van de mens. Voorbeelden hiervan zijn voedselproductie, klimaatregulatie, afvalverwerking en waterzuivering ([10]). De brede term *Living Machine* heeft dus niet slechts betrekking op een systeem dat water zuivert.

Living Machines zijn zorgvuldig ontworpen ecosystemen die gevoed worden door zonlicht. Een mix van zeer veel micro-organismen, kleine en grote dieren, algen, schimmels en hogere planten zorgt voor een stabiel, veerkrachtig systeem. Welke organismen deel uitmaken van het systeem, hangt sterk af van de taak waarvoor het systeem is ontworpen. Het idee van Ecological Engineering is dat de ontwerper een afgebakend ecosysteem ontwerpt, soorten daarin introduceert en dat de natuur de rest doet.

In 1987 ontwierp Todd zijn eerste waterzuiveringssysteem. Het was het eerste systeem ooit dat gebruik maakte van hogere aquatische organismen in combinatie met bacteriën. Het bestond uit een serie geschakelde mini-ecosystemen in beluchte, transparante cilinders en ondiepe open bakken dat huishoudelijk afvalwater na een septic tank behandelde. Met een hydraulische verblijftijd van 10 dagen was 99% van het ammonium en fosfaat verwijderd uit het afvalwater, maar ook metalen, vetten en oliën en fecale coliformen.

Gesterkt door de eerste resultaten ontwikkelde Todd zijn systeem verder zodat verschillende typen afvalwater behandeld kunnen worden. Todd definieerde 12 principes waaraan een ecologisch systeem voor afvalverwerking moet voldoen wil deze succesvol zijn:

1. Diversiteit aan mineralen. Elk ecosysteem dat floreert begint bij een basis van diversiteit aan anorganische componenten. Alle belangrijke elementen en sporenelementen dienen aanwezig te zijn.
2. Aanwezigheid van nutriëntreservoirs. Voor de succesvolle ontwikkeling van een diversiteit aan organismen dienen nutriënten in de juiste hoeveelheid en verhoudingen aanwezig te zijn.
3. Steile gradiënten (in concentraties). Scherpe overgangen in concentraties van nutriënten, zuurstof en organische componenten, in redox potentiaal, pH en temperatuur zorgen voor een ecologische diversiteit die een robuust systeem garanderen.
4. Hoge uitwisselingssnelheden. Een van de belangrijkste ontwerpcriteria is het vergroten van het contactoppervlak tussen levende organismen en te zuiveren afvalstroom. Dit vergroot de mogelijkheid tot uitwisseling van stoffen tussen levende biomassa en afvalstroom.
5. Periodieke en willekeurige veranderingen. Door regelmatig voorspelbare en onvoorspelbare plotselinge veranderingen in de omgeving door te voeren, “leert” het ecosysteem te reageren

op onverwachte gebeurtenissen. Het ecosysteem stelt zich in op deze veranderingen en wordt hierdoor robuuster bij plotselinge veranderingen in aanvoer van stoffen, concentraties, temperatuurschokken en dergelijke die ongetwijfeld een keer optreden, bijvoorbeeld door uitval van een pomp of onvoorzien temperatuurveranderingen.

6. Cellulair ontwerp. Net als bij een levend organisme, die uit (gespecialiseerde) cellen bestaat, worden ecologische systemen zodanig ontworpen dat elk onderdeel een gespecialiseerde taak uitvoert binnen het geheel. Dit maakt het systeem robuust en uit te breiden.
7. Minimalisatie van het aantal subsystemen (compartimenten). Todd heeft verschillende systemen uitgetest en ondervonden dat minimaal drie subsystemen nodig zijn in succesvolle living machines voor afvalwaterbehandeling. Systemen met een of twee subsystemen werden instabiel. Afhankelijk van de taak van het systeem dient per keer het optimale aantal worden bepaald.
8. Microbiologische gemeenschappen. Het is duidelijk dat microbiologische gemeenschappen de kern vormen van veel ecologische systemen om afvalstoffen af te breken. Een hoge diversiteit in bacteriën is nodig. Deze diversiteit zorgt ervoor dat sterke schommelingen in de omgeving (waaronder het substraat waarin de bacteriën groeien) opgevangen kunnen worden en de organismen kunnen overleven. Behalve bacteriën gaat het ook om diversiteit aan andere organismen, zoals algen, schimmels en protozoa.
9. Fotosynthetische basis. Ecologische systemen draaien op zonlicht. Algen en planten vormen de basis van elk ecosysteem. In kunstmatig gecreëerde ecosystemen is dat niet anders. Zij zorgen voor het creëren van geschikte habitats voor andere organismen, maar ook voor de vorming van essentiële stoffen zoals enzymen en vitamines waardoor andere organismen kunnen overleven.
10. Diversiteit in dierlijke organismen. Dierlijke organismen zijn essentieel in de ogen van Todd voor de werking van Living Machines. Slakken zijn bijvoorbeeld zeer nuttig voor de reductie van slib, maar ook als indicatororganisme. Als de omstandigheden in het afvalwater snel veranderen, bijvoorbeeld door toevoer van毒ische stoffen, kruipen de slakken het water uit. Mosselen zijn onmisbaar voor het filteren van deeltjes uit het water, evenals zoöplankton, rotiferen en insectenlarven. Deze dieren filteren deeltjes van 0,5 tot 50 µm uit het water met een verwijderingsrendement van 99,5%. Vissen, vooral algeneters en detrituseters spelen eveneens een belangrijke rol. Ook zij filteren dagelijks veel water. *Tilapia* wordt gebruikt om de hoeveelheid eendenkroos en ondergedoken waterplanten binnen de perken te houden. *Pimephales promelas* (Amerikaanse dikkopelrits) wordt gebruikt voor het verwijderen van rotte plantendelen. Deze wordt verkocht als aasvis voor de sportvisserij¹.
11. Connecties tussen subsystemen en natuurlijke systemen voor uitwisseling van organismen. Het is belangrijk om de soortenrijkdom op peil te houden. Soms neemt deze af door onvoorzien omstandigheden. Soorten moeten dan terug worden geïntroduceerd. Open connecties tussen subsystemen en het natuurlijke systeem (bijvoorbeeld een eutroof watersysteem buiten de Living Machine), zorgen voor herintroductie van verdwenen soorten en voor vluchtplaatsen voor soorten als de omstandigheden in de Living Machine ongunstig worden.
12. Mikrokosmos, mesokosmos en makrokosmos relaties. Todd stelt dat de aarde als geheel, het meest complete levende systeem dat we kennen, de basis moet zijn voor ecologisch ontwerp. Soortenrijkdom, relaties tussen soorten en tussen soorten en de omgeving, verhoudingen tussen land en water, tussen verschillende typen organismen en tussen concentraties van stoffen die in de natuur voorkomen geven goede handvatten voor het ontwerpen van stabiele, robuuste ecologische systemen.

Zie voor een uitgebreidere beschrijving de literatuurbronnen [9] en [10].


¹ Levend aas is in Nederland niet toegestaan.

2.2 LIVING MACHINES

De Living Machine van Providence, Rhode Island in de VS wordt hier als voorbeeld getoond voor hoe Living Machines eruitzien. Deze Living Machine verwerkt maximaal 61 m^3 huishoudelijk afvalwater per dag (gemiddeld $34\text{ m}^3/\text{d}$) en is operationeel sinds 1989. In Figuur 1 is een schematische weergave gegeven van deze installatie. De installatie ligt op het terrein van de conventionele rioolwaterzuiveringsinstallatie die 150.000 m^3 huishoudelijk afvalwater per dag verwerkt. De Living Machine staat in een kas met een oppervlak van 380 m^2 . De hydraulische verblijftijd van het water in het systeem varieert van 2,5 tot 4,5 dag.

FIGUUR 1

SCHETS VAN DE LIVING MACHINE VAN PROVIDENCE, RHODE ISLAND, VS VAN JOHN TODD ([9])



Het rioolwater wordt eerst grof gefilterd. In de eerste kamer van de kas staan vier rijen van zes doorschijnende tanks. Deze rijen zijn in serie geschakeld. Zij zijn $1,83\text{ m}^2$ in diameter en $1,98\text{ m}$ hoog. Het watervolume in elke tank is $4,54\text{ m}^3$. De tanks zijn voorzien van rijke gemeenschappen van micro-organismen en algen en bovenop drijven waterhyacinthen. De eerste vijf tanks in elke rij worden gemengd en belucht met beluchters die fijne bellen afgeven. De zesde tank wordt niet belucht en functioneert als bezinktank. De bezonken delen uit de zesde tank gaan terug naar de eerste tank.

Het water uit de zesde tanks gaat naar een serie kunstmatige getijdenmoerassen. Deze zijn $0,91\text{ m}$ breed, $2,44\text{ m}$ lang en $0,46\text{ m}$ diep. Zij zijn gevuld met kiezels en beplant met moerasplanten, voornamelijk met *Scirpus* soorten, zoals grote lisododde. Gedurende 12 uur wordt een moeras gevuld met water, waarna het water naar een ander moeras wordt geleid zodat de eerste kan leeglopen. Dit simuleert de nat/droog cyclus van een getijdemoeras.

Na de moerassen wordt het water naar een volgende serie doorschijnende tanks gepompt. Deze zijn voorzien van verschillende soorten op drijvers geplante moerasplanten. Dit zijn tropische en gematigde soorten. In deze tanks zitten dieren zoals vissen uit de karperfamilie (*Cyprinidae*), zoöplankton, slakken en zoetwatermosselen.

Vervolgens gaat het water naar een biofilter. Dit filter bestaat uit een doorschijnende tank

van 0,76 m doorsnee gevuld met een gerecycled plastic drijvend materiaal (niet verder gespecificeerd).

Tenslotte gaat het water naar een laatste moeras bestaande uit een bak gevuld met kiezels en beplant met verschillende soorten tropische en gematigde moerasplanten soorten.

In paragraaf 3.2 worden de zuiveringseigenschappen van dit systeem besproken.


Het systeem heeft geen anaerobe compartimenten voor denitrificatie. In latere systemen heeft Todd deze wel toegevoegd in moerassubsystemen en *fluidized beds*.

2.3 ZUIVERENDE KASSEN

Food Chain Reactors van Organica en *Metabolic Network Reactors* van Biopolus zijn sterk geënt op Living Machines. De grondleggers van Organica, Attila Bodnar en István Kenyeres (die later Biopolus heeft opgericht) hebben samengewerkt met John Todd en het systeem naar hun inzichten gewijzigd zodat het efficiënter werkt. Een van de belangrijkste wijzigingen is het toevoegen van speciale, gepatenteerde vezels die naast de plantenwortels in het water hangen en deze deels simuleren. Hieraan hecht zich actief slib, zodat het systeem een hybride tussen een slib op dragersysteem en een Living Machine is geworden. Er wordt gebruik gemaakt van een combinatie van doeken en plantenwortels, omdat een systeem met alleen plantenwortels snel zou dichtgroeien en de doorstroming belemmerd zou worden. Bovendien groeien de meeste plantenwortels niet dieper dan 2 meter en kunstmatige wortels kunnen dieper komen. Een systeem met alleen plantenwortels zou veel meer onderhoud vergen en een groter oppervlak vragen. Een schematische weergave van het systeem is te zien in Figuur 2.

FIGUUR 2

SCHEMATISCHE WEERGAVE VAN EEN FOOD CHAIN REACTOR



Een FCR bestaat uit opeenvolgende modules met verschillende beluchtingsregimes en organismen. Organica en Biopolus hebben onderzocht dat in hun concepten meer dan 3000 soorten organismen voorkomen in het systeem en dat er 8 tot 12 kg biomassa per m³ water aanwezig is. Behalve bacteriën bestaat de biomassa uit planten, protozoa, wormen, mosselen, slakken, arthropoden en vissen.

Volgens Organica sturen enzymen die de plantenwortels uitscheiden de samenstelling van de bacteriepopulatie. De plantenwortels sturen hiermee ook de bacteriepopulatie op de doeken en zorgen voor een robuust en efficiënt systeem.


De installaties worden ontworpen voor de verwijdering van organisch materiaal en soms ook specifiek voor het behalen van strenge nutriëntennormen. In de aerobe reactors treedt

nitrificatie op, gevolgd door denitrificatie door nogmaals een anoxische stap te doorlopen. Fosfaatverwijdering treedt op door sedimentatie en opname door organismen. Dit is echter niet veel in vergelijking met biologische fosfaatverwijdering zoals deze bij rwzi's plaats vindt. Daar vindt biologische fosfaatverwijdering plaats doordat bacteriën eerst in de anaerobe fase veel vetzuren opnemen en in de aerobe fase zich vervolgens fosfaat opslaan. Omdat FCR's weinig gesuspendeerde bacteriën en veel aangehechte bacteriën bevatten, vindt dit proces niet of nauwelijks plaats. De installaties kunnen wel ontworpen worden voor biologische fosfaat verwijdering maar dan is er sprake van een hybride systeem met actief slib en slib op drager. De door de fabrikanten aanbevolen methode voor fosfaatverwijdering is precipitatie met metalen. In de installatie van South Pest in Boedapest (Hongarije) is een Biofor systeem nageschakeld om stikstof en fosfaat te verwijderen. De FCR wordt voornamelijk gebruikt voor de verwijdering van organische stof.

2.3.1 SLIB OP PLANTENWORTELS

Een plantenwortel heeft een typische structuur. Het gedeelte van de plant dat onder de grond zit is net zo groot of soms groter dan de structuur boven de grond. In een waterige omgeving is om deze wortels en wortelhaartjes veel ruimte voor de aangroei van biofilm. Een kubieke meter reactorvolume met wortels biedt een biofilm oppervlak van 12.000 m². De wortels zijn echter wel beperkt in lengte en worden maximaal 1,5 tot 2 meter lang. De reactoren zijn onder andere om deze reden uitgerust met modules met kunstmatige wortels. Deze modulaire constructie is zo ontworpen dat de kunstwortels niet over elkaar heen schuren, een effect dat ervoor kan zorgen dat er te veel biomassa afschraapt ([11]).

FIGUUR 3 TWEE TYPEN KUNSTWORTEL (LINKS BIOPOLUS, RECHTS ORGANICA)




De hoeveelheid dragermateriaal neemt toe per opeenvolgende reactor. In de eerste reactoren is er veel voedsel aanwezig en groeit de biofilm snel en is daarom minder dragermateriaal

nodig. In de latere reactoren is meer dragermateriaal benodigd om te compenseren voor de trager groeiende micro-organismen waaronder de autotrofen verantwoordelijk voor nitrificatie ([1]).

Het gebruik van uitsluitend kunstmatige dragermateriaal is in feite voldoende voor de kerntaken van een afvalwaterzuivering. Bij opstart zijn de wortels nog onvoldoende volgroeid om voldoende biomassa te kunnen dragen. Toch hebben de planten een belangrijke meerwaarde. De biodiversiteit in de biofilm op de plantenwortel is groter dan op de kunstwortels. Een slab op drager systeem met alleen kunstwortels heeft een hogere biodiversiteit dan een actief slab systeem. Plantenwortels zorgen voor een nog hogere biodiversiteit.

FIGUUR 4 SCHEMATISCHE WEERGAVE VAN DE PLANT EN DE INVLOED OP BACTERIEPOPULATIES (SCHIMMELS EN OVERIGE MICRO-ORGANISMEN ZIJN HIER NIET WEEERGEVEN)



De plant heeft namelijk de mogelijkheid om de condities in de wortel (endosfeer), op het worteloppervlak en de biofilm daar dicht op (rhizosfeer) te beïnvloeden. De zuurgraad kan bijvoorbeeld hiertussen met een factor pH 2 verschillen door excretie van organische zuren,

bicarbonaten, protonen en CO₂. De organische zuren zijn daarnaast ook voeding voor bepaalde soorten micro-organismen. Ook zorgt de plant ervoor dat de omstandigheden altijd micro-aeroob zijn in en rondom de wortels doordat zuurstof (vanuit de lucht via de bladeren en stengels) hier naartoe transporteert. Het belang van de plant voor een gezonde diverse biofilm is bescherming tegen ziekteverwekkers en optimale opname van nutriënten ([1]).

De toegevoegde waarde van deze biodiversiteit voor het zuiveringsproces is processtabiliteit. Het systeem is beter bestand tegen schommelingen in belasting en toxicische componenten. Het laat ook de ontwikkeling toe van micro-organismen die potentie hebben om complexere microverontreinigingen af te breken. In een onderzoek gericht op enkele medicijnresten (Ibuprofen, Naproxen, Diclofenac) is een hogere verwijdering aangetoond dan bij een conventioneel actief slib systeem ([7]). Nader onderzoek is nodig om deze verwijdering te bevestigen en uit te breiden met meer microverontreinigingen.

Aangezien de slibdichtheid in een FCR hoger is dan in een gesuspendeerd actief slib systeem, wordt vaak ten onrechte verwacht dat er meer restslib ontstaat. Restslib dat na bezinking verder moet worden ingedikt, vervolgens grotendeels ontwaterd en daarna verbrand of gecomposeerd. Aan dit proces zijn hoge kosten verbonden zijn. Daarnaast is de verwachting dat meer biomassa ook een hoger zuurstofverbruik betekent en daarmee een hoger verbruik van beluchtingsenergie. Dit is volgens de fabrikanten echter niet het geval.

De biofilm die groeit op het dragermateriaal is vrij dik. De biofilm is 25 tot 30 mm dik, terwijl deze op alternatieve slibdragers 0,3 tot 0,5 mm dik is. Dit is duidelijk te zien wanneer het begroeide dragermateriaal uit de reactor is gehaald (zie Figuur 5). Wanneer het dragermateriaal is ondergedompeld is te zien dat het een heel juist een zeer losse structuur heeft met veel ruimte hiertussen voor interactie met luchtbellen.

FIGUUR 5

BIOFILM OP DRAGER. LINKS BUITEN DE REACTOR , RECHTS IN WATER




De zuurstof inbreng capaciteit wordt hoger naar mate er zich minder deeltjes in de waterfase bevinden. Bij actief slib systemen met hoge slibconcentraties zoals een MBR-systeem is 10 tot 12 g ds/l aan biomassa aanwezig en dit heeft invloed op de zuurstof inbreng capaciteit. De alfafactor is hier veel lager (0,3 tot 0,4). Bij de vast bed bioreactorsystemen is de biofilm

gebonden en de ruimte rondom bevat enkel deeltjes van het influent en materiaal dat vervelt. De concentratie onopgeloste bestandsdelen is in dit geval dan ongeveer 200 – 400 mg ds/l. Dit heeft als effect dat het verschil tussen schoon en vervuild water kleiner is en de alfafactor in de ordegrootte zit van 0,85 tot 0,9 ([5]).

2.3.2 MINDER RESTSLIB

Een effect dat optreedt bij slib op drager systemen is dat de verblijftijd van de biomassa hoger is. Dit betekent dat in dit systeem micro-organismen kunnen groeien en zich handhaven die in conventionele systemen niet voorkomen. Dit biedt niet alleen een hogere diversiteit aan bacteriesoorten maar ook een hogere diversiteit aan predatoren. Naast bacteriën, die de grootste groep micro-organismen zijn in actief slib, zijn ook micro-organismen aanwezig die in het verleden ingedeeld werden tot het rijk van de protozoa. Dit is een diverse groep die bacteriën als voedsel gebruikt. Vervolgens vallen zij zelf weer ten prooi aan elkaar en meercellige micro-organismen (metazoa). Deze organismen zijn in conventionele systemen wel aanwezig, maar zijn veelal niet een substantiële factor.

FIGUUR 6 DE BIOFILM EN PREDATOREN



In slib op drager systemen zijn meercellige organismen veelvuldig aanwezig. Ook zijn er macro-organismen, die in actief slib systemen veelal niet voorkomen, zoals watervlooien, kevers, wormen en slakken aanwezig, die zich voeden met het slib. In andere biofilm systemen versturen ze het zuiveringsproces doordat ze de biomassa sneller eten dan dat het kan groeien en dit ten koste gaat van de BZV-verwijdering, nitrificatie en denitrificatie.


In FCR-bioreactoren is dit mede door de opzet van meerdere opvolgende reactoren veel meer in balans. In de eerste reactoren is nog enige zuurstof aanwezig en groeit de bacteriebiomassa sneller dan de biomassa van predatoren. De hoeveelheid protozoa, metazoa en macro-organismen neemt toe per reactor. Dit komt doordat het eenvoudige voedsel steeds schaarser wordt en enkel complexer voedsel (bacteriebiomassa – protozoa) overblijft. Dit bevordert de groei van organismen die hierop aangepast zijn. Dit resulteert in een afname van restslib dat de reactoren verlaat. Deze reductie kan oplopen tot wel 30% minder slib ([1], [11]) ten opzichte van een conventionele actiefslib installatie.

2.3.3 KLEINER OPPERVLAK

Het kleinere benodigde oppervlak voor de afvalwaterzuivering komt hoofdzakelijk door een grotere hoeveelheid biomassa in een bepaalde hoeveelheid reactorvolume. De biomassa blijft ook grotendeels in de reactor.

FIGUUR 7

AFNAME ONOPGELOSTE BESTANDSDELEN (TSS) EN SLIB PRODUCTIE PER REACTOR ([7])



In Figuur 7 is te zien dat de hoeveelheid onopgeloste bestandsdelen (TSS; Total suspended solids) afneemt in de serie reactoren. De concentratie aan onopgeloste bestandsdelen in de reactor is 200 tot 300 mg/l in plaats van 3 tot 5 g/l bij actief slib systemen.

Bij een conventioneel actief slib systeem wordt meestal een nabezinktank gebruikt voor het scheiden van het slib van het gezuiverde water. Een RWZI is vrijwel altijd uitgerust met 1 of meerdere ronde nabezink tanks. De diameter van deze tanks varieert tussen de 20 en 60 meter (314 tot 2.827 m²).


Met de lagere concentraties in FCR-systemen is het mogelijk om alternatieve scheidings-technieken te gebruiken die niet berusten op bezinking maar op bijvoorbeeld filtratie of flotatie. Deze installaties nemen veel minder ruimte in beslag ([7]).

2.3.4 BELEVINGSEFFECTEN: GEUR EN VISUEEL

Rioolwaterzuiveringsinstallaties liggen in de praktijk ver buiten bewoond gebied en verborgen achter groen, omdat rwzi's een industrieel uiterlijk hebben en geuremissies veroorzaken. Vaak werden zij aangelegd op de plek waar het gemeentelijke riool in het oppervlaktewater uit kwam.

Geurontwikkeling op een rwzi verhindert het ondernemen van activiteiten zoals wonen en werken in de nabije omgeving. Bepaalde procesonderdelen zijn standaard voorzien van luchtbehandeling maar dit sluit niet uit dat er geur vrij komt. Gecombineerd met het grote oppervlak van een rwzi en een optelling van deze factoren is het mogelijk deze geuremissie in te schatten en te visualiseren op een kaart (Figuur 8). Bij een zuiverende kas zou, volgens de fabrikanten, buiten de kassen geen geur waarneembaar moeten zijn.

FIGUUR 8

VOORBEELD VAN GEURCIRKELS BIJ RWZI EINDHOVEN. GEUREMISSIE: GROEN 1 GE/M³, GEEL 2 GE/M³, ORANJE 3 GE/M³, ROOD 7 GE/M³

Ook een psychologische factor speelt mee. Anders gezegd: zien doet ruiken. Mensen verwachten stank bij een rwzi, ondanks alle geurmaatregelen. Mensen zijn extra alert op iedere geurafwijking en ruiken, zelfs indien dit niet terecht is, de rwzi sneller.

Zuiverende kassen behandelen op nagenoeg dezelfde wijze de geur als conventionele systemen. De anoxische reactoren zijn bedekt met de constructies waarin de planten zich bevinden. Het poreuze materiaal dat zich naast de plant hierin bevindt, dient als filter. Hierin groeien micro-organismen die de lucht zuiveren. Ook de planten zelf hebben een luchtzuiverende en geurverwijderende rol. Het groene uiterlijk van de installatie verlaagt de psychologische geurfactor. Ook bij het betreden van het biologische deel van de installatie blijft de associatie positief. Wat hier zichtbaar is, is een weelderige groei van planten. De lagere geuruitstoot en het groene uiterlijk van de installatie maken het mogelijk om op zeer dichte afstand van de afvalwaterzuivering te wonen, werken en zelfs te recreëren.

2.4 OPERATIONELE EIGENSCHAPPEN

In de volgende paragrafen komen de reacties op de vragenlijst aan de orde. Deze vragenlijst is beantwoord door Organica (Biopolis had op het moment van enqueteren nog geen installaties gebouwd). De hier gegeven informatie is dus afkomstig van een van de fabrikanten van zuiverende kassen. Zuiveringsrendementen en eigenschappen van bestaande systemen komen aan de orde in hoofdstuk 3. In de vergelijking van ontwerpen (hoofdstuk 4) komt aan de orde in hoeverre de uitspraken in deze paragraaf tot uitdrukking komen.

CAPACITEIT

Zuiverende kassen zijn geschikt voor afvalwaterstromen vanaf 500 i.e., maar relatief goedkoper bij grotere afvalwaterstromen. Door de modulaire opbouw kan gemakkelijk worden opgeschaald.

FLUCTUATIES IN DEBIET

Fluctuerende debieten zijn voor FCR-systemen geen probleem. Omdat het actief slib voornamelijk is aangehecht aan plantenwortels en doeken, wordt het slib minder uitgespoeld bij plotselinge hoge debieten. Zuiveringsrendementen kunnen omlaaggaan door verkorting van de hydraulische verblijftijd.

COMBINATIE COMMUNAAL MET INDUSTRIEEL WATER

Standaard FCR-systemen worden ontworpen voor de behandeling van communaal afvalwater, maar het is zeker mogelijk om het systeem te ontwerpen op een mengsel van communaal met industrieel afvalwater. Organica heeft ervaring met een mengsel van communaal afvalwater met afvalwater uit een pluimveeslachterij (Gallicoop Inc., Szarvas, Hongarije).

SLIBDICHTHEID

In Organica systemen is typisch 7 tot 12 kg slib per m³ water aanwezig, waarvan het merendeel gehecht aan wortels en doeken.

SLIBPRODUCTIE

Volgens de fabrikanten produceren de systemen produceren 0,6 tot 0,9 kg slib (droge stof) per kg verwijderd BZV, maar zoals uit hoofdstuk 3 blijkt, ligt dit in de praktijk hoger.

SLIBSCHEIDING EN -DROGING

Het slib wordt van het water gescheiden door een nabezinktank of door een isodisk. Het slib kan ingedikt en ontwaterd worden met elke wenselijke techniek.

ONDERHOUD PLANTEN

Planten worden eens per twee weken gesnoeid. Het afgeknipte plantenmateriaal wordt ter plekke gecomposteerd of toegevoegd aan een aanwezige vergistingsinstallatie. Sommige planten die commercieel aantrekkelijk verkocht kunnen worden, worden geoogst wanneer dat kan en hoe vaak dat gebeurt, hangt af van de soort.

PERSONEEL

In de meeste installaties zijn in totaal 3 operators. Telkens zijn er twee tegelijkertijd aanwezig. In het weekend is er niemand aanwezig maar worden de operators per SMS-bericht bij problemen. Dit geldt met name voor de Franse installaties. In dat land is het verplicht om altijd operators aanwezig te hebben. In Nederland wordt vaker gewerkt met operators op afstand.

GEUR EN LUCHTBEHANDELING

Voorbehandeling en slibverwerking gebeurt in gesloten ruimten met ventilatie. De lucht in deze ruimten wordt gefilterd met een luchtwassysteem alvorens naar buiten te worden afgevoerd.

In een studie naar de verwijdering van geur door planten, bleek dat de planten een verwijderingsrendement van 54% voor geuractieve stoffen ([1]) hadden. De geursterkte werd verlaagd

van 26 OU²/m³ naar 12 OU/m³. Dit betekent een lage, maar wel detecteerbare geurconcentratie.

Gevaarlijke stoffen of bacteriën komen niet in schadelijke hoeveelheden voor in de lucht in de kassen. Het is veilig om, zeker na de eerste (anaerobe en anoxische) stappen van de zuivering, de kas open te stellen voor publiek.

NABEHANDELING

Elke gewenste nabehandeling kan worden toegepast. Op sommige locaties vindt een geschakelde nutriëntenverwijdering en/of ontsmettingsstap plaats. Ontsmetting gebeurt meestal met UV.

HERGEBRUIK VAN WATER

Bij de bestaande installaties van Organica wordt het water meestal niet hergebruikt. Bij de meeste installaties wordt het effluent geloosd op een oppervlaktewater. De installaties kunnen echter ontworpen worden op elk gewenst type hergebruik. Zeker bij lokale, kleinschaliger zuivering ziet Organica mogelijkheden voor hergebruik van water.

HERGEBRUIK VAN STOFFEN

Door planten en dieren (siervissen) te kiezen met marktwaarde, kan een zuiverende kasgeld opleveren, maar het is te betwijfelen of dit veel geld zal opleveren en of de inkomsten ook maar in de buurt komen van de operationele kosten van de installatie. Planten met een nuttige inhoudsstof, zoals eiwitten, zetmeel en etherische oliën komen hiervoor in aanmerking. Ook sierplanten kunnen in de kas worden gekweekt. Minder nuttige planten kunnen worden gecomposeerd en zo bijdragen aan een gezondere bodem en hergebruik van nutriënten. Mogelijk zal deze route een optie worden in de toekomst. Vooralsnog is er geen zicht op een positieve businesscase.

LOKALE WERKGELEGENHEID

Werkgelegenheid kan bestaan uit het kweken en vermarkten van planten met een nuttige inhoudsstof of ornamentale planten en bloemen. Ook het verzorgen van rondleidingen en educatieve uitstapjes kan voor werkgelegenheid zorgen.

2 Europese geureenhed, gemeten volgens CEN EN 13725:2003. 1 OU/m³ betekent per definitie dat 50% van de proefpersonen de geur detecteert en 50% niet. Een concentratie van 10 OU/m³ betekent dat het monster 10 keer verduld moet worden om de 1 OU/m³ waarde te bereiken.

3

BESTAANDE SYSTEMEN

3.1 OVERZICHT

In onderstaand overzicht is te zien van welke systemen er informatie is verkregen die in deze rapportage is verwerkt.

TABEL 1 OVERZICHT SYSTEMEN

Naam	Type	Capaciteit (m³/d)	Jaar ingebruikname
Providence, Rhode Island (USA)	Living Machine	61	1989
Dierenpark Emmen (Nederland)	Living Machine	700	2002
South Pest (Organica, Hongarije)	FCR	80.000	2012
Etyek (Organica, Hongarije)	FCR	1.000	2007
Telki (Organica, Hongarije)	FCR	800	2005
Le Lude (Organica, Frankrijk)	FCR	815	2010
Melbourne pilot (Organica, Australië)	FCR	85	2015

In volgende paragrafen wordt elk systeem kort belicht.

3.2 PROVIDENCE, RHODE ISLAND

Het systeem van Providence, Rhode island is ontworpen en aangelegd door John Todd. Enkele eigenschappen van het systeem worden al gegeven in paragraaf 2.2.

In de periode van september 1992 tot en met augustus 1993 is uitvoerig gemeten ([1] en [9]).

3.2.1 ZUIVERINGSEIGENSCHAPPEN

De concentraties van verschillende gemeten stoffen in influent en effluent van de Living Machine van Providence staan in Tabel 2.

TABEL 2 GEMETEN INFLUENT- EN EFFLUENTKVALITEIT (1992-1993)

Parameter	Influent	Effluent	Eenheid
BZV5	149 (50 – 280)	2,9	mg/l
Zwevend stof	153	3	mg /l
N-Kjeldahl	10,8	0,3	mg N/l
Totaal P	3,9	1,9	mg P/l
E. coli	244.550	15	Kve/100 ml
Debit	34		m³/d

VOOR- EN NABEHANDELING

De voorbehandeling bestaat uit het zeven van het water middels een zeefbocht. Het effluent wordt zonder verdere nabehandeling geloosd in de oceaan.

ENERGIEVERBRUIK

Het energieverbruik voor de Living Machine in Providence is niet bekend.

SLIBPRODUCTIE


In de periode van september 1992 tot en met augustus 1993 is 27 m^3 nat slib verwijderd uit tank 6 van elke serie. Het vochtgehalte is niet gerapporteerd, dus omrekening naar droge stof is niet mogelijk.

3.3 DIERENPARK EMMEN

In het Dierenpark van Emmen is een waterzuiveringsconcept neergezet om het waterverbruik van het dierenpark te minimaliseren. In de oude situatie gebruikte het dierenpark 180.000 m³ drinkwater per jaar. Met de nieuwe installatie, die in 2002 in gebruik is genomen, daalde het drinkwatergebruik met 75%.

Afvalwater uit bassins van dierenverblijven, toiletten en de horeca gaan naar een opvangbassin. Via een zeebocht gaat het water naar een Living Machine. Vervolgens doorloopt het water een ultrafiltratie en een UV-desinfectie. Het concentraat van de ultrafiltratie gaat terug naar het opvangbassin. Regenwater wordt opgevangen en gebruikt om het gezuiverde water te verdunnen. Dit om ophoping van zouten te voorkomen. Het gezuiverde water wordt gebruikt voor irrigatie, het spoelen van toiletten, schoonmaakwerkzaamheden en het op peil houden van sommige vijvers. Een schematische weergave van het systeem is te zien in Figuur 9.


FIGUUR 9 SCHEMATISCHE WEERGAVE VAN DE WATERCYCLUS IN DIERENPARK EMMEN



De Living Machine is ontworpen door WMD op basis van de Living Machine technologie van het bedrijf Living Technologies Inc. van John Todd. Het bestaat uit een anoxische tank, een aerobe tank en twee bassins met planten. Vervolgens is er een nabezinktank. De aerobe tank en de tanks met planten worden actief belucht. Een schematische weergave is te zien in Figuur 10.

FIGUUR 10

SCHEMATISCHE WEERGAVE VAN DE LIVING MACHINE IN DIERENPARK EMMEN



FIGUUR 11

DE EERSTE EN TWEED RING VAN DE LIVING MACHINE



3.3.1 ZUIVERINGSEIGENSCHAPPEN

De zuiveringseigenschappen van de Living Machine in Dierenpark Emmen is te zien in Tabel 3.

TABEL 3

GEMETEN INFLUENT- EN EFFLUENTKWALITEIT (2002)

Parameter	Influent	Effluent*	Eenheid
BZV5	35,1	3,8	mg/l
NO ₂ -N	0,74	0,003	mg N/l
NO ₃ -N	11,48	16,79	mg N/l
N-Kjeldahl	15,95	2,98	mg N/l
Totaal N	25,72	20,11	mg N/l
Totaal P	2,85	1,48	mg P/l
Debit	633		m ³ /d

* kwaliteit na de Living Machine, dus voor de ultrafiltratie

Organische stoffen worden voor bijna 90% verwijderd en de concentratie totaal-P wordt ongeveer gehalveerd. Stikstofverwijdering vindt beperkt plaats.

3.3.2 OPERATIONELE EIGENSCHAPPEN

VOOR- EN NABEHANDELING

De voorbehandeling bestaat uit het zeven van het water middels een zeefbocht. De nabehandeling bestaat uit een ultrafiltratie en UV-desinfectie.

ENERGIEVERBRUIK

Het energieverbruik voor de Living Machine in Emmen (exclusief verwarming) is 434.526 MJ/j. Dit is 1,86 MJ/m behandelde afvalwater.

SLIBPRODUCTIE


In de zomer van 2002 werd 16,0 kg ds slib per dag geproduceerd en in de herfst 21,9 kg ds/d. Dit is 1,0 kg ds slib/kg BZV.

3.4 SOUTH PEST (BOEDAPEST, ORGANICA)

De installatie South Pest is gelegen in het zuiden van Boedapest. De installatie behandelt 15 tot 20% van de totale afvalwaterstroom van Boedapest en is begonnen als een conventionele rioolwaterzuiveringsinstallatie (rwzi) in 1966.

FIGUUR 12

BUITENAANZICHT VAN SOUTH PEST. BRON: ORGANICA



In de loop van de jaren zijn verschillende aanpassingen aan de installatie gedaan. In 2012 is de installatie volledig vernieuwd, waarbij 6 straten in operatie zijn. Straten 5 en 6 zijn omgebouwd tot *Food Chain Reactor* (FCR). Straten 1 t/m 4 zijn omgebouwd tot *Return Activated Sludge* (RAS). Dit is een hybride systeem. In deze straten is gesuspendeerd actief slib gecombineerd met geimmobiliseerd actief slib. Straten 1 en 2 zijn ouder en kleiner gedimensioneerd dan de overige straten. 75 tot 80% van het afvalwater wordt gelijk verdeeld tussen straten 3 t/m 6, de rest wordt verdeeld over straten 1 en 2. Door de verschillende systemen in verschillende straten te hebben, is de werking van de FCR goed te vergelijken met de RAS. De FCR is niet ontworpen voor stikstofverwijdering.


De installatie behandelt gemiddeld 60.000 m³ afvalwater per dag, met piekbelastingen tot 80.000 m³/d. Bij piekbelasting is de hydraulische verblijftijd 2 uur en 42 minuten.

FIGUUR 13 VOOR EN NA DE OMBOUW TOT FCR. BRON: ORGANICA



Behalve waterzuivering vindt er op de locatie ook energieproductie plaats uit organisch afval (voedsel dat over de verkoopdatum is, afval uit restaurants, zuiveringsslib), zie Figuur 14. De opgewekte energie wordt gebruikt voor de operatie van de rwzi.


FIGUUR 14 SCHEMA VAN HET WATERZUIVERINGS- EN ENERGIESYSTEEM (WWTP = RWZI). BRON: ORGANICA



De zuiveringsinstallatie ziet er schematisch als volgt uit. In dit schema staat hoe de FCR straten eruit zien.

FIGUUR 15

SCHEMA VAN DE FCR STRATEN IN DE RWZI. BRON: ORGANICA



Voor stikstofverwijdering is een BIOFOR-systeem in werking. Dit systeem kost veel energie en er dient methanol te worden toegevoegd. Dit systeem is met name toegevoegd om het effluent uit de straten 1 t/m 4 te behandelen.

3.4.1 ZUIVERINGSEIGENSCHAPPEN

De zuiverende eigenschappen van het South Pest systeem is te zien in tabellen 4 en 5. Hierbij dient te moeten worden opgemerkt dat de (klimatologische) omstandigheden, de influent-concentraties en de effluenteisen anders zijn dan in Nederland.

TABEL 4

GEMETEN INFLUENTKVALITEIT NA DE VOORBEZINKING (2012-2016)

Parameter	Gemeten*	Eenheid
CZV	437	mg/l
BZV5	237	mg/l
Zwevend stof	106	mg/l
NH ₄ -N	63,3	mg N/l
Totaal N	76,3	mg N/l
Totaal P	10	mg P/l
Temperatuur min	12	°C
Temperatuur max	25	°C
Debit	20.944	m ³ /d

* na primaire bezinker

TABEL 5

EFFLUENTKVALITEITSEISEN EN EFFLUENTKVALITEIT (NA BIOFOR, GEMIDDELD 2012-2016)

Parameter	Effluenteis	Effluentkwaliteit	Eenheid
CZV	< 125	55,1	mg/l
BZV5	< 25	13,3	mg/l
Zwevend stof	< 35	9,1	mg/l
Totaal N	< 35	24,4	mg N/l
NH ₄ -N	< 10	5,53	mg N/l
Totaal P	< 5	0,95	mg P/l

De effluentconcentraties liggen voor alle parameters (ver) onder de effluenteisen.

3.4.2 OPERATIONELE EIGENSCHAPPEN

VOOR- EN NABEHANDELING

De voorbehandeling bestaat uit een voorbezinktank waarna het water naar een verdeelkamer gaat. Van hieruit wordt het water verdeeld over de verschillende straten. Nabehandeling bestaat uit een nabezinktank en een BIOFOR-systeem voor verwijdering van N en P. Het slib uit de FCR wordt ingedikt en vergist samen met organisch afval. Het retourwater uit de BIOFOR en de slibindikking gaat terug naar de verdeelkamer.

SLIBPRODUCTIE

De slibproductie staat in onderstaande tabel. Dit is de slibproductie per straat. Ter vergelijking staat er de slibproductie van de RAS en de FCR naast elkaar.

TABEL 6

GEMIDDELDE SLIBPRODUCTIE (DROOG) PER STRAAT VAN RAS EN FCR IN DE PERIODE 2013-2015

Slibproductie	RAS	FCR
Totaal per straat	2.132 kg/j	1.738 kg/j
DS per m ³ afvalwater	0,21 kg/m ³	0,17 kg/m ³
DS per kg BZV in het influent	1,09 kg/kg	0,93 kg/kg
DS per kg verwijderd BZV	-	1,10 kg/kg

3.5 ETYEK

De installatie van Etyek is gelegen in het dorp Etyek, ten westen van Boedapest in Hongarije. Afvalwater van 8.334 inwoners wordt gezuiverd, alsmede afvalwater uit de lokale wijnindustrie en uit de nieuwe toen Korda filmstudio. De capaciteit van de installatie is 1.000 m³/dag en de installatie is operationeel sinds 2007. In 2013 werd 492 m³/d afvalwater behandeld.

De installatie van Etyek, alsmede die van Telki en de Franse installaties worden bedreven als batchproces en niet als continuproces.

FIGUUR 16


BUITENAANZICHT VAN DE INSTALLATIE IN ETYEK. BRON: ORGANICA




In Figuur 17 is een schematische weergave te zien van de zuiveringsinstallatie. Na een zeef (3 mm maaswijdte) en een zandvanger gaat het water naar een voorbeluchtingstank en een mixtank. In de voorbeluchtingstank wordt voornamelijk H_2S verwijderd. Hierna gaat het water naar de FCR in. Eerst wordt zuurstof biologisch uit het water verwijderd, vervolgens gaat het water naar anaerobe/anoxische tanks en vervolgens naar aerobe tanks. Tenslotte gaat het water naar een oorspronkelijk voor desinfectie bedoeld bassin. De kwaliteit van het water vraagt echter geen aanvullende desinfectie meer, dus deze tank wordt niet voor desinfectie gebruikt. Het slib wordt ingedikt en ontwaterd alvorens het wordt afgevoerd. Het water uit de slibindikking en -ontwatering gaat terug de FCR in.

Plattegronden van de ondergrondse en bovengrondse delen van de installatie zijn te zien in Figuur 18 en Figuur 19. Het totale oppervlak van de installatie is 520 m².

FIGUUR 17 SCHEMATISCHE WEERGAVE VAN DE ZUIVERINGSINSTALLATIE VAN ETYK MET DE ONTWERPPARAMETERS. BRON: ORGANICA




FIGUUR 18 PLATTEGROND VAN DE ONDERGRONDSE ONDERDELEN VAN DE INSTALLATIE. BRON: ORGANICA



FIGUUR 19

PLATTEGROND VAN DE BOVENGRONDSE ONDERDELEN VAN DE INSTALLATIE. BRON: ORGANICA



3.5.1 ZUIVERINGSEIGENSCHAPPEN

De zuiveringseigenschappen van de installatie in Etyek staan in tabellen 7 en 8.

TABEL 7

ONTWERPPARAMETERS EN GEMETEN INFLUENTKVALITEIT (2007-2015)

Parameter	Ontwerp	Daadwerkelijk	Eenheid
CZV	1.000	632	mg/l
BZV5	500	325,6	mg/l
Zwevend stof	416	282,6	mg/l
NH ₄ -N	75	78,8	mg N/l
Totaal N	100	99,1	mg N/l
Totaal P	15	10,2	mg P/l
Temperatuur min		12	°C
Temperatuur max		25	°C
Debit	1.000		m ³ /d

TABEL 8

EFFLUENTKVALITEITSEISEN EN EFFLUENTKVALITEIT (GEMIDDELD 2006-2015)

Parameter	Effluenteis	Effluentkwaliteit	Eenheid
CZV	< 100	42,8	mg/l
BZV5	< 30	7,2	mg/l
Zwevend stof	< 35	10,9	mg/l
Totaal N	< 35	16,7	mg/l
NH ₄ -N	< 10	4	mg N/l
Totaal P	< 5	2,8	mg P/l

Voor alle parameters liggen de concentraties in het effluent (ver) onder de effluenteisen.

3.5.2 OPERATIONELE EIGENSCHAPPEN

VOOR- EN NABEHANDELING

De voorbehandeling van het afvalwater bestaat uit een grove filtering (3 mm) en een zandvanger met een doorsnee van 1,4 m.

Er is geen nabehandeling.

ENERGIEVERBRUIK

Het totale energieverbruik van de installatie was in 2013 238.234 MJ/j en dat is 744 MJ/m²/j. In dat jaar werd 179.717 m³ afvalwater behandeld. Het energieverbruik per m³ afvalwater was 1,33 MJ. Dit was het totale energieverbruik, dus inclusief het energieverbruik voor verwarming van de kassen, slibindikking en -ontwatering en voor- en nabehandeling. Gegevens per procesonderdeel zijn niet beschikbaar.

SLIBPRODUCTIE

De gemiddelde slibproductie is weergegeven in Tabel 9.

TABEL 9

GEMIDDELDE SLIBPRODUCTIE (DROOG) IN 2013

Slibproductie	FCR
Totaal per straat	323.940 kg/j
DS per m ³ afvalwater	0,28 kg/m ³
DS per kg BZV in het influent	0,87 kg/kg
DS per kg verwijderd BZV	1,45 kg/kg

3.6 TELKI

De installatie van Telki is sinds 2005 operationeel in het Hongaarse dorp Telki, vlak bij Boedapest. De installatie is gedimensioneerd op 800 m³/dag.

FIGUUR 20


DE INSTALLATIE VAN TELKI, MET OP DE ACHTERGROND HET DORP. BRON: ORGANICA



De opzet van de installatie van Telki is gelijk aan die van Etyek. Omdat er minder water behandeld wordt, is de installatie iets kleiner (zie Figuur 21).


FIGUUR 21

SCHEMatische weergave van de installatie van Telki met de ontwerpparameters. Bron: ORGANICA



FIGUUR 22

DWARSDOORSNEDE VAN DE INSTALLATIE VAN TELKI. BRON: ORGANICA



3.6.1 ZUIVERINGSEIGENSCHAPPEN

De concentraties waarop de installatie is ontworpen en de daadwerkelijke influentconcentraties staan in Tabel 10. De effluentkwaliteitseisen en de behaalde effluentkwaliteit staan in Tabel 11.

Parameter	Ontwerp	Daadwerkelijk	Eenheid
CZV	700	890	mg/l
BZV5	385	430	mg/l
Zwevend stof	400	436	mg/l
NH ₄ -N	54	64	mg N/l
Totaal N	61	87	mg N/l
Totaal P	10	21	mg P/l
Temperatuur min		12	°C
Temperatuur max		22	°C
Debit	800	524	m ³ /d

TABEL 10

ONTWERPPARAMETERS EN GEMETEN INFLUENTKwaliteit (2006-2015)

Parameter	Ontwerp	Daadwerkelijk	Eenheid
CZV	700	890	mg/l
BZV5	385	430	mg/l
Zwevend stof	400	436	mg/l
NH ₄ -N	54	64	mg N/l
Totaal N	61	87	mg N/l
Totaal P	10	21	mg P/l
Temperatuur min		12	°C
Temperatuur max		22	°C
Debit	800	524	m ³ /d

TABEL 11

EFFLUENTKWALITEITSEISEN EN EFFLUENTKWALITEIT (GEMIDDELD 2006-2015)

Parameter	Effluenteis	Effluentkwaliteit	Eenheid
CZV	< 125	52	mg/l
BZV5	< 25	9	mg/l
Zwevend stof	< 35	9	mg/l
Totaal N	< 35	10	mg N/l
NH ₄ -N	< 10	3	mg N/l
Totaal P	< 5	1	mg P/l

Voor alle parameters liggen de concentraties in het effluent (veel) lager dan de effluenteisen.

3.6.2 OPERATIONELE EIGENSCHAPPEN

VOOR- EN NABEHANDELING

De voorbehandeling van het afvalwater bestaat uit een grove filtering (3 mm) en een zandvanger met een doorsnee van 1,4 m.

De nabehandeling bestaat uit een desinfectiestap.

ENERGIEVERBRUIK

Het totale energieverbruik van de installatie was in 2013 155.189 MJ/j en dat is 517 MJ/m³/j. In dat jaar werd 189.918 m³ afvalwater behandeld. Het energieverbruik per m³ afvalwater was 0,82 MJ. Dit was het totale energieverbruik, dus inclusief het energieverbruik voor slibindikking en -ontwatering, voor- en nabehandeling. Gegevens per procesonderdeel zijn niet beschikbaar.

SLIBPRODUCTIE


De slibproductie is niet bekend.

3.7 MELBOURNE

In de Australische stad Melbourne is een proefinstallatie gebouwd die dagelijks 58 m³ huiselijk afvalwater kan zuiveren.

FIGUUR 23

SCHEMATISCHE WEERGAVE VAN DE PROEFINSTALLATIE IN MELBOURNE. BRON: ORGANICA



3.7.1 ZUIVERINGSEIGENSCHAPPEN

Hoewel de daadwerkelijke influentkwaliteit behoorlijk afwijkt van de ontwerpparameters (Tabel 12), presteert de installatie goed. De effluentkwaliteitseisen worden gehaald.

TABEL 12

ONTWERPPARAMETERS EN GEMETEN INFLUENTKVALITEIT (2015)

Parameter	Ontwerp	Daadwerkelijk	Eenheid
CZV	507	1085	mg/l
BZV5	274	211	mg/l
Zwervend stof	199	736	mg/l
N-Kjeldahl	75	96	mg N/l
Temperatuur min		16	°C
Temperatuur max		26	°C
Debit	58	33	m³/d

TABEL 13

EFFLUENTKVALITEITSEISEN EN EFFLUENTKVALITEIT (2015, JAARGEMIDDELD)

Parameter	Effluenteis	Effluentkwaliteit	Eenheid
Zwervend stof	< 20	14,21	mg/l
BZV5	< 10	2,75	mg/l
Totaal N	< 20	18,87	mg/l
NH ₄ -N	Niet meer dan 7 dagen > 1	0,27	mg N/l
N-Kjeldahl		2,49	mg N/l
NO ₂ -N	Niet meer dan 7 dagen > 2	0,32	mg N/l
Totaal P		6,08	mg P/l

3.7.2 OPERATIONELE EIGENSCHAPPEN

VOOR- EN NABEHANDELING

Omdat influent van de gangbare rwzi wordt gebruikt, is er geen aparte voorbehandeling. De nabehandeling bestaat uit een nabezinktanks.

ENERGIEVERBRUIK

Het totale energieverbruik van de installatie is 59.000 MJ/j. Dat is 4,9 MJ/m³ behandeld afvalwater.

SLIBPRODUCTIE

De slibproductie in deze pilotinstallatie is 1,12 kg ds/kg verwijderd BZV.

3.8 LE LUDE

De installatie van Le Lude bevindt zich in de gemeente Le Lude aan de oevers van de Loir in het departement Sarthe in Frankrijk. De installatie is gedimensioneerd op de behandeling van afvalwater van 6.000 inwoners en heeft een capaciteit van 815 m³/d. De installatie is operationeel sinds 2010 en wordt bedreven als batchproces.

De installatie bestaat uit een FCR, biologische fosforverwijdering en co-precipitatie.

FIGUUR 24

BUITENAANZICHT VAN LE LUDE. BRON: ORGANICA



3.8.1 ZUIVERINGSEIGENSCHAPPEN

In onderstaande tabel zijn de gemiddelde in- en effluentconcentraties weergegeven van de jaren 2010 en 2011.

TABEL 14

ONTWERPPARAMETERS EN GEMETEN INFLUENTKwaliteit (2010-2011)

Parameter	Ontwerp	Daadwerkelijk	Eenheid
CZV	960	903	mg/l
BZV5	440	390	mg/l
Zwervend stof	660	511	mg/l
N-Kjeldahl	110	61	mg N/l
Totaal N	Geen ontwerpparameter	91	mg N/l
Totaal P	24	12	mg P/l
Temperatuur min			°C
Temperatuur max			°C
Debit	815		m ³ /d

TABEL 15

EFFLUENTKWALITEITSEISEN EN EFFLUENTKWALITEIT (JAARGEMIDDELD 2010-2011)

Parameter	Effluenteis	Effluentkwaliteit	Eenheid
CZV	< 125	37	mg/l
BZV5	< 25	6	mg/l
Zwervend stof	< 35	8	mg/l
N-Kjeldahl	Geen eis	6	mg N/l
Totaal N	< 15	8	mg N/l
Totaal P	< 4,8	0,7	mg P/l

Ook in Le Lude liggen de concentraties in het effluent voor alle parameters (ruim) onder de effluenteis.

SLIBPRODUCTIE

In 2015 werd 1.302 kg slib geproduceerd. Dit is 0,109 kg/m³ behandeld afvalwater en 0,556 kg/kg BZV.

3.9 LIVING MACHINES

Van Living Machines of Ecomachines gebouwd door het bedrijf van John Todd zijn niet veel gegevens gepubliceerd. In een rapport van John Todd Ecological Design staan enkele getallen over de prestaties van de Ecomachines. Dit document is ongedateerd, maar moet van na 2012 zijn ([1]). Hieronder een overzicht van de in het document gepresenteerde gegevens, aangevuld met gegevens uit [9].

TABEL 16 GEGEVENS VAN JOHN TODD ECOMACHINES

Type afvalwater	Harwich Septic tank effluent en slib	Providence Huishoudelijk afvalwater	South Burlington Huishoudelijk afvalwater	San Francisco Effluent rwzi	Ben & Jerry's Bedrijfsafval- water
Hydraulische verblijftijd (d)	10	2,5-4,5	2,8	0,71	20
Debit (m ³ /d)		34	302.800	75	3.785
Influent BZV (mg/l)	1.400	142	225	14	4.265
Effluent BZV (mg/l)	7	2,9	5,5	5,6	23,4
Influent ZS (mg/l)	4.800	153	203	13	327
Effluent ZS (mg/l)	20	3	3,4	5,6	20,8
Influent N-Kj (mg N/l)	117	10,8	26,3		52
Effluent N-Kj (mg N/l)	5	0,3	1,2		12
Influent E-coli (kve/100 ml)		244.550	8.960.000	648.000	2.377.091
Effluent E-coli (kve/100 ml)		15	763	157	2.464
Influent NO ₃ (mg N/l)			26		43
Effluent NO ₃ (mg N/l)			6,2		0,8

Helaas ontbreken gegevens over de voor- en nabehandeling, oppervlakten, energieverbruik en slibproductie.

De Living Machines zijn ingezet voor verschillende typen afvalwater en het systeem is aangepast op dat water en de eisen aan het effluent. De hydraulische verblijftijden variëren dan ook sterk: van 0,7 tot 20 dagen. Ook het debiet van het influent varieert sterk en dat laat zien dat Living Machines geschikt zijn om kleine en grote afvalwaterstromen te behandelen. De hier getoonde Living Machines zijn, net als de meeste zuiverende kassen van Organica vooral ingezet voor de verwijdering van BZV, zwevend stof en ammonium.

4

VERGELIJKING MET CONVENTIONELE SYSTEMEN

4.1 ONTWERPVRAAG

De cijfers en informatie van de bestaande systemen uit het vorige hoofdstuk zijn afkomstig van de betreffende leverancier. Naast het feit dat dit niet van een onafhankelijke bron komt, zijn de omstandigheden en scenario's niet geheel te vergelijken met die van Nederland. Zo zijn de effluenteisen voor totaal stikstof en fosfaat strenger in Nederland en is het verschil in aanvoer bij droog weer en regen weer groter.

Om deze reden is een ontwerpervraag uitgezet bij Organica en Biopolus voor twee scenario's. Dit zijn het scenario RWZI Vriescheloo en RWZI Epe. Dit zijn bestaande installaties ontworpen voor respectievelijk 10.000 en 55.000 i.e. De gedachte is dat op deze manier een bestaande situatie op het gebied van onder andere slibproductie en energie vergeleken kan worden met de desbetreffende ontwerpen.

Deze installaties worden echter nog niet belast met hetgeen waarvoor ze ontworpen zijn en dus geen representatieve cijfers kunnen laten zien. Om dit op te lossen, is gebruik gemaakt van de ontwerp- en terugrekentool (OWT) van Tauw en de participerende waterschappen. Voor de ontwerpen is wel gebruik gemaakt van de gemiddelde influentconcentraties van deze installaties en zullen de scenario's nog respectievelijk Vriescheloo en Epe heten. In het geval van dit laatste scenario is er dus gerekend als zijnde een conventioneel actief slib systeem en niet als Nereda™.

Een FCR of MNR is in de basis een installatie die voor de fosfaatverwijdering gebruik maakt van de dosering van metaalzouten en geen biologische fosfaatverwijdering kent. Beide partijen hebben aangegeven dat het wel mogelijk is, maar dat er dan sprake is van een hybride systeem (zowel zwevend als vastgehecht zuiveringsslib). Om deze reden is dus voor ieder scenario zowel een installatieontwerp gevraagd voor chemische fosfaatverwijdering (Chem-P) en biologische fosfaatverwijdering (Bio-P).

4.2 RESULTATEN

4.2.1 VRIESCHELOO

RWZI Vriescheloo is in 2001 ontworpen voor een belasting van 17.392 i.e. (a 150 g TZV). Voor de ontwerp aanvraag is gebruik gemaakt van de huidige gemiddelde influent concentraties gekoppeld aan het maximale dag debiet. Tabel 17 geeft de gebruikte influentvrachten en -debieten weer.

TABEL 17

INFLUENTCIJFERS RWZI VRIESCHELOO

Parameter	Influent gegevens
Capaciteit (v.e.)	17.392
CZV (kg/d)	1.745
BZV ₅ (kg/d)	727
Kjeldahl-N (kg N/d)	189
P-totaal (kg P/d)	27
O.B. (kg/d)	552
Dagdebit (m ³ /d)	2.800
Droogweer debiet (m ³ /h)	145
Regenweer debiet (m ³ /h)	470

De effluenteisen zijn de standaard eisen voor een zuivering van dit formaat en zijn als volgt:

TABEL 18

EFFLUENT EISEN ONTWERP

Parameter	Effluent eis
CZV (mg/l)	125
BZV ₅ (mg/l)	20
O.B. (mg/l)	30
N-totaal (mg N/l)	15
P-totaal (mg P/l)	2

Met de ontwerp- en terugreken tool is uitgekomen op een phoredox type systeem. Afwijkend van de werkelijke eis is geprobeerd om jaarrond onder de gestelde eis te blijven van N= < 15 en P= < 2 in plaats van een jaar- of voortschrijdend gemiddelde. Het temperatuurprofiel dat daarvoor gebruikt is, is afgeleid van de gemiddelde maandtemperaturen van het influent van RWZI Vriescheloo: in de zomer een maximum van 19°C en in de winter een minimum van 8°C.

De actiefslibtank bestaat uit een anaerobe zone van 150 m³, een anoxische zone van 1.800 m³ en een aerobe zone van 2.350 m³. Voor slib/water scheiding is gekozen voor een NBT met een diameter van 30 meter en kantdiepte van 2 meter. In het scenario is directe slibontwatering meegenomen.

Belangrijk detail is dat de OWT op dit moment gelimiteerd is met het doorrekenen van bepaalde parameters (OB, CZV) of hier zelfs een hard minimum voor aangeeft (NH₄-N).

Daarnaast bleek het niet mogelijk om de centraal stroom mee te rekenen met de influentconcentratie. Aangezien er in dit scenario geen sprake is van een slibgisting, is het effect van de centraal stroom op de stikstof- en fosfaatconcentraties beschouwd als verwaarloosbaar.


Met de OWT bleek het niet mogelijk om de installatie volledig Bio-P te ontwerpen en is gebruik gemaakt van additieve chemische P-verwijdering.

ONTWERP ORGANICA

In de opzet is de voorzuivering niet veel anders dan die van conventionele systemen. Het behelst een roostergoed verwijdering (3 mm) en een beluchte zandvanger. Bij de biologische verwerking is gekozen voor 1 proceslijn met 6 FCR's met een gezamenlijk volume van 1.898 m³. De recirculatie ten behoeve van denitrificatie vindt plaats tussen de 6e en de 1e reactor. Na deze fase volgt een coagulatietank voor fosfaatverwijdering voorafgaand aan een hoge

nabezinktank. Een standaard nabehandeling, afgeleid uit Hongaarse richtlijnen, is met U.V. De sliblijn is eveneens vergelijkbaar met traditionele systemen, hoewel onconventioneel met zuivering van dit formaat, wordt er zowel ingedikt als ontwaterd. Waterschappen hebben veelal een of twee grotere zuivering die mede slib ontwaterd van kleine installaties.

FIGUUR 25 WEERGAVE VAN HET ONTWERP VOOR VRIESCHELOO VAN ORGANICA. BRON: ORGANICA




Het oppervlak van de gehele installatie 873 m^2 . Hierbij moet vermeld worden dat het hier gaat om een standaardontwerp waarbij 206 m^2 gedefinieerd is als ruimte voor sociale interactie (educatie, recreatie e.d.). Het netto oppervlak voor afval water zuiveren is in deze dus 667 m^2 . De totale hoogte van het gebouw is 10 meter, waarvan 3 meter onder het maaiveld en 7 meter er boven.

Het verschil tussen de installatie met chemische en de installatie met biologische P verwijdering kan het beste in beeld gebracht worden door beide processchema's naast elkaar te leggen, zie Figuur 26.

FIGUUR 26

PROCESSCHEMA'S ONTWERP CHEMISCHE EN BIOLOGISCHE P VERWIJDERING VRIESCHELOO VAN ORGANICA. BRON: ORGANICA



Het meest in het oog springende verschil is de extra reactor. FCR 1 en 2 zijn hierbij anaeroob en faciliteren het contact voor de gesuspendeerde biomassa met het afvalwater. Opvallend hierbij is de recirculatie van FCR 2 naar 1. Het totale reactor volume is 278 m³ groter dan het ontwerp met chemische fosfaatverwijdering, qua oppervlak komt het neer op een netto van 755 m² zuiveringsoppervlak.

Een ander aspect dat opvalt in beide ontwerpen is de aanwezigheid van een bypassleiding. De argumentatie hiervoor is dat gedurende de RWA het water zo dun is dat het gewoon de installatie kan passeren. Bij maximale RWA zal dus 26% van het influent de FCR's passeren. In dit scenario betekent dit alles boven de 350 m³ per uur. In Nederland wordt een dergelijke constructie gezien als not-done. Ook na de first flush zal het water hoge concentraties aan verontreinigingen kennen die niet ongezuiverd geloosd mogen worden op het oppervlakte-water.


De documenten bijbehorende bij het ontwerp van Organica zijn terug te vinden in bijlage 4.

ONTWERP BIOPOLUS

De primaire zuivering is een roostergoedverwijdering (3mm) en een zand/vetzanger. Biopolus

verdeelt vervolgens het afvalwater over twee straten met ieder 6 MNR's. Het gezamenlijke volume van de reactoren is 1.920 m³. Opmerkelijk is dat niet al het afvalwater start bij MNR 1, de eerste anoxische zone, maar dat een derde deel van de stroom doorgaat naar de tweede anoxische zone MNR 5. Deze opzet is waarschijnlijk gekozen om bovenop de recirculatie nitraatreductie te bevorderen. Na de MNR-straten stroomt het water via een pijpflocculator, ten behoeve van coagulatie/flocculatie, naar een DAF-installatie. Na afloop van deze installatie volgt nog een microfilter en eventueel een UV-desinfectie. Het slib vanuit de DAF en Microfilter wordt, na buffering in een beluchte slibtank, ontwaterd.

FIGUUR 27 PROCESFLOWDIAGRAMMEN CHEMISCHE EN BIOLOGISCHE P VERWIJDERING VRIESCHELOO VAN BIOPOLUS. BRON: BIOPOLUS




De variant met biologische fosfaatverwijdering heeft 2 extra reactoren. Een kleine selector en MNR 1 zonder dragermateriaal. Verder verloopt het traject nagenoeg hetzelfde. Het retourslib komt vanuit een DAF-installatie en de verwerking van het spuislib verschilt met het chemisch ontwerp in die zin dat er nog een gravitaire indikker aanwezig is.

Het oppervlak is in de basis 635 m² voor het chemisch P verwijdering ontwerp en 690 m² voor het biologische P verwijdering ontwerp. Biopolus geeft in zijn ontwerpvoorstel aan dat de modulaire opzet het mogelijk maakt het oppervlak nog verder te reduceren, dit door bijvoorbeeld meer de hoogte in te gaan. Op deze wijze is het mogelijk deze installaties in stedelijk gebied met beperkte ruimte te plaatsen. Hieronder wat voorbeeld schetsen van installatieconstructies.

FIGUUR 28

LAYOUTMOGELIJKHEDEN ZUIVERENDE KASSEN. BRON: BIOPOLUS



De documenten bijbehorende bij het ontwerp van Biopolus zijn terug te vinden in bijlage 3.

4.2.2 VERGELIJKINGEN SCENARIO VRIESCHELOO

Voor de vergelijking zijn een aantal aspecten naast elkaar gezet: effluentkwaliteit, energie, chemicaliën, reststoffen, en kosten. Deze vergelijkingen worden uiteengezet in tabellen gevolgd door een korte discussie.

EFFLUENTKWALITEIT

In Tabel 19 zijn de verwachte effluentconcentraties weergegeven. Een belangrijke kanttekening is dat in het geval van de OWT en het Biopolus ontwerp de slechtste situatie wordt weergegeven (bij 8°C). Organica hanteert jaargemiddelde waarden. Inhoudbaar betekent dit laatste dat de N-eis bij temperaturen onder de 10°C niet te behalen is.

TABEL 19 VERWACHTE EFFLUENTCONCENTRATIES

Parameter	Eenheid	Scenario Vriescheloo	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
CZV	mg/l		38	39	85	70
BZV	mg/l	5,3	4,6	4,2	6,5	7,0
Ammonium	mg/l	1,5	2,2	0,9	3,0	4,0
Nitraat	mg/l	10,3	11,3	12,4	10,0	9,0
Totaal -N	mg/l	13,3	14,8	14,5	14,5	14,5
N-org	mg/l	1,5	1,3	1,3	1,5	1,5
PO ₄ -P	mg/l	n.b.	1,7	1,3	0,5	0,5
Totaal-P	mg/l	1,2	1,9	1,7	2,0	2,0
O.B.	mg/l	n.b.	10,0	10,0	<30	<30

RUIMTEGEBRUIK

De enige vergelijking die gemaakt kan worden met het OWT Vriescheloo scenario is die met betrekking tot het reactorvolume. Het volume van de zuiverende kassen is rond de 50% kleiner dan het actiefslib model. Een aspect wat niet is meegenomen in deze vergelijking, zijn de volumes en oppervlakken van de overige procesonderdelen, zoals een nabezinktank.

TABEL 20 RUIMTEGEBRUIK VAN DE REACTOREN

Onderdeel	Eenheid	Scenario Vriescheloo	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Totaal reactor volume	m ³	4.300	1.920	2.230	1.898	2.176
Oppervlak Reactoren	m ²	n.b.	227	345	396	452
Totale oppervlak zuivering	m ²	n.b.	635	690	921	915

ENERGIEVERBRUIK

In Tabel 21 is het verwachte elektriciteitverbruik van de ontwerpen op jaarbasis en het verbruik per m³ behandeld afvalwater te zien. Dit laatste onderdeel is vervolgens opgesplitst naar energieverbruik per procesonderdelen.

TABEL 21 ELECTRICITEITSVERBRUIK

Energie onderdeel	Eenheid	Scenario Vriescheloo	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Jaarlijks elektriciteitsverbruik	kWh/y	504.795	378.140	551.880	316.820	439.460
Elektriciteit per m ³	kWh/m ³	0,46	0,37	0,54	0,31	0,44
- Primaire zuivering	kWh/m ³	0,006	0,034	0,034	0,04	0,04
- Reactor(en)	kWh/m ³	0,33	0,26	0,27	0,22	0,35
- Na behandeling	kWh/m ³	0,012	0,028	0,2	0,011	0,011
- Slibbehandeling	kWh/m ³	0,063	0,023	0,017	0,026	0,026
- Overig	kWh/m ³	0,045	0,021	0,017	0,008	0,008

In vergelijking met het conventionele ontwerpscenario is het energieverbruik in alle ontwerpen lager met uitzondering van het Bio-P-ontwerp van Biopolus. De oorzaak hiervan is de keuze van nabehandeling. Een vergelijking die meer in lijn is met de opdracht van deze rapportage is om te kijken naar het energieverbruik van de reactoren (zie Tabel 22).

TABEL 22 ENERGIEVERBRUIK VAN DE REACTOREN, UITGESPLITST NAAR ONDERDEEL

Reactor(en)	Eenheid	Scenario Vriescheloo	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Beluchting	kWh/m ³	0,23	0,195	0,201	0,197	0,273
Menging	kWh/m ³	0,1	0,062	0,062	0,000	0,017
Recirculatie	kWh/m ³	0,004	0,005	0,005	0,017	0,056
Dosering	kWh/m ³	n.a.	0,001		0,001	

Te zien is dat de verschillen tussen in ieder geval de ontwerpen van Biopolus en het ontwerp van de chemische P-verwijdering van Organica niet zo groot is. De bio-P-installatie van Organica heeft een wat hogere beluchtingsenergie dan de andere ontwerpen. Dit energieverbruik neemt wat toe, omdat de reactoren naast slib-op-drager ook actiefslib bevatten en dit de zuurstoftransferefficiëntie negatief beïnvloedt. Het is niet duidelijk waarom dit vele malen hoger is bij Organica dan bij Biopolus. De recirculatie energie van Organica is opvallend hoger dan dit heeft in het chem-P-scanario te maken met dat er grotere volumes worden rerecirculeerd dan bijvoorbeeld het chem-P van Biopolus. In het geval van de bio-P-installatie is er ook nog een extra recirculatie aanwezig tussen FCR 1 en 2.

Te zien is dat het gasverbruik voor het verwarmen van de kas bij de ontwerpen van Organica niet aanwezig is in tegenstelling tot bij de ontwerpen van Biopolus. Het gasverbruik is te zien in Tabel 23.

TABEL 23 GASVERBRUIK

Energieonderdeel	Eenheid	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Aardgas verbruik	m ³ /d	8,25	9,7	0	0
Als elektrische energie	kWh/d	81,24	95,7	0	0

Bij navraag verklaarde Biopolus dat dit te maken heeft met het op een minimale temperatuur te houden van de kas van 6 graden. Hierbij wordt geen restwarmte van het afvalwater gebruikt, is er een geringe isolatie van de kas en komt er geen warme van nabijgelegen bebouwing. Strikt noodzakelijk voor de zuiverende werking van het systeem is deze verwarming niet. De gebruikte tropische planten vereisen echter deze minimumtemperatuur. Een optie om verwarming te voorkomen is door een soberdere uitstraling te gebruiken met andere planten. Verwarming met aardgas is dus een keuze, net zoals het gebruikmaken van milieuvriendelijker technieken, zoals warmte/koude opslag.

Organica bevestigt dat extra verwarming niet nodig is om de temperatuur in de kas boven de 6 graden te houden, de restwarmte van het afvalwater en inval van zonlicht voorzien hierin.

CHEMICALIËNVERBRUIK

In Tabel 24 is de dagelijkse hoeveelheid chemicaliën die volgens de ontwerpen gebruikt wordt weergegeven. Onder chemicaliën verstaan we hier metaalzouten voor het binden van fosfaat en polyelektryolyt voor indikking en/of ontwatering van slib. Voor de vergelijking is de hoeveelheid metaalzout naast m³/d en kg/d ook weergegeven in het aantal mol/d, omdat de ontwerpers met verschillende type metaalzouten werken.

TABEL 24 CHEMICALIËNGERUIK VOLGENDS DE ONTWERPEN

Onderdeel	Eenheid	Scenario Vriescheloo	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
FeCl ₃ (40%)	m ³ /d	0,018	0,18			
Mol FeCl	kMol/d	0,19	1,9			
Massa FeCl (1.400 kg/m ³)	kg/d	10	100,8			
PAC (10% Al ₂ O ₃)	m ³ /d				0,28	
Mol PAC / Al ₂ O ₃	Mol/d				1,3	
Massa PAC (1.210 kg/m ³)	kg/d				34	
Polyelektrolyt	kg/d	7	3,7	5	4,6	4,6

In het OWT-ontwerp van Vriescheloo is dosering van metaalzout enkel nodig ter aanvulling van de Bio-P verwijdering. Kijkend naar de hoeveelheden in mol product doseert Biopolus meer dan Organica. De Me:P-verhoudingen zijn 2,2 (Biopolus) en 1,5 (Organica).

De hoeveelheid polyelektrolytverbruik verschilt eveneens in de onderlinge ontwerpen. Dit heeft waarschijnlijk te maken de aannamen van verbruik polyelektrolyt per ingaande kg droge stof. Deze hoeveelheid is uiteraard ook afhankelijk van de hoeveelheid slib die behandeld wordt.

RESTSTOFFENPRODUCTIE

Voor de berekening van de slibproductie is gebruik gemaakt van de productie bij 8°C (10°C ontwerpen Organica). De productie van reststoffen is te zien in Tabel 25.

TABEL 25 PRODUCTIE RESTSTOFFEN

Onderdeel	Eenheid	Scenario Vriescheloo	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Roostergoed	kg/d	n.b.	0,14	0,14	0,24	0,24
Zand	kg/d	n.b.	74,47	74,47	140	140
Slib	Kg d.s./d	543	616	531	540	520
- waarvan chemisch	Kg d.s./d		90	n.a.	n.b.	n.b.
Plantenbiomassa	Kg d.s./ jaar	n.a.	1.920	1.920	1.180	1.331

In de tabel is te zien dat de ontwerpen van Organica en Biopolus minder biologisch slib produceren dan het actiefslibsysteem. De totale slibproductie wordt echter sterk beïnvloed door het gebruik van metaalzouten. In het geval van Biopolus is de hogere Me:P en het type (zwaardere) metaalzout ook ongunstig. Een opvallend verschil tussen de ontwerpen van Organica en vooral Biopolus is dat het slibproductie daalt bij biologische fosfaatverwijdering. De lijn der verwachting zou zijn dat dit hybride systeem meer slib moet afvoeren om het fosfaat te verwijderen. Organica meldt na navraag dat er inderdaad veel meer slib uit de nabezinker komt, maar dat dit grotendeels gerecirculeerd wordt terug naar de tweede tank van de hybride versie. P wordt verwijderd met het slib dat niet wordt gerecirculeerd. Bij het Epe scenario gaat dit terug naar de twee treinen. In totaal gaat er dus veel meer door het systeem en door de biomassa opnieuw in te brengen, wordt de slibleeftijd verlengd om biologische P opname te realiseren. Uiteindelijk gaat een kleine stroom naar de ontwatering, waarna de opgegeven hoeveelheid overblijft.

Belangrijke kanttekening bij het kijken naar de slibcijfer verschillen tussen Biopolus en Organica is de temperatuur. Dit scheelt twee graden met elkaar. In de ontwerp en terug reken-

tool betekent dit al gauw een verschil van 2,5% in slibproductie wat neer komt op ongeveer 14 kg ds/dag, maar gezien de onnauwkeurigheden in metingen van slibproductie en modellering van productie is dit niet significant te noemen.

Een ander opvallend verschil gerelateerd aan de zuiverende kassen is het groenafval (Tabel 26). Biopolus bepaalt het groenafval op basis van een minimale binnentemperatuur van 6°C, het type planten dat dan groeit en de maximale grootte die de planten kunnen/mogen bereiken. Op deze basis betekent dit een groei van 10 tot 30 kg biomassa/m².j. In de berekening is gekozen voor het gemiddelde van 20 kg d.s./m².j. Organica koos voor een groei van 14,3 kg d.s./m².j.

TABEL 26 GEPRODUCEERDE PLANTENBIOMASSA BIJ GELIJKE GROEIFACTOR

Productie	Eenheid	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Planten biomassa	kg d.s./j	1.373	1.373	1.180	1.331

Bij dezelfde groeifactor is te zien dat de hoeveelheid plantenbiomassa bij Biopolus groter is. Dit is opvallend, want in Tabel 20 is te zien dat de oppervlakte van de reactoren bij Biopolus juist kleiner is. Het oppervlak aan plantenrekken is bij Biopolus echter hoger. Het verschil zit waarschijnlijk in de hoeveelheid plantenrekken of het oppervlak per plantenrek dat gehanteerd wordt.

TABEL 27 OPPERVLAKTE PLANTENREKKEN

	Eenheid	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Oppervlak plantenrekken	m ²	96,0	96,0	82,5	93,1

KOSTEN

Een inschatting van de realisatiekosten voor de ontwerpen staan in Tabel 28.

TABEL 28 REALISATIEKOSTEN VAN DE ONTWERPEN

Onderdeel	Scenario Vriescheloo	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Realisatiekosten zonder toeslagfactor	€ 4.765.882	€ 2.651.000	€ 3.064.000	€ 3.363.000	€ 3.385.000
Realisatiekosten met toeslagfactor (70%)	€ 8.102.000	€ 4.506.700	€ 5.208.800	€ 5.717.100	€ 5.754.500

Belangrijk om te vermelden, is dat het voor alle ontwerpen (Biopolus, Organica, OWT) gaat om een schatting van de kosten. De OWT heeft een uitgebreide detailberekening en maakt het gebruik van een toeslagfactor (70%). Deze toeslagfactor is ook bij de kosten voor de realisatie van de ontwerpen van Biopolus en Organica berekend.

Wat betreft jaarlijks terugkerende kosten is het in deze vergelijking enkel mogelijk de kosten van energie, slibverwerking en chemicaliën naast elkaar te zetten.

TABEL 29 JAARLIJKSE KOSTEN VAN ENERGIE, SLIBVERWERKING EN CHEMICALIËN

Onderdeel	Scenario Vriescheloo	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Energie ¹	€/jaar	30.353	23.914	24.835	20.236
Slibverwerking ²	€/jaar	63.918	72.510	62.505	63.565
Metaalzouten ³	€/jaar	6.935	69.350		47.450
Totaal	€/jaar	101.206	165.774	87.340	131.251
					93.404

¹ Op basis van reactor(en), prijs € 0,09 /kW² € 322,50,-/ ton d.s. slibkoek (bron: Waterspiegel Unie van Waterschappen)³ Metaalzout op basis van € 0,10 / mol Me³⁺ (bron: waterspiegel Unie van Waterschappen)

4.2.3 EPE

RWZI Epe de eerste groene weide Nereda installatie op praktijkschaal. Deze installatie is (nog) niet representatief voor alle Nereda installaties, omdat deze nog niet volledig belast is en zogenaamd *veilig ontworpen* is. Dat wil zeggen dat ook hier praktijkcijfer materiaal niet bruikbaar is voor vergelijking en dat gebruik is gemaakt van de OWT. Gekozen is om de gemiddelde influent cijfers van Epe te gebruiken voor dit scenario. Hetzelfde temperatuurprofiel als dat van scenario Vriescheloo is in deze toegepast. Tabel 30 geeft de gebruikte influentvrachten en debieten weer.

TABEL 30 INFLUENTGEGEVENS RWZI EPE

Parameter	Influentwaarden
Capaciteit (v.e.)	
CZV (kg/d)	5.420
BZV ₅ (kg/d)	2.230
Kjeldahl-N (kg N/d)	570
P-totaal (kg P/d)	61
O.B. (kg/d)	2.120
Dagdebit (m ³ /d)	8.000
Droogweer debiet (m ³ /h)	560
Regenweer debiet (m ³ /h)	1.500

De effluenteisen zijn de standardeisen opgegeven aan Organica en Biopolus:

TABEL 31 EFFLUENTEISEN AAN DE ONTWERPEN

Parameter	Effluent eis
CZV (mg/l)	125
BZV ₅ (mg/l)	20
O.B. (mg/l)	30
N-totaal (mg N/l)	10
P-totaal (mg P/l)	2

In de praktijk zijn de eisen voor N-totaal < 5, P-totaal < 0,3. Het gaat hier dus om een fictief scenario.


De OWT adviseert net als in het voorgaande scenario een Phoredox type systeem. De anaerobe tank heeft een inhoud 480 m³, de anoxische tank 4.185 m³ en de aerobe tank 6.400 m³. Deze worden gevolgd door twee nabezinktanks met een diameter van 35 m² en een kantdiepte van 2 meter.

Voor het scenario Epe geldenzelfde beperkingen als voor het scenario Vriescheloo (zie paragraaf 4.2.1).

ONTWERP ORGANICA

Ten opzichte van de ontwerpen voor Vriescheloo is er een aantal verschillen. De meest voor de hand liggende is de aanwezigheid van 2 straten met ieder 7 FCR's (8 bij Bio-P) die een groter volume hebben. Wat niet zo voor de hand ligt, is de interne recirculatie voor de denitrificatie. Deze loopt van FCR 5 naar het begin in plaats van naar de laatste reactor. Dit voor de in FCR 6 en 7 (of 7 en 8 bij Bio-P) extra denitrificatie, waarbij het opvalt dat er een externe koolstofbron (methanol) dosering nodig is om deze voldoende te laten verlopen.

FIGUUR 29 PROCESSSCHEMA'S ONTWERPEN VOOR EPE VAN ORGANICA. BRON: ORGANICA




De documenten behorende bij het ontwerp van Organica zijn terug te vinden in bijlage 5.

ONTWERP BIOPOLUS

In vergelijking met het scenario Vriescheloo is er alleen verschil in de grootte van de MNR's (zie Figuur 30).

De documenten bijbehorende bij het ontwerp van Biopolus zijn terug te vinden in bijlage 3.

FIGUUR 30 PROCESSSCHEMA'S ONTWERPEN VOOR EPE VAN BIOPOLUS. BRON: BIOPOLUS



4.2.4 VERGELIJKING SCENARIO EPE

Voor de vergelijking is een aantal aspecten naast elkaar gezet: effluentkwaliteit, energie, chemicaliën, reststoffen en kosten. Deze vergelijkingen worden uiteengezet in tabellen gevolgd door een korte discussie.

EFFLUENTKWALITEIT

In Tabel 32 zijn de verwachte effluentconcentraties weergegeven. Een belangrijke kanttekening is dat in het geval van de OWT en het Biopolus ontwerp de maximale concentraties worden weergegeven (bij een influenttemperatuur van 8°). Organica hanteert jaargemiddelde waarden. Inhoudelijk betekent dit laatste dat de N-eis bij temperaturen onder de 10°C niet te behalen is. Gezien de stikstof eis een jaargemiddelde betreft is het in feite ook niet noodzakelijk hier aan te voldoen.

TABEL 32 VERWACHTE EFFLUENTCONCENTRATIES VAN DE ONTWERPEN

Parameter	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
CZV	mg/l	n.b.	45	48	85	70
BZV	mg/l	5,7	3,8	3,2	7,0	6,5
Ammonium	mg/l	1,5	1,3	1,5	2,5	1,0
Nitraat	mg/l	6,7	7,2	7,2	6,0	8,0
Totaal -N	mg/l	9,7	9,8	9,9	10,0	10,0
N-org	mg/l	1,5	2,6	2,9	1,5	1,0
PO ₄ -P	mg/l	n.b.	1,4	1,1	0,5	0,5
Totaal-P	mg/l	0,2	1,8	1,6	2,0	2,0
O.B.	mg/l	n.b.	6,8	10	<30	<30

RUIMTEGEBRUIK

Het enige opmerkelijke in deze vergelijking (Tabel 33), ten op zichte van het Vriescheloo scenario, is het volume verschil tussen de Chem-P en Bio-P ontwerpen van Organica. Bij het voorgaande scenario was het verschil in volume 278 m³ en in dit scenario is dat 1.552 m³. Bij het Biopolus ontwerp was het verschil 310 m³ en in dit scenario is dat 330 m³. Organica meldt dat dit komt omdat de CZV-concentratie 8% hoger ligt, de BZV-concentratie 7% en de totaal-N concentratie 7%. Alleen de totaal-P-concentratie ligt lager. Door de hogere concentraties moet de verblijftijd langer worden. In het Vriescheloo scenario is de hybride installatie 15% groter dan de FCR en bij het Epe scenario is dat 25%. Organica ziet niet in hoe dat bij de Biopolus installaties anders kan zijn, gezien het verschil in belasting.

TABEL 33 RUIMTEGEBRUIK VAN DE ONTWERPEN

Onderdeel	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Totaal reactor volume	m ³	11.065	6.600	6.930	6.582	8.134
Totale oppervlak zuivering	m ²	n.b.	1.566	1.777	2.604	2.739
Reactoren	m ²	n.b.	1.367	1.480	1.304	1.604
Plantenrekken	m ²		210	210	280	348

ENERGIEVERBRUIK

In Tabel 34 staat het verwachte elektriciteitverbruik van de ontwerpen op jaarbasis en het verbruik per m³ behandeld afvalwater. Dit laatste onderdeel is vervolgens opgesplitst naar energieverbruik per procesonderdeel.

TABEL 34 VERWACHT ELECTRICITEITSVERBRUIK IN DE ONTWERPEN

Energie onderdeel	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Jaarlijks elektriciteitverbruik	kWh/y	1.442.115	934.400	1.343.200	878.920	1.497.960
Elektriciteit per m ³	kWh/m ³	0,49	0,32	0,46	0,301	0,513
- Primaire zuivering	kWh/m ³	0,007	0,045	0,045	0,021	0,024
- Reactor(en)	kWh/m ³	0,35	0,22	0,25	0,25	0,42
- Na behandeling	kWh/m ³	0,014	0,031	0,126	0,004	0,004
- Slibbehandeling	kWh/m ³	0,04	0,018	0,025	0,026	0,025
- Overig	kWh/m ³	n.b.	0,009	0,009	n.b.	n.b.

TABEL 35 VERWACHT ELECTRICITEITSVERBRUIK OPGESPLITST NAAR ONDERDEEL

Reactor(en) uitgesplitst	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Beluchting	kWh/m ³	0,24	0,19	0,21	0,24	0,32
Menging	kWh/m ³	0,1	0,022	0,027	0	0,087
Recirculatie	kWh/m ³	0,006	0,009	0,009	0,015	0,015
Dosering	kWh/m ³	n.a.	0,002		0,001	

Het verwachte aardgasverbruik staat in Tabel 36.

TABEL 36 VERWACHT AARDGASGEbruIK

Energieonderdeel	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Aardgas verbruik	m ³ /d	n.b.	27	30	0	0
In GER (35,17 MJ/m ³)	m ³ /d		950	1.062	0	0
Als elektrische energie	kWh/d		266	297	0	0

Zoals eerder aangegeven bij het Vriescheloo scenario, is het hoogstwaarschijnlijk niet noodzakelijk de kas bij te verwarmen.

CHEMICALIËNVERBRUIK

In Tabel 37 is de dagelijkse hoeveelheid chemicaliën die volgens de ontwerpen gebruikt wordt weergegeven. Onder chemicaliën verstaan we hier metaalzouten voor het binden van fosfaat en polyelektrolyt voor indikking en/of ontwatering van slib. Voor de vergelijking is de hoeveelheid metaalzout naast m³/d en kg/d ook weergegeven in het aantal mol/d, omdat de ontwerpers met verschillende type metaalzouten werken.

TABEL 37 CHEMICALIËNGERUIK VOLGENS DE ONTWERPEN

Onderdeel	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
FeCl ₃ (40%)	m ³ /d	n.a.	0,34			
kMol FeCl	kMol/d	n.a.	3,4			
Massa FeCl (1.400 kg/m ³)	kg/d	n.a.	190			
PAC (10% Al ₂ O ₃)	m ³ /d				0,14	
kMol PAC / Al ₂ O ₃	kMol/d				0,63	
Massa PAC (1.210 kg/m ³)	kg/d				16,9	
Polyelektrolyt	kg/d	22	7,8	8,6	16,5	15,5
Methanol	m ³ /d	n.a.	n.a.	n.a.	0,5	0,4
Massa methanol	kg /d				396	317

In voorgaande scenario was er klein verschil in Me:P-verhoudingen. In dit scenario verschilt dit zeer sterk: 2,4 bij het ontwerp van Biopolus en 0,32 bij dat van Organica.

Nog een verschil met het voorgaande scenario is de noodzaak in het ontwerp van Organica om een koolstofbron te doseren. De BZV/N-verhouding in het influent is 3,9, terwijl dit in 4 à 5 zou moeten zijn. Bij navraag geeft Organica aan, dat koolstofdosering dit is toegevoegd om er zeker van te zijn dat stikstofverwijdering goed verloopt. Waarschijnlijk is toevoeging in de praktijk niet nodig.

RESTSTOFFENPRODUCTIE

De productie van reststoffen is te zien in Tabel 38. De slibproductie is berekend op basis van de productie bij 8°C (10°C ontwerpen Organica).

TABEL 38 RESTSTOFFENPRODUCTIE VAN DE ONTWERPEN

Onderdeel	Eenheid	Scenario Epe	Biopolus		Organica	
			Chem-P	Bio-P	Chem-P	Bio-P
Roostergoed	kg/d	n.b.	0,41	0,41	0,69	0,69
Zand	kg/d	n.b.	286,2	286,2	146	146
Slib	Kg d.s./d	1.982	1.380	1.499	1.880	1.740
Waarvan chemisch	Kg d.s./d	n.a.	139	n.a.	n.b.	n.b.
Planten biomassa	Kg d.s./j	n.a.	4.200	4.200	4.008	4.970

Een opvallend verschil bij de Biopolus ontwerpen tussen het voorgaande scenario en in dit scenario is dat de slibproductie met chemisch slib lager is dan bij het actiefslib ontwerp.

KOSTEN

De verwachte realisatiekosten staan in Tabel 39. Belangrijk om te vermelden, is dat het voor alle ontwerpen (Biopolus, Organica, OWT) gaat om een schatting van de kosten. De OWT heeft een uitgebreide detailberekening en maakt het gebruik van een toeslagfactor (70%). Ook voor de ontwerpen van Biopolus en Organica is de toeslagfactor berekend.

TABEL 39 VERWACHTE REALISATIEKOSTEN

Onderdeel	Scenario Epe	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Realisatie kosten zonder toeslagfactor	€ 7.224.118	€ 5.456.000	€ 6.137.000	€ 5.940.000	€ 6.401.000
Realisatie kosten met toeslagfactor (70%)	€ 12.281.000	€ 9.275.200	€ 10.432.900	€ 10.098.000	€ 10.881.700

De verwachte jaarlijkse kosten van energie, slibverwerking en chemicaliëngebruik staan in Tabel 40.

TABEL 40 VERWACHTE JAARLIJKSE KOSTEN

Onderdeel	Scenario Vriescheloo	Biopolus		Organica	
		Chem-P	Bio-P	Chem-P	Bio-P
Energie ¹	€/jaar	30.353	23.914	24.835	20.236
Slibverwerking ²	€/jaar	63.918	72.510	62.505	63.565
Metaalzouten ³	€/jaar	6.935	69.350		47.450
Totaal	€/jaar	101.206	165.774	87.340	131.251

¹ Op basis van reactor(en), prijs € 0,09 /kW

² € 322,50,-/ ton d.s. slibkoek (bron: Waterspiegel Unie van Waterschappen)

³ Metaalzout op basis van € 0,10 / mol Me³⁺ (bron: waterspiegel Unie van Waterschappen)

4.2.5 DISCUSSIE

De ontwerp partijen claimen in hun communicatie over hun system dat deze compacter en energiezuiniger zijn en dat zij minder slib produceren dan conventionele actiefslib systemen. De ontwerp vergelijkingen geven inzicht of deze claims waarheidsgetrouw zijn.

1. Oppervlaktebeslag

Gekeken naar de kern van de techniek, het biologische zuiveringsproces, zijn de volumes die de technieken vragen kleiner dan die van het conventionele systeem. In het Vriescheloo scenario is de grootste zuiverende kas 48% kleiner dan de actiefslib tank. In het Epe scenario is dit 27% kleiner. Een tweede aspect dat het oppervlak van deze systemen kleiner maakt is de nabehandeling. Dit is in beide ontwerpen een compacter systeem: een kleinere nabezink tank, D.A.F. of microzeef.

2. Energieverbruik

Bij het vergelijken van het energieverbruik is het van belang dat de juiste dingen met elkaar worden vergeleken met gelijke aannamen. De primaire zuivering (roosters, zandvanger e.d.) bijvoorbeeld, zijn in deze vergelijkingen verschillend. Door aannamen van de ontwerpers verbruikt de voorzuivering meer energie en komt het ongunstig uit in de totaal berekening. Andersom geldt hetzelfde voor de slibbehandeling. Het energieverbruik valt hoger uit bij het conventionele ontwerp. De belangrijkste vergelijking is die van het energieverbruik van de reactoren en dan met name de beluchting. Bij eerder ontwerpen kwam naar voren dat de zuiverende kassen meer energie verbruiken ten opzichte van het conventioneel ontwerp. Bij navraag kwam naar voren dat er een ongelijke zuurstoftransfercoëfficiënt was toegepast. Dit is een relevant aspect bij het type beluchtingssysteem. De ontwerpers van de zuiverende kassen maakten in hun berekeningen gebruik van buisbeluchters. De ontwerptool heeft als minst efficiënte systeem schotel beluchting. Het verschil tussen deze systemen is een $1,5 \text{ g O}_2/\text{Nm}^3$ lucht inbreng. Dit lijkt niet veel, maar geeft uiteindelijk een groot verschil in energieverbruik.

Het is aan de hand van deze ontwerpen nog niet geheel duidelijk of het systeem energiezuiniger is. De systemen met chemische fosfaatverwijdering zijn dat wel, maar bij de systemen met biologische fosfaatverwijdering is er verschil in ontwerp en energieverbruik. Het is aanneemelijk dat de hybride (IFAS) systemen een hoger energieverbruik hebben, omdat het te beluchten medium meer verontreinigingen bevat die de overdracht van zuurstof negatief beïnvloeden (gekoppeld aan de α factor). Maar waarom dit vele malen groter is bij de ene ontwerper dan de ander is niet duidelijk.

3. Slibproductie

Een opmerkelijk gegeven in deze vergelijking is dat een hybride (IFAS) systeem voor wat betreft slibproductie gunstiger is dan een puur systeem met alleen vastgehecht slib. Kijkend naar de scenario's onderling valt op dat bij een fabrikant de chemische fosfaatverwijdering ontwerpen in het ene scenario (Vriescheloo) meer slib produceert (hoofdzakelijk chemisch slib), maar in het andere scenario (ondanks de aanwezigheid van chemisch slib) minder dan in het conventionele ontwerp. Hierover is navraag gedaan bij de ontwerper. Volgens de ontwerper heeft dit te maken met de influentsamenstelling en hoe de dynamische simulatie tool hier mee omgaat. Deze tool, SUMO genaamd, gaat uit van breed scala aan variabelen, waaronder niet-biologisch afbreekbare componenten, de afbraaksnelheid van biologische componenten en predatiefactoren. Om het niet te complex te maken komt het neer op een netto slib aangroei per kg BZV in het influent. De statische OWT rekent in beide scenario's met een vaste slibaangroei van 0,65 kg d.s./kg BZV. De SUMO rekent in scenario Vriescheloo met 0,7 kg d.s./kg BZV

en in scenario Epe met 0,5 kg d.s./kg BZV. Uit de praktijkcijfers van South Pest en Etyek komt echter naar voren dat de slibproductie respectievelijk 1,10 en 1,45 kg d.s./kg verwijderd BZV is. Aanzienlijk hoger dus dan waar OWT en SUMO mee rekenen.

De claims van de fabrikanten worden middels deze vergelijking van ontwerpen grotendeels bevestigd. Daarbij moet in gedachten gehouden worden dat zowel de claims als de ontwerpen van de fabrikanten afkomstig zijn. De fabrikanten hebben echter geen inzicht gehad in of invloed kunnen uitoefenen op de uitkomsten van de OWT.

Het ziet ernaar uit dat de zuiverende kassen goedkoper zijn om te bouwen dan zuivering met conventionele actief slib systemen. Het gaat hier echter om ramingsbedragen die, hoewel vrij gedetailleerd, gemaakt zijn op basis van ontwerp. Het is onduidelijk of het verschil in praktijk ook zo groot zal zijn. Een factor die ook mee zou moeten wegen is de grondprijs. Niet alleen van de daadwerkelijke bouwgrond oppervlak, maar ook de resterende waarde van de omliggende gronden, inclusief hinderzone. Op beide aspecten springen zuiverende kassen er positief uit ten opzichte van conventionele actiefslibsystemen.

Kijkend naar de terugkerende kosten valt op dat de jaarlijkse kosten van de chemische fosfaatverwijderingsinstallaties hoger zijn dan die van het conventionele ontwerp. Dit wordt hoofdzakelijk veroorzaakt door de kosten van metaalzouten. De Bio-P-ontwerpen zijn in ieder geval bij het eerste scenario wel goedkoper in jaarlijks terugkerende kosten. In het 2^e scenario is dit voor het ontwerp van Organica niet te zeggen, dit hoofdzakelijk door de keuze om methanol te doseren.

Een ander aspect dat naar voren komt is de alternatieve nabehandeling ten opzichte van een nabezinktank. Dit type systemen biedt veelal de potentie om verdergaand na te zuiveren, bijvoorbeeld op een parameter zoals onopgeloste bestandsdelen. Vergaande verlaging van deze parameter komt ten gunste van in de toekomst eventueel noodzakelijke vierde zuiveringsstap(en) ten behoeve van verwijdering van microverontreinigingen.

In de kassen wordt plantenbiomassa geproduceerd. In bestaande installaties in het buitenland wordt dit vergist in een vergistingsinstallatie ter plekke of afgevoerd ter compostering.

Een belangrijk punt om te noemen is de effluentkwaliteit en gelijkheid van de ontwerpen. Waar Biopolus en de OWT effluent waarden weergeven gericht op altijd onder de de totaal stikstof eis en niet voortschrijdend zoals in het ontwerp van Organica. Bij temperaturen onder de 10 graden is de totaal stikstof in het effluent waarschijnlijk groter dan de eis. De installatie ontwerpen van Organica zou bij gelijke ontwerp temperatuur als de OWT en Biopolus groter zijn en meer beluchtingsenergie vragen.

Een tweede factor die van invloed is op het ontwerp, is het toepassen van een RWA - bypass. Deze ontwerpkeuze is gemaakt met de gedachte dat het water sterk genoeg verdunt bij RWA om direct te kunnen lozen op het oppervlaktewater. Hierdoor is het ontwerp van Organica niet 1 op 1 te vergelijken is met de andere twee ontwerpen.

4.2.6 CONCLUSIE

Op basis van deze theoretische ontwerpen is in ieder geval duidelijk dat deze systemen compacter zijn dan huidige conventionele actief slib systemen. De slibproductie is over algemeen lager (m.u.v. Biopolus chem-P in scenario Vriescheloo) en zo ook het energieverbruik

(m.u.v. Organica Bio-P-installaties). De afwijkende ontwerpen maken niet duidelijk of de installaties op alle punten een verbetering zijn ten aanzien van het actief slib systeem. Om de techniek op praktijkschaal te kunnen evalueren, zouden een of meer waterschappen gezamenlijk een of meer installaties kunnen realiseren waarin nader onderzoek wordt gedaan en ervaring wordt opgedaan.

4.3 CASE: STRIJP-S

4.3.1 ACHTERGROND

Strijp-S is een stedelijk district dichtbij het centrum van Eindhoven. Het is een voormalig industrieterrein van Philips van 30 ha. De gemeente wil het inrichten als een plek voor innovaties en experimenten in stedelijke ontwikkeling, technologie, ontwerp en kennis. In het gebied staat een aantal cultureel waardevolle gebouwen en objecten.

De transformatie van Strijp-S die nu gaande is zal resulteren in een gebied met een hoge dichtheid en een grote dynamiek. De historische gebouwen zijn gerenoveerd en huisvesten winkels, cafés, restaurants en bedrijven. Nieuwe woningen worden nu en in de toekomst gerealiseerd. Hierbij hoort ook een gezonde en vitale publieke groene ruimte.

Een van de experimenten zal zijn het realiseren van een lokale zuivering voor het ter plekke geproduceerde afvalwater.

In samenwerking met Waterschap De Dommel is door de Wageningen Universiteit onderzoek verricht naar de inpassing van een waterzuivering in het gebied ([4]). In dit onderzoek zijn drie typen waterzuivering betrokken:

- Een conventioneel actiefslib installatie
- Een Nereda installatie
- Een zuiverende kas (Biomakery van Biopolus)

De onderzoeks vragen waren:

- Wat zijn ontwerp criteria voor vergroting van ecosysteemdiensten en voor de integratie van een rwzi in publieke groene ruimten in steden?
- Welke ecosysteemdiensten kunnen worden versterkt door de integratie van een rwzi in publieke ruimten en welk type rwzi heeft de grootste potentie om ecosysteemdiensten te versterken?
- In welke mate levert de integratie van een rwzi in publieke groene ruimten een bijdrage aan de eisen van stakeholders?
- Hoe ziet een door de stakeholders ondersteunde oplossing voor de integratie van een rwzi in Strijp-S eruit?

4.3.2 VERGELIJKING

In het rapport is voor de drie typen rwzi gescoord op criteria. Deze worden hieronder weergegeven (Tabel 41).

TABEL 41 SCORES VAN EEN ACTIEF SLIB INSTALLATIE, EEN NEREDA INSTALLATIE EN EEN BIOMAKERY OP ECOSYSTEEMDIENSTEN IN STRIJP-S

Criterium		Actief slib	Nereda	Biomakery
Aanwezigheid van gebieden voor voedselproductie	--	Nee, onvoldoende ruimte	++ Ja, kan water leveren aan stadslandbouw	++ Ja, kan water leveren aan stadslandbouw
Retentiegebieden voor tijdelijke wateropslag	+/-	Ja, al passen bufferzones niet in stedelijke omgeving	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte
Biobrandstof, herbruikbaar organisch materiaal	-	Nee, onvoldoende ruimte	++ Ja, door stadslandbouw	++ Ja, door stadslandbouw
Mogelijkheden voor vermindering hitte-eilanden in de stad	+/-	Ja, binnen de bufferzone van de rwzi	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte
Retentiegebieden, infiltratiegebieden, doorlatende bestrating	--	Nee, onvoldoende ruimte	++ Ja, rwzi kan water leveren voor retentiegebieden	++ Ja, rwzi kan water leveren voor retentiegebieden
Vegetatie voor afvangen fijnstof, bomen als fysieke barrière	+/-	Ja, binnen de bufferzone van de rwzi	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte
Geluiddemping door band van dichte vegetatie	+/-	Ja, binnen de bufferzone van de rwzi	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte
Infiltratiegebieden voor neerslag	--	Nee, onvoldoende ruimte	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte
Ondooringbare gebieden, diverse vegetatie met hoge complexiteit	--	Nee, onvoldoende ruimte	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte
Goed toegankelijke publieke groene ruimte, ook voor recreatie	--	Nee, onvoldoende ruimte	+/- rwzi niet toegankelijk, ruimte eromheen wel	++ Ja, Biomakery is toegankelijk voor publiek
Stedelijke bossen en tuinen, semi-natuurlijke omgeving	--	Nee, onvoldoende ruimte	+/- rwzi niet toegankelijk, ruimte eromheen wel	++ Ja, Biomakery is toegankelijk voor publiek
Ontmoetingsplekken in groene ruimte	--	Nee, onvoldoende ruimte	+/- rwzi niet toegankelijk, ruimte eromheen wel	++ Ja, Biomakery is toegankelijk voor publiek
Stedelijke bossen en tuinen met een hoge ecologische waarde	--	Nee, onvoldoende ruimte	++ Ja, voldoende ruimte	++ Ja, voldoende ruimte

Uit de scores op mogelijkheden om ecosysteemdiensten in het gebied Strijper-S te vergroten scoort een Biomakery het best, gevolgd door een Nereda installatie. Een klassiek actief slibinstallatie biedt nauwelijks mogelijkheden.

4.3.3 CONCLUSIES

Uit de vergelijking zijn in het rapport ([4]) de volgende conclusies getrokken.

Het verkrijgen van draagvlak van bewoners voor het plaatsen van een rwzi in de nabije omgeving kan een probleem vormen. Voor veel mensen is de nabijheid van een rwzi geen prettig idee. Wanneer mensen denken aan een rwzi, dan zien zij een conventionele actiefslib installatie voor zich en het is goed te denkbaar dat een zuiverende kas tot een grotere acceptatie kan leiden. Alternatieve technieken en hun potentie om goed geïntegreerd te kunnen worden in de publieke groene omgeving zijn nieuw en onbekend. Goede communicatie naar bewoners over hoe nieuwe technieken zoals de Biomakery eruitzien en wat voor eigenschappen zij hebben, is daarom erg belangrijk.

5

CONCLUSIES

Zuiverende kassen lijken een visueel aantrekkelijk alternatief te zijn voor conventionele rwzi's. Zij lijken beter in de bebouwde omgeving of groene structuur eromheen te passen dan conventionele rwzi's en goed te combineren te zijn met sociale functies.

Bestaande installaties in het buitenland voldoen aan de daar geldende effluentnormen en functioneren soms al vele jaren naar verwachting. Bij gebrek aan ervaring in Nederland kan nog niet worden hardgemaakt dat zij ook onder de Nederlandse omstandigheden kunnen voldoen aan de in Nederland geldende effluentnormen van nu en van de toekomst.

Uit de casestudies en ontwerpen die Organica en Biopolus hebben gemaakt voor twee rwzi's komen de volgende conclusies:

1. Zuiverende kassen nemen minder ruimte in beslag dan conventionele rwzi's.
2. Het is aan de hand van deze ontwerpen nog niet geheel duidelijk of het systeem energiezijriger is. De systemen met chemische fosfaatverwijdering zijn dat wel, maar bij de systemen met biologische fosfaatverwijdering is er verschil in ontwerp en energieverbruik tussen de twee fabrikanten.
3. De slibproductie is in zuiverende kassen in het buitenland hoger dan die van actiefslib installaties in Nederland. Uit de ontwerpberkeningen van de fabrikanten en met OWT blijkt deze vergelijkbaar met of lager te zijn dan die van conventionele actiefslib installaties.
4. De constructiekosten voor zuiverende kassen zijn lager dan die voor een conventionele rwzi.
5. De jaarlijkse kosten van de chemische fosfaatverwijderingsinstallaties zijn hoger dan die van het conventionele ontwerp. Dit wordt hoofdzakelijk veroorzaakt door de kosten van metaalzouten. De Bio-P-ontwerpen zijn bij het scenario Vriescheloo wel goedkoper in jaarlijks terugkerende kosten. In het scenario Epe is dit voor het ontwerp van Organica niet te zeggen, dit hoofdzakelijk door de keuze om methanol te doseren.

Zuiverende kassen lijken een aantal voordelen te hebben boven conventionele rwzi's. Het verdient dan ook de aanbeveling om een of meer zuiverende kassen in Nederland te realiseren om de werking onder Nederlandse omstandigheden goed in kaart te brengen en te bestuderen of de door de fabrikanten opgegeven eigenschappen en kosten daadwerkelijk zijn zoals in dit rapport weergegeven. Belangrijke aspecten bij dit onderzoek zijn dan:

- Hoe presteren de systemen in de winter?
- Welke geuremissies zijn er in de praktijk?
- Hoe presteren de systemen onder regenrijke omstandigheden?
- Hoe verloopt de bedrijfsvoering in de praktijk en hoeveel werk is hiermee gemoeid?
- Hoeveel plantenbiomassa wordt geproduceerd en wat is de meest kostenefficiënte en duurzame manier om deze plantenbiomassa te benutten of te verwerken?
- Wat zijn in Nederland in de praktijk het energieverbruik, de slibproductie, de stichtingskosten en de operationele kosten?

- (Hoe) kunnen zuiverende kassen worden aangepast zodat zij beter aansluiten bij het streven naar energie- en grondstoffenterugwinning?
- (Hoe) kunnen zuiverende kassen worden aangepast zodat zij (beter) microverontreinigen zoals medicijnresten, gewasbeschermingsmiddelen en microplastics verwijderen?

6

LITERATUUR

1. Benedek, T., A. Táncsics, N. Szilágyi, I. Tóth, M. Farkas, S. Szoboszlay, C. Krifaton, M. Hartman & B. Kriszt (2014). Analysis of biofilm bacterial communities responsible for carbon removal through a reactor cascade treating wastewater, *World J Microbiol Biotechnol* (2014) 30:977-987
2. Hacquard, S., R. Garrido-Oter, A. González, S. Spaepen, G. Ackemann, S. Lebeis, A.C. McHardy, J.L. Dangl, R. Knight, R. Ley & P. Schulze-Lefert (2015). Microbiota and Host Nutrition across Plant and Animal Kingdoms, *Cell Host & Microbe* 17, May 13, 2015 Elsevier Inc.
3. Hazi F. (2016)*. Interview Metabolic Network reactor, Interviewer: D. Schellekens, Bezoek Biopolus op locatie: Záhony u. 7 1031 Budapest Hungary.
4. Hetem, V. (2016). Strijp-S Revived: A landscape design for public green space that integrates wastewater treatment. MSc Thesis, Landscape Architecture, Wageningen University.
5. Kenyeres I.(2014,2015,2016)*. Interview Metabolic Network reactor. Interviewers:D. Schellekens en A. Otte
6. Krizstina, P. & Á. Czaba (2016)*. Expert opinion about the Odor Measurement Implemented in the Greenhouses. Expert Opinion No. EO-16-164-01. KVI-Plusz Environmental Testing Office Ltd. Budapest.
7. Szilagyi, N., V. Szmolka, I. Kenyeres, Z. Csikor & R. Kovács (2009)*. PPCP removal potential from wastewater with a biofilm-based treatment technology, IWA conference manuscript, IWA-10330R1, 2009
8. Todd, J.H., M. Rome & L. Valle (ongedateerd). Summary of Ecomachines® performance data. John Todd Ecological Design Inc.
9. Todd, J. & B. Josephson (1996). The design of living technologies for waste treatment. *Ecological Engineering* 6 (1996) 109-136.
10. Todd, N.J. & J. Todd (1993). From Eco-Cities to Living Machines. *Principles of Ecological Design*. North Atlantic Books, Berkeley, California.
11. Varga P. (2014)*. Interview Food chain reactor, vragenlijst. Interviewer: D. Schellekens en A. Otte, Organica Water, Telefonisch overleg en contact via E-mail.

* Informatie van leverancier (Biopolus of Organica).

BIJLAGE 1

VRAGENLIJST

Living Machines, Food Chain Reactors and Bioprocessors are attracting more and more attention from the water boards in The Netherlands. But there still are a lot of questions to be answered before waste water engineers will adapt these techniques.

The water boards, united in STOWA, have started an extensive study on these technologies in order to gain more insight in these green treatment technologies. In this questionnaire questions, gathered from waste water engineers of 13 water boards, are grouped into categories. The engineers have stressed that they want data from existing plants. These data will be analyzed and evaluated and the results will be published in a publicly available report. The data analyses and writing of the report will be done by Bioniers.

As stated above, we would like the questions to be answered per plant. We kindly ask you to answer these questions for at least 5 existing treatment plants (sites). If data isn't available for this amount of plants, maybe you answer the questions for one or more plants on the drawing table.

On behalf of the water boards of The Netherlands, thank you for your cooperation and your time.

The first series of questions is treatment plant specific. Please answer the questions for every site.

SITE SPECIFIC QUESTIONS

GENERAL

- Give a short description of the system. What kind of components are involved? If available, add a drawing, schematic or leaflet.
- What kind of waste water is being treated?
- Where is the plant located?
- What is the net and gross area of the plant?
- How much cubic meter of waste water is treated per year?
- Since when is the plant in operation?
- In case of municipal waste water: does this include rain water? What is the average proportion of rain water of the total flow?

PRE-TREATMENT

- Is the waste water pre-treated? If so, what is that pre-treatment?
- If the waste water is filtered as pre-treatment: what is the minimum size of the captured particles? What happens next with the captured material?
- If the waste water is pre-treated: what is the efficiency of CZV and suspended solids removal?

LIVING MACHINE/FCR/BIOPROCESSOR

- What is the hydraulic retention time of the waste water in the system?
- We would like to have data of measurements (preferably measurements of several years) of:
 - Date of measurement
 - Incoming flow rate (m^3/hour or m^3/day)
 - BZV (in and out) (mg/l)
 - CZV (in and out) (mg/l)
 - Ammonia (in and out) (mg N/l)
 - Nitrite (in and out) (mg N/l)
 - Nitrate (in and out) (mg N/l)
 - Kjeldahl-N (in and out) (mg N/l)
 - Total N (in and out) (mg N/l)
 - Ortho-phosphate (in and out) (mg P/l)
 - Total phosphate (in and out) (mg P/l)
 - Metals (in and out) (concentrations)
 - Organic micro's (in and out) (concentrations)
- What treatment steps are there? Have you measured water quality parameters between those steps?
- How is phosphate being removed? Is it possible to include a biological P-removal step in the system?
- How much man power is used to keep the system going? Include labor like trimming the plants etc.
- How much air is being pumped into the system ($\text{m } \text{air}/\text{m treated water}$)? How much energy is being consumed by aeration? How is the aeration system maintained?
- What is the density of sludge in the system ($\text{g of sludge}/\text{m } \text{of water}$)? What is the dry matter content of the sludge (in suspension and attached to the roots/cloth)
- How many sludge is being produced (kg/year)?
- How are the plants maintained?
- What happens with plant parts that are cut off or have died off? Is there a market for plants grown in this treatment plant?
- How is the sludge being separated from the water?
- Are there measurements of air quality? If so, please provide them.

ODOR TREATMENT

- What kind of odor treatment is necessary for the different parts of the treatment plant (including pre-treatment and sludge treatment)?

POST-TREATMENT

- What kind of post-treatment is conducted on the effluent of the treatment plant?
- How is the sludge thickened and dewatered? What is the dry matter content after this step?
- What happens with the sludge (treatment)? Can this happen odor-free?

REUSE

- Is the effluent being reused? If so, what is it reused for? Is the water discharged on surface water?

COSTS AND BENEFITS

- What were the investment costs of the treatment plant?
- What are the yearly maintenance and operational costs?
- What are the yearly benefits and how are these generated?

The following questions aren't specific for treatment plants in use.

GENERAL QUESTIONS

LIVING MACHINE/FCR/BIOPROCESSOR


- Is the treatment suited for smaller plants (<20.000 p.e.)?
- Is the treatment plant suited for fluctuating flow rates, for example when a lot of rain water is being transported to the plant?)
- Is the plant suited for combining municipal waste water with industrial waste water?
- Can the system create local employment?
- Does the system contribute to closing loops (energy, water, resources)?
- Is the treated water suited or can it be made suitable for use as industrial process water or other purposes?
- Can the air in the greenhouse be polluted with Legionella, endotoxines or other harmful agents?
- Does H₂S from the wastewater get into the air?


SOCIAL ASPECTS

- Is the treatment plant suited for educational purposes? Is it open for the public?
- Are there any special facilities needed to make it possible to open the plant for the public? What are these facilities?

BIJLAGE 2

ONTWERPEN BIOPOLUS VRIESCHELOO





Technology Description

The following document describes the main biological treatment process steps and parameters for a Waste Water Treatment Plant in the Netherlands, with a design capacity of 2,800 m³/d. The process design was prepared by BIOPOLUS Technologies, Inc. for STOWA and Bioniers. The design is based on Biopolus's proprietary MNR (Metabolic Network Reactor) technology. The process parameters were determined using advanced dynamic simulations based on the data provided by the client.

This process sizing was executed based on a biofilm reactor scheme that applies chemical precipitation for phosphorus removal.

Design Basis


The technology design of the treatment facility is based on the data provided by STOWA. The main parameters of the influent water used in this design are as follows:

Denomination	Design	Unit
COD	623	mg O ₂ /l
BOD ₅	260	mg O ₂ /l
NH ₄ -N	51	mg N/l
TN	68	mg N/l
TP	10	mg P/l
TSS	197	mg TSS/l
Minimum influent wastewater temperature	8	°C
Flow	2,800	m ³ /d
Average Flow	116.6	m ³ /hr

The design parameters for the effluent are based on the following water quality specifications:

Denomination	Maximum	Unit
COD	125	mg O ₂ /l
BOD ₅	20	mg O ₂ /l
TN	15	mg N/l
TP	2	mg P/l
TSS	30	mg TSS/l

In the simulation the following diurnal flow distribution was assumed (based on provided data and experience):



Main Process Units

The designed process utilizes the following main units:

- 1) Pre-treatment
 - a) Fine screen
 - b) Grit and grease trap
- 2) Chemical dosage
 - a) Ca(OH)₂ (optional)
 - b) FeCl₃ or PAC
 - c) Polyelectrolyte
- 3) Biological treatment step with MNR reactor cascade
- 4) Phase separation: Microfiltration
- 5) UV disinfection (optional)
- 6) Sludge storage tank
- 7) Sludge dewatering: Dewatering belt filter-press

Process Parameters

Pre-treatment

For the biological treatment to function properly, fine screening, sand and grease removal are suggested as pre-treatment steps.

It is assumed that wastewater will be pumped to the pre-treatment units from where it can flow to the following steps by gravitation.

Screen

The screening unit is designed as a fine screen with screen waste washing, dewatering and compacting. The estimated daily waste generation is based on an exponential correlation between the experienced volume of screenings and the related opening size between screen bars. (See Metcalf & Eddy: Wastewater Treatment and Reuse; tables 5-7 to 5-8.) We calculated with a screen waste compaction ratio of 60 percent.

Denomination	Value	Unit
Opening size	3	mm
Specific volume of screenings	86	l/1000 m ³ water
Generated screen waste	241	l/d
Compaction ratio	0.6	l/l
Compacted screen waste	140	l/d

Sand and grease trap

The sand and grease trap is a horizontal flow design. It is aerated to avoid odor. Based on the influent characteristics, our calculation shows that approximately 15% of the influent TSS is inorganic. The horizontal flow sand trap efficiency is 90% for suspended inorganic solids.

Denomination	Value	Unit
Inorganic suspended solids removal ratio	0.9	-
Mass flow of influent inorganic TSS	74.5	kg/d
Mass flow of removed inorganic TSS	108	kg/d
Density of sand	2,000	kg/m ³
Sand trap waste	37	l/d

Chemical dosage

Increasing alkalinity (optional)

Low influent alkalinity concentration can slow down, and in some cases completely inhibit nitrification. If pH drops below 6, nitrification is significantly slowed. Denitrification can help to alleviate this effect to some extent. To avoid this process it may optionally be required to raise the alkalinity of the influent. In case the alkalinity is too low to maintain the nitrification efficiency, we recommend a 30 m/m% Ca(OH)₂ solution to be dosed after the sand trap.

Chemical Phosphorus Removal

Chemical Phosphorus precipitation is required to meet the effluent limits. This is achieved by dosing hydrous Ferric chloride solution (192.7 kg Fe/m³) prior to the Microfiltration unit.

Biological Treatment

The proposed solution consists of two parallel MNR cascade lines, each consisting of 6 tanks, for each line a total reactor volume of 960 m³, and a total reactor volume of 1,920 m³ for the entire plant. The design is operated with biofilm growing on the installed media. Due to the low TSS concentration, the aeration is much more effective than in conventional activated sludge reactors.

Further staging can be applied by non-concrete dividers within the reactors, providing a more sophisticated substrate gradient. The segmented construction ensures operational efficiency by creating the ideal environment in each compartment for the different processes.

The reactors should be equipped with piping to bypass any single reactor for easy and safe maintenance without shutting down the entire treatment plant. All reactors are designed to have a water depth of 6 m. For mixing, the anoxic reactors should be equipped with high efficiency propeller mixers. Meanwhile in the aerobic reactors, the right numbered and positioned tube-type fine bubble diffusers ensure the effective aeration and mixing.

In order to achieve a sufficient concentration of biomass, the reactors should be equipped with the patented biofilm carrier media inserts, with 51% volumetric fill ratio in all reactors. The artificial media developed by Biopolus – called Biopolus Artificial Root Package (ARP) – is designed for use in anoxic and aerobic tanks as well, in different setup to ensure the effectiveness and durability.

A split portion of the influent should be distributed to the 5th reactor at each cascade, with a volumetric flow of 450 m³/d per line. This distributes the carbon source for the anoxic zones more evenly, making denitrification more effective and requiring a lower flow rate of internal nitrate recycle.

Anoxic reactors

At each reactor cascade, the 1st and 5th reactors are designed as anoxic spaces with proper mixing and a volume of 96 m³. These reactors should be covered with a planted biofilter to ensure removal and neutralization of volatile organic compounds (VOC), thus preventing odors. The mixing should be managed with two high efficiency propeller mixers in each anoxic reactor. Each mixer has a built-in electric power of 0.9 kW. The media design in these reactors is the Biopolus ARP Model 2 type with a total height of 5 m to ensure the proper mixing.

Aerobic reactors

At each MNR cascade the 2nd-4th and 6th tanks are prepared for aerobic processes to implement nitrification, and the degradation of organic compounds. Each reactor is designed with a volume of 192 m³, and further staged into two compartments by non-concrete divider walls. These reactors could be opened or covered with plants on top, thus providing more surface and interaction to establish more effective biofilm growth.

These reactors are mixed by the intensive aeration. This mixing method allows to generate upwards streams with higher dissolved oxygen content throughout the media. The media set up for these reactors is the ARP Model 1 type.

From the last reactor, there is an internal nitrate recirculation flow back to the first anoxic reactor to ensure denitrification. The calculated recirculation flow rate is 1,400 m³/d at each line; and is 2,800 m³/d in total for the entire treatment plant.

The effluent water dissolved oxygen concentration is between 1.5-3.0 mg O₂/l.

The summarized reactor volumes are the following:

Denomination	Design	Unit
Anoxic reactor volume (per line)	192	m ³
Anoxic reactor volume (entire plant)	384	m ³
Aerobic reactor volume (per line)	768	m ³
Aerobic reactor volume (entire plant)	1,536	m ³
Total reactor volume	1,920	m³

Phase Separation

Microfiltration

We recommend two parallel drum-type microfiltration units for phase separation. The drumfilter has mechanical and self-cleaning system and offers large filter area on a small footprint. It is suitable for the filtration of wastewater with a TSS concentration up to 300 mg/l. In this design the wastewater leaving the MNR cascade has a suspended solid concentration of 192 mg/l. The provided effluent water TSS concentration will be below 30 mg/l. At a low TSS effluent value, the other effluent parameters, such as COD, BOD, TN or TP will be lower as well. The calculated sludge flow removed from the filter units is 70 m³/d with 9.2 kg/m³ TSS concentration.

UV disinfection (optional)

The low solids concentration of the effluent creates optimal conditions for disinfection by UV light.

Sludge Treatment

The sludge from phase separation should be dewatered on-site, then transported for disposal. The excess sludge should be forwarded to an aerated sludge storage tank before dewatering. After the dewatering the sludge is temporarily stored in closed and odor free containers. For the sludge amount calculation we took into consideration the sludge dewatering belt filter-press, assuming 25% dry solids content for the amount of 2.5 m³/d.

Technical and Operational Parameters

The most important technical and operational parameters of the plant, calculated based on dynamic modelling, are summarized below:

Biofilm Carrier Media

Based on Biopolus ARP Model 2 type media in anoxic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	51	%
Total filled volume	196	m ³

Based on Biopolus ARP Model 1 type media in aerobic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	51	%
Total filled volume	784	m ³

Aeration

The aeration requirement is calculated for the worst-case situation such as high influent flow and high water temperature.

Denomination	Design	Unit
Required aeration capacity	815	m ³ /h
Required aeration capacity	19,560	m ³ /d

The following airflows, and number of diffusers are required at the aerobic basins at each line:

MNR Aerobic A02 and B02	Design	Unit
Average air flow	125	m ³ /h
Number of diffuser tubes (2 per carrier)	80	pc
MNR Aerobic A03 and B03	Design	Unit
Average air flow	118	m ³ /h
Number of diffuser tubes (2 per carrier)	80	pc
MNR Aerobic A04 and B04	Design	Unit
Average air flow	58	m ³ /h
Number of diffuser tubes (2 per carrier)	80	pc
MNR Aerobic A06 and B06	Design	Unit
Average air flow	108	m ³ /h
Number of diffuser tubes (2 per carrier)	80	pc

Blowers

We calculated with the blower set up of 1+1+1 configuration. At each line, the running blower should be powered through a variable frequency drive to help to cover the required air flow range. The plus one is a common hot spare.

Diffusers

We suggest installing tube diffusers with the following properties:

Denomination	Design	Unit
Diffuser type	tube	
SOTE (Standard Oxygen Transfer Efficiency)	7	%/m
Diffuser membrane diameter	63	mm
Diffuser length	0.7	m/pc
Required average air flow rate per tube	4.9	m ³ /h/pc
Required maximum air flow rate per tube	8.4	m ³ /h/pc
Diffuser amount	640	pc
Installed aeration capacity	5,376	m ³ /h

Hydraulic Parameters

We designed two parallel MNR cascade reactor systems, each containing 6 reactors, with further internal staging in the aerobic tanks, effectively applying 10 reactor compartments in total.

The influent wastewater is pumped to the screen and from there the water flows through the technology units driven by gravity.

The summarized hydraulic parameters are the following:

Denomination	Design	Unit
Plant input flow	2,800	m ³ /d
Split flow to 5 th MNR reactor (per line)	450	m ³ /d
Split flow to 5 th MNR reactors (entire plant)	900	m ³ /d
Internal recirculation (per line)	1,400	m ³ /d
Internal recirculation (entire plant)	2,800	m ³ /d
RAS flow (entire plant)	0	m ³ /d
TSS mass flow entering the microfiltration unit	701	kg TSS/d
TSS concentration entering the microfiltration unit	192	g TSS/m ³
Microfiltration sludge flow	70	m ³ /d
TSS concentration of microfiltration sludge	9.2	kg TSS/m ³
TSS mass flow of microfiltration sludge	648	kg TSS/d
Dewatered sludge production	2.5	m ³ /d
Dry matter content of dewatered sludge	25	%
TSS mass flow of dewatered sludge	616	kg TSS/d
Biological sludge mass flow	526	kg TSS/d
Biological sludge production	0.698	kg TSS/kg BOD
Chemical sludge mass flow	90	kg TSS/d
Chemical sludge production	0.119	kg TSS/kg BOD
Total sludge production	0.818	kg TSS/kg BOD

Chemical Dosing

Phosphorous removal

While considering the chemical dosage for phosphorus removal, the amount of Fe³⁺ is the determinant for reaching the effluent limit. According to this, FeCl₃ should be used in an appropriate ratio.

Denomination	Design	Unit
FeCl ₃ dosing (per line)	0.18	m ³ /d
FeCl ₃ dosing (entire plant)	0.09	m ³ /d
Soluble Fe	192.7	kg Fe/m ³
Mass concentration	40	m/m%

Polyelectrolyte dosage

The polyelectrolyte dosage point is before the dewatering filter-press unit. The proper amount can be defined during the detailed design.

Denomination	Design	Unit
Specific polyelectrolyte dosage	5	g PE/kg TSS
Daily polyelectrolyte dosing (entire plant)	3.5	kg/d

Effluent Characteristics

Based on the dynamic computer simulation this process can produce the following effluent water quality at 8°C in a stable and safe manner:

Denomination	Maximum	Unit
COD	<55	mg O ₂ /l
BOD ₅	<6	mg O ₂ /l
NH ₄ -N	<1	mg N/l
TN	<15	mg N/l
TP	<2	mg P/l
TSS	<30	mg TSS/l

Technology Description

The following document describes the main biological treatment process steps and parameters for a Waste Water Treatment Plant in the Netherlands, with a design capacity of 2,800 m³/d. The process design was prepared by BIOPOLUS Technologies, Inc. for STOWA and Bioniers. The design is based on Biopolus's proprietary MNR (Metabolic Network Reactor) technology. The process parameters were determined using advanced dynamic simulations based on the data provided by the client.

This process sizing was executed based on a hybrid biofilm reactor scheme that applies enhanced biological phosphorus removal.

Design Basis


The technology design of the treatment facility is based on the data provided by STOWA. The main parameters of the influent water used in this design are as follows:

Denomination	Design	Unit
COD	623	mg O ₂ /l
BOD ₅	260	mg O ₂ /l
NH ₄ -N	51	mg N/l
TN	68	mg N/l
TP	9.6	mg P/l
TSS	197	mg TSS/l
Minimum influent wastewater temperature	8	°C
Flow	2,800	m ³ /day
Average Flow	116.6	m ³ /hr

The design parameters for the effluent are based on the following water quality specifications:

Denomination	Maximum	Unit
COD	125	mg O ₂ /l
BOD ₅	20	mg O ₂ /l
TN	15	mg N/l
TP	2	mg P/l
TSS	30	mg/l

In the simulation the following diurnal flow distribution was assumed (based on provided data and experience):



Main Process Units

The designed process utilizes the following main units:

- 1) Pre-treatment
 - a) Fine screen
 - b) Grit and grease trap
- 2) Chemicals dosage
 - a) Ca(OH)₂ (optional)
 - b) VFA (optional)
 - c) FeCl₃ or PAC (optional)
 - d) Polyelectrolyte
- 3) Biological treatment step with MNR reactor cascade
- 4) Phase separation
 - a) Dissolved air flotation
 - b) Microfiltration
- 5) Disinfection (optional)
- 6) Sludge thickening
- 7) Sludge storage tank
- 8) Sludge dewatering
 - Dewatering belt filter press

Process Parameters

Pre-treatment

For the biological treatment to function properly, fine screening, sand and grease removal are suggested as pre-treatment steps.

It is assumed that wastewater will be pumped to the pre-treatment units from where it can flow to the following steps by gravitation.

Screen

The screening unit is designed as a fine screen with screen waste washing, dewatering and compacting. The estimated daily waste generation is based on an exponential correlation between the experienced volume of screenings and the related opening size between screen bars. (See Metcalf & Eddy: Wastewater Treatment and Reuse; tables 5-7 to 5-8.) We calculated with a screen waste compaction ratio of 60 percent.

Denomination	Value	Unit
Opening size	3	mm
Specific volume of screenings	86	l/1000 m ³ water
Generated screen waste	299	l/d
Compaction ratio	0.6	l/l
Compacted screen waste	140	l/d

Sand and grease trap

The sand and grease trap is a horizontal flow design. It is aerated to avoid odor.

Based on the influent characteristics, our calculation shows that approximately 15% of the influent TSS is inorganic. The horizontal flow sand trap efficiency is 90% for suspended inorganic solids.

Denomination	Value	Unit
Inorganic suspended solids removal ratio	0.9	-
Mass flow of influent inorganic TSS	120	kg/d
Mass flow of removed inorganic TSS	108	kg/d
Density of sand	2,000	kg/m ³
Sand trap waste	37	l/d

Chemical dosage

Increasing alkalinity (optional)

Low influent alkalinity concentration can slow down, and in some cases completely inhibit nitrification. If pH drops below 6, nitrification is significantly slowed. Denitrification can help to alleviate this effect to some extent. To avoid this process it may optionally be required to raise the alkalinity of the influent. In case the alkalinity is too low to maintain the nitrification efficiency, we recommend a 30 m/m% Ca(OH)₂ solution to be dosed after the sand trap.

VFA dosage (optional)

With the current design and influent parameters, the plant will be able to meet the effluent discharge limits safely. However, the process is near to a carbon limited state, thus, the installation of a carbon dosing system at the anaerobic tanks is advised to allow safe operation of biological phosphorus removal. We propose using VFA as a carbon source (e.g. acetic-acid or equivalent).

Chemical Phosphorus Removal (optional)

Chemical precipitation is advised as a spare process to achieve the effluent TP limit, in case of difficulties with biological phosphorus removal. This is executed by dosing hydrous FeCl₃ in a static mixer before the microfiltration units.

Biological Treatment

The proposed solution consists of two parallel hybrid MNR cascade lines, each consisting of 7 reactors and one anoxic selector, for each line a total reactor volume of 1,115 m³, and a total reactor volume of 2,230 m³ for the entire plant. This design is operated with biofilm growing on the installed media and 994 mg MLSS/l in the liquid phase of the anaerobic, anoxic and aerobic reactors.

Further staging can be applied by non-concrete dividers within the reactors, providing a more sophisticated substrate gradient. The segmented construction ensures operational efficiency by creating the ideal environment in each compartment for the different processes. The reactors should be equipped with piping to bypass any single reactor for easy and safe maintenance without shutting down the entire treatment plant.

All reactors are designed to have a water depth of 6 m. For mixing, the anaerobic and anoxic reactors should be equipped with high efficiency propeller mixers. Meanwhile in the aerobic reactors, the right numbered and positioned tube-type fine bubble diffusers ensure the effective aeration and mixing.

In order to achieve a sufficient concentration of biomass, the anoxic and aerobic reactors should be equipped with the patented biofilm carrier media inserts, with 51% volumetric fill ratio. The artificial media developed by Biopolus – called Biopolus Artificial Root Package (ARP) – is designed for use in anoxic and aerobic tanks as well, in different setup to ensure the effectiveness and durability.

A split portion of the influent should be distributed to the 6th reactor at each cascade, with a volumetric flow of 400 m³/d. This distributes the carbon source for the anoxic zones more evenly, making denitrification more effective and requiring a lower flow rate of internal nitrate recycle.

Anaerobic reactors

At each line the 1st reactor is designed as an anaerobic space with a volume of 135 m³. In this reactor, negligible oxygen and nitrate concentration is required to enable the anaerobic fermentation and phosphorus release. To remove the nitrate-nitrogen content of the returned sludge, a pre-anoxic selector with a volume of 20 m³ is placed prior to each anaerobic reactor.

Sludge recirculation is a key parameter to keep a constant 994 mg MLSS concentration in the liquid phase of the reactors. Recycled sludge is led back from the DAF units to the anaerobic reactors. The calculated RAS flow rate is 202 m³/d at each line.

These reactors should be covered with a planted biofilter to ensure removal and neutralization of volatile organic compounds (VOC) thus preventing odors. Mixing should be executed with two high efficiency propeller mixers. Each mixer has a built-in electric power of 0.9 kW.

Anoxic reactors

At each reactor cascade, the 2nd and 6th reactors are designed as anoxic spaces with proper mixing and a volume of 96 m³. These reactors should be covered with a planted biofilter to ensure removal and

neutralization of volatile organic compounds (VOC), thus preventing odors. The mixing should be managed with two high efficiency propeller mixers in each anoxic reactor. Each mixer has a built-in electric power of 0.9 kW. The media design in these reactors is the Biopolus ARP Model 2 type with a total height of 5 m to ensure the proper mixing.

Aerobic reactors

At each MNR cascade the 3rd-5th and 7th tanks are prepared for aerobic processes to implement nitrification, and the degradation of organic compounds. Each reactor is designed with a volume of 192 m³, and further staged into two compartments by non-concrete divider walls. These reactors could be opened or covered with plants on top, thus providing more surface and interaction to establish more effective biofilm growth.

These reactors are mixed by the intensive aeration. This mixing method allows to generate upwards streams with higher dissolved oxygen content throughout the media. The media set up for these reactors is the ARP Model 1 type.

From the last reactor, there is an internal nitrate recirculation flow back to the first anoxic reactor to ensure denitrification. The calculated recirculation flow rate is 2,250 m³/d at each line; and is 4,500 m³/d in total for the entire treatment plant.

The effluent water dissolved oxygen concentration is between 1.5-3.0 mg O₂/l.

The summarized reactor volumes are the following:

Denomination	Design	Unit
Pre-anoxic selector volume (per line)	20	m ³
Pre-anoxic selector volume (entire plant)	40	m ³
Anaerobic reactor volume (per line)	135	m ³
Anaerobic reactor volume (entire plant)	270	m ³
Anoxic reactor volume (per line)	192	m ³
Anoxic reactor volume (entire plant)	384	m ³
Aerobic reactor volume (per line)	768	m ³
Aerobic reactor volume (entire plant)	1,536	m ³
Total reactor volume	2,230	m³

Phase Separation

The hybrid MNR reactors are designed to operate with a relatively low concentration of suspended solids (around 1,000 g/m³), the largest part of the biomass is attached to the biofiber media. To safely reach the effluent TSS limit, we propose a two-step phase separation solution with Dissolved Air Flotation and an additional Microfiltration.

Dissolved Air Flotation Unit

Biopolus recommends to use two parallel DAF units. The DAF effluent TSS concentration is below 100 mg/l. The calculated removed sludge flow is 213 m³/d per line. At higher hydraulic load the DAF efficiency will be lower but the output TSS concentration will be handled by the polishing effect of the microfilter. Our calculation shows that this set up provides the required separation capacity. The sludge dry material content is between 0.5 and 1%. Partially, the separated sludge is recycled back to the anaerobic tank in each line, and the wasted sludge is forwarded to thickening.

The DAF units also provide oil and grease removal by skimming, which pollutants can safely be removed after the biological treatment since they can no longer be utilised as a source of organic carbon.

Microfiltration

We recommend two parallel drum-type microfiltration units for secondary effluent polishing. The provided effluent water TSS concentration will be below 30 mg/l. At a low TSS effluent value, the other effluent parameters, such as COD, BOD, TN or TP will be lower as well. The calculated sludge flow removed from the filter units is 17.4 m³/d with 11.3 kg/m³ TSS concentration.

UV disinfection (optional)

The low solids concentration of the effluent creates optimal conditions for disinfection by UV light.

Sludge Treatment

The sludge from phase separation should be thickened and dewatered on-site, then transported for disposal. For thickening the wasted sludge, we suggest installing gravity belt thickeners. The thickened sludge should be forwarded to an aerated sludge storage tank before dewatering. After the dewatering the sludge is temporarily stored in closed and odor free containers. For the sludge amount calculation we took into consideration the sludge dewatering belt filter-press, assuming 25% dry solids content for the amount of 2.1 m³/d.

Technical and Operational Parameters

The most important technical and operational parameters of the plant, calculated based on dynamic modelling, are summarized below:

Biofilm Carrier Media

Based on Biopolus ARP Model 2 type media in anoxic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	51	%
Total filled volume	196	m ³

Based on Biopolus ARP Model 1 type media in aerobic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	51	%
Total filled volume	784	m ³

Aeration

The aeration requirement is calculated for the worst-case situation such as high influent flow and high water temperature.

Denomination	Design	Unit
Required aeration capacity	890	m ³ /h

Required aeration capacity	21,360	m ³ /d
----------------------------	--------	-------------------

The following airflows, and number of diffusers are required at the aerobic basins at each line – these figures are provided based on the average load of the facility:

MNR Aerobic A03 and B03	Design	Unit
Average air flow	225	m ³ /h
Number of diffuser tubes (2 per carrier)	80	
MNR Aerobic A04 and B04	Design	Unit
Average air flow	100	m ³ /h
Number of diffuser tubes (2 per carrier)	80	
MNR Aerobic A05 and B05	Design	Unit
Average air flow	20	m ³ /h
Number of diffuser tubes (2 per carrier)	80	
MNR Aerobic A07 and B07	Design	Unit
Average air flow	100	m ³ /h
Number of diffuser tubes (2 per carrier)	80	

Blowers

We calculated with the blower set up of 1+1+1 configuration. At each line, the running blower should be powered through a variable frequency drive to help to cover the required air flow range. The plus one is a common hot spare.

Diffusers

We suggest installing tube diffusers with the following properties:

Denomination	Design	Unit
Diffuser type		tube
SOTE (Standard Oxygen Transfer Efficiency)	7	%/m
Diffuser membrane diameter	63	mm
Diffuser length	0.7	m/pc
Required average air flow rate per tube	4.9	m ³ /h/pc
Required maximum air flow rate per tube	8.4	m ³ /h/pc
Diffuser amount	640	pc
Installed aeration capacity	5,376	m ³ /h

Hydraulic Parameters

We designed two parallel hybrid MNR cascade reactor systems, each containing 7 reactors, with further internal staging in the aerobic tanks, effectively applying 10 biofilm reactor compartments in total.

The influent wastewater is pumped to the screen and from there the water flows through the technology units driven by gravity.

The summarized hydraulic parameters are the following:

Denomination	Design	Unit
Plant input flow	2,800	m ³ /d
Split flow to 6 th MNR reactors (per line)	400	m ³ /d
Split flow to 6 th MNR reactors	800	m ³ /d
Internal recirculation (per line)	2,250	m ³ /d
Internal recirculation (entire plant)	4,500	m ³ /d
RAS flow (per line)	202	m ³ /d
RAS flow (entire plant)	404	m ³ /d
TSS mass flow entering the DAF units	2,711	kg TSS/d
TSS concentration entering the DAF units	994	g TSS/m ³
Sludge production of DAF units	426	m ³ /d
TSS mass flow of DAF sludge	2,417	kg/d
TSS concentration of DAF sludge	5.6	kg TSS/m ³
Sludge production of microfiltration units	17.4	m ³ /d
TSS concentration of microfiltration sludge	11.2	kg TSS/m ³
TSS mass flow of microfiltration sludge	196	kg/d
TSS mass flow entering the thickener unit	2,613	kg/d
Sludge production of the thickener unit	11.2	m ³ /d
TSS mass flow of thickener sludge	559	kg/d
TSS concentration of thickener sludge	50	kg TSS/m ³
Dewatered sludge production	2.1	m ³ /d
Dry matter content of dewatered sludge	25	%
TSS mass flow of dewatered sludge	531	kg/d
Biological sludge mass flow	531	kg/d
Biological sludge production	0.704	kg TSS/kg BOD
Chemical sludge mass flow	0	kg/d
Chemical sludge production	0	kg TSS/kg BOD
Total sludge production	0.704	kg TSS/kg BOD

Chemical Dosing

Polymer dosage

We recommend polyelectrolyte solution to be dosed prior to the thickener unit and the sludge dewatering unit. The proper amount can be defined during the detailed design.

Denomination	Design	Unit
Specific polyelectrolyte dosage	5	g PE/kg TSS
Polyelectrolyte dosage of thickener	3.1	kg/d
Polyelectrolyte dosage of dewatering unit	2.8	kg/d
Daily polymer dosing (entire plant)	5.9	kg/d


Effluent Characteristics


Based on the dynamic computer simulation this process can produce the following effluent water quality at 8°C in a stable and safe manner:

Denomination	Maximum	Unit
COD	<60	mg O ₂ /l
BOD	<5	mg O ₂ /l
NH ₄	<1	mg N/l
TN	<15	mg N/l
TP	<2	mg P/l
TSS	<30	mg TSS/l

BIJLAGE 3

ONTWERPEN BIOPOLUS EPE





Technology Description

The following document describes the main biological treatment process steps and parameters for a Waste Water Treatment Plant in the Netherlands, with a design capacity of 8,000 m³/d. The process design was prepared by BIOPOLUS Technologies, Inc. for STOWA and Bioniers. The design is based on Biopolus's proprietary MNR (Metabolic Network Reactor) technology. The process parameters were determined using advanced dynamic simulations based on the data provided by the client.

This process sizing was executed based on a biofilm reactor scheme that applies chemical precipitation for phosphorus removal.

Design Basis


The technology design of the treatment facility is based on the data provided by STOWA. The main parameters of the influent water used in this design are as follows:

Denomination	Design	Unit
COD	677.5	mg O ₂ /l
BOD ₅	279	mg O ₂ /l
NH ₄ -N	53	mg N/l
TN	71	mg N/l
TP	7.6	mg P/l
TSS	265	mg TSS/l
Minimum influent wastewater temperature	8	°C
Flow	8,000	m ³ /day
Average Flow	333	m ³ /hr

The design parameters for the effluent are based on the following water quality specifications:

Denomination	Maximum	Unit
COD	125	mg O ₂ /l
BOD ₅	20	mg O ₂ /l
TN	10	mg N/l
TP	2	mg P/l
TSS	30	mg TSS/l

In the simulation the following diurnal flow distribution was assumed (based on provided data and experience):



Main Process Units

The designed process utilizes the following main units:

- 1) Pre-treatment
 - a) Fine screen
 - b) Grit and grease trap
- 2) Chemical dosage
 - a) Ca(OH)₂ (optional)
 - b) FeCl₃ or PAC
 - c) Polyelectrolyte
- 3) Biological treatment step with MNR reactor cascade
- 4) Phase separation:
Microfiltration
- 5) UV disinfection (optional)
- 6) Sludge storage tank
- 7) Sludge dewatering
Dewatering belt filter-press

Process Parameters

Pre-treatment

For the biological treatment to function properly, fine screening, sand and grease removal are suggested as pre-treatment steps.

It is assumed that wastewater will be pumped to the pre-treatment units from where it can flow to the following steps by gravitation.

Screen

The screening unit is designed as a fine screen with screen waste washing, dewatering and compacting. The estimated daily waste generation is based on an exponential correlation between the experienced volume of screenings and the related opening size between screen bars. (See Metcalf & Eddy: Wastewater Treatment and Reuse; tables 5-7 to 5-8.) We calculated with a screen waste compaction ratio of 60 percent.

Denomination	Value	Unit
Opening size	3	mm
Specific volume of screenings	86	l/1000 m ³ water
Generated screen waste	688	l/d
Compaction ratio	0.6	l/l
Compacted screen waste	413	l/d

Sand and grease trap

The sand and grease trap is a horizontal flow design. It is aerated to avoid odor. Based on the influent characteristics, our calculation shows that approximately 15% of the influent TSS is inorganic. The horizontal flow sand trap efficiency is 90% for suspended inorganic solids.

Denomination	Value	Unit
Inorganic suspended solids removal ratio	0.9	-
Mass flow of influent inorganic TSS	318	kg/d
Mass flow of removed inorganic TSS	286	kg/d
Density of sand	2,000	kg/m ³
Sand trap waste	143	l/d

Chemical dosage

Increasing alkalinity (optional)

Low influent alkalinity concentration can slow down, and in some cases completely inhibit nitrification. If pH drops below 6, nitrification is significantly slowed. Denitrification can help to alleviate this effect to some extent. To avoid this process it may optionally be required to raise the alkalinity of the influent. In case the alkalinity is too low to maintain the nitrification efficiency, we recommend a 30 m/m% Ca(OH)₂ solution to be dosed after the sand trap.

Chemical Phosphorus Removal

Chemical Phosphorus precipitation is required to meet the effluent limits. This is achieved by dosing hydrous Ferric chloride solution (192.7 kg Fe/m³) prior to the Microfiltration unit.

Biological Treatment

The proposed solution consists of two parallel MNR cascade lines, each consisting of 6 tanks, for each line a total reactor volume of 3,300 m³, and a total reactor volume of 6,600 m³ for the entire plant. The design is operated with biofilm growing on the installed media. Due to the low TSS concentration, the aeration is much more effective than in conventional activated sludge reactors.

Further staging can be applied by non-concrete dividers within the reactors, providing a more sophisticated substrate gradient. The segmented construction ensures operational efficiency by creating the ideal environment in each compartment for the different processes.

The reactors should be equipped with piping to bypass any single reactor for easy and safe maintenance without shutting down the entire treatment plant. All reactors are designed to have a water depth of 6 m. For mixing, the anoxic reactors should be equipped with high efficiency propeller mixers. Meanwhile in the aerobic reactors, the right numbered and positioned tube-type fine bubble diffusers ensure the effective aeration and mixing.

In order to achieve a sufficient concentration of biomass, the reactors should be equipped with the patented biofilm carrier media inserts, with 53.4% volumetric fill ratio in the anoxic reactors and 51.5% volumetric fill ratio in the aerobic reactors. The artificial media developed by Biopolus – called Biopolus Artificial Root Package (ARP) – is designed for use in anoxic and aerobic tanks as well, in different setup to ensure the effectiveness and durability.

A split portion of the influent should be distributed to the 5th reactor at each cascade, with a volumetric flow of 1,375 m³/d per line. This distributes the carbon source for the anoxic zones more evenly, making denitrification more effective and requiring a lower flow rate of internal nitrate recycle.

Anoxic reactors

At each reactor cascade, the 1st and 5th reactors are designed as anoxic spaces with proper mixing and a volume of 450 m³, with staging into two compartments by non-concrete divider walls. These reactors should be covered with a planted biofilter to ensure removal and neutralization of volatile organic compounds (VOC), thus preventing odors. The mixing should be managed with two high efficiency propeller mixers in each anoxic reactor. Each mixer has a built-in electric power of 1.9 kW. The media design in these reactors is the Biopolus ARP Model 2 type with a total height of 5 m to ensure the proper mixing.

Aerobic reactors

At each MNR cascade the 2nd-4th and 6th tanks are prepared for aerobic processes to implement nitrification, and the degradation of organic compounds. Each reactor is designed with a volume of 600 m³, and further staged into three compartments by non-concrete divider walls. These reactors could be opened or covered with plants on top, thus providing more surface and interaction to establish more effective biofilm growth. These reactors are mixed by the intensive aeration. This mixing method allows to generate upwards streams with higher dissolved oxygen content throughout the media. The media set up for these reactors is the ARP Model 1 type.

From the last reactor, there is an internal Nitrate recirculation flow back to the first anoxic reactor to ensure denitrification. The calculated recirculation flow rate is 11,000 m³/d at each line; and is 22,000 m³/d in total for the entire treatment plant.

The effluent water dissolved oxygen concentration is between 1.5-3.0 mg O₂/l.

The summarized reactor volumes are the following:

Denomination	Design	Unit
Anoxic reactor volume (per line)	900	m ³
Anoxic reactor volume (entire plant)	1,800	m ³
Aerobic reactor volume (per line)	2,400	m ³
Aerobic reactor volume (entire plant)	4,800	m ³
Total reactor volume	6,600	m³

Phase Separation

Microfiltration

We recommend two parallel drum-type microfiltration units for secondary effluent polishing. The drumfilter has mechanical and self-cleaning system and offers large filter area on a small footprint. It is suitable for the filtration of wastewater with a TSS concentration up to 300 mg/l. In this design the wastewater leaving the MNR cascade has a suspended solid concentration of 200 mg/l. The provided effluent water TSS concentration will be below 20 mg/l. At a low TSS effluent value, the other effluent parameters, such as COD, BOD, TN or TP will be lower as well. The calculated sludge flow removed from the filter units is 158 m³/d with 9.1 kg TSS/m³ TSS concentration.

UV disinfection (optional)

The low solids concentration of the effluent creates optimal conditions for disinfection by UV light.

Sludge Treatment

The sludge from phase separation should be dewatered on-site, then transported for disposal. The excess sludge should be forwarded to an aerated sludge storage tank before dewatering. After the dewatering the sludge is temporarily stored in closed and odor free containers. For the sludge amount calculation we took into consideration the sludge dewatering belt filter-press, assuming 25% dry solids content for the amount of 5.5 m³/d.

Technical and Operational Parameters

The most important technical and operational parameters of the plant, calculated based on dynamic modelling, are summarized below:

Biofilm Carrier Media

Based on Biopolus ARP Model 2 type media in anoxic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	53.4	%
Total filled volume	960	m ³

Based on Biopolus ARP Model 1 type media in aerobic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	51.5	%
Total filled volume	2,470	m ³

Aeration

The aeration requirement is calculated for the worst-case situation such as high influent flow and high water temperature.

Denomination	Design	Unit
Required aeration capacity	2,800	m ³ /h
Required aeration capacity	67,200	m ³ /d

The following airflows, and number of diffusers are required at the aerobic basins at each line:

MNR Aerobic A02 and B02	Design	Unit
Average air flow	400	m ³ /h
Number of diffuser tubes (1 per carrier)	126	
MNR Aerobic A03 and B03	Design	Unit
Average air flow	375	m ³ /h
Number of diffuser tubes (1 per carrier)	126	
MNR Aerobic A04 and B04	Design	Unit
Average air flow	200	m ³ /h
Number of diffuser tubes (1 per carrier)	126	
MNR Aerobic A06 and B06	Design	Unit
Average air flow	425	m ³ /h
Number of diffuser tubes (1 per carrier)	126	

Blowers

We calculated with the blower set up of 1+1+1 configuration. At each line, the running blower should be powered through a variable frequency drive to help to cover the required air flow range. The plus one is a common hot spare.

Diffusers

We suggest installing tube diffusers with the following properties:

Denomination	Design	Unit
Diffuser type		tube
SOTE (Standard Oxygen Transfer Efficiency)	7	%/m
Diffuser membrane diameter	63	mm
Diffuser length	0.7	m/pc
Required average air flow rate per tube	4.9	m ³ /h/pc
Required maximum air flow rate per tube	8.4	m ³ /h/pc
Diffuser amount	1,008	pc
Installed aeration capacity	8,467	m ³ /h

Hydraulic Parameters

We designed two parallel MNR cascade reactor systems, each containing 6 reactors with further internal staging, effectively applying 16 reactor compartments in total.

The influent wastewater is pumped to the screen and from there the water flows through the technology units driven by gravity.

The summarized hydraulic parameters are the following:

Denomination	Design	Unit
Plant input flow	8,000	m ³ /d
Split flow to 5 th MNR reactors per line	1,375	m ³ /d
Split flow to 5 th MNR reactors (entire plant)	2,750	m ³ /d
Internal recirculation per line	11,000	m ³ /d
Internal recirculation (entire plant)	22,000	m ³ /d
RAS flow (entire plant)	0	m ³ /d
TSS mass flow entering the microfiltration unit	1,601	kg TSS/d
TSS concentration entering the microfiltration unit	200	g TSS/m ³
Microfiltration sludge flow	158	m ³ /d
TSS concentration of microfiltration sludge	9.1	kg TSS/m ³
TSS mass flow of microfiltration sludge	1,453	kg TSS/d
Dewatered sludge production	5.5	m ³ /d
Dry matter content of dewatered sludge	25	%
TSS mass flow of dewatered sludge	1,380	kg TSS/d
Biological sludge mass flow	1,241	kg TSS/d
Biological sludge production	0.460	kg TSS/kg BOD
Chemical sludge mass flow	139	kg TSS/d
Chemical sludge production	0.051	kg TSS/kg BOD
Total sludge production	0.512	kg TSS/kg BOD

Chemical Dosing

Phosphorous removal

While considering the chemical dosage for phosphorus removal, the amount of Fe³⁺ is the determinant for reaching the effluent limit. According to this, FeCl₃ should be used in an appropriate ratio.

Denomination	Design	Unit
FeCl ₃ flow rate (per line)	0.17	m ³ /d
FeCl ₃ flow rate (entire plant)	0.34	m ³ /d
Soluble Fe	192.7	kg Fe/m ³
Mass concentration	40	m/m%

Polymer dosage

The location of polymer dosage is before the sludge dewatering filter press unit. The proper amount can be defined during the detailed design.

Denomination	Design	Unit
Specific polyelectrolyte dosage	5	g PE/kg TSS
Daily polymer dosing (entire plant)	7.3	kg/d

Effluent Characteristics

Based on the dynamic computer simulation this process can produce the following effluent water quality at 8°C in a stable and safe manner:

Denomination	Maximum	Unit
COD	<60	mg O ₂ /l
BOD ₅	<8	mg O ₂ /l
NH ₄ -N	<1	mg N/l
TN	<8	mg N/l
TP	<2	mg P/l
TSS	<30	mg TSS/l

Technology Description

The following document describes the main biological treatment process steps and parameters for a Waste Water Treatment Plant in the Netherlands, with a design capacity of 8,000 m³/d. The process design was prepared by BIOPOLUS Technologies, Inc. for STOWA and Bioniers. The design is based on Biopolus's proprietary MNR (Metabolic Network Reactor) technology. The process parameters were determined using advanced dynamic simulations based on the data provided by the client.

This process sizing was executed based on a hybrid biofilm reactor scheme that applies enhanced biological phosphorus removal.

Design Basis


The technology design of the treatment facility is based on the data provided by STOWA. The main parameters of the influent water used in this design are as follows:

Denomination	Design	Unit
COD	677.5	mg O ₂ /l
BOD ₅	279	mg O ₂ /l
NH ₄ -N	53	mg N/l
TN	71	mg N/l
TP	7.6	mg P/l
TSS	265	mg TSS/l
Minimum influent wastewater temperature	8	°C
Flow	8,000	m ³ /day
Average Flow	333	m ³ /hr

The design parameters for the effluent are based on the following water quality specifications:

Denomination	Maximum	Unit
COD	125	mg O ₂ /l
BOD ₅	20	mg O ₂ /l
TN	10	mg N/l
TP	2	mg P/l
TSS	30	mg/l

In the simulation the following diurnal flow distribution was assumed (based on provided data and experience):



Main Process Units

The designed process utilizes the following main units:

- 1) Pre-treatment
 - a) Fine screen
 - b) Grit and grease trap
- 2) Chemicals dosage
 - a) Ca(OH)₂ (optional)
 - b) VFA (optional)
 - c) FeCl₃ or PAC (optional)
 - d) Polyelectrolyte
- 3) Biological treatment step with MNR reactor cascade
- 4) Phase separation
 - a) Dissolved air flotation
 - b) Microfiltration
- 5) Disinfection (optional)
- 6) Sludge thickening
- 7) Sludge storage tank
- 8) Sludge dewatering:
Dewatering belt filter press

Process Parameters

Pre-treatment

For the biological treatment to function properly, fine screening, sand and grease removal are suggested as pre-treatment steps.

It is assumed that wastewater will be pumped to the pre-treatment units from where it can flow to the following steps by gravitation.

Screen

The screening unit is designed as a fine screen with screen waste washing, dewatering and compacting. The estimated daily waste generation is based on an exponential correlation between the experienced volume of screenings and the related opening size between screen bars. (See Metcalf & Eddy: Wastewater Treatment and Reuse; tables 5-7 to 5-8.) We calculated with a screen waste compaction ratio of 60 percent.

Denomination	Value	Unit
Opening size	3	mm
Specific volume of screenings	86	l/1000 m ³ water
Generated screen waste	688	l/d
Compaction ratio	0.6	l/l
Compacted screen waste	413	l/d

Sand and grease trap

The sand and grease trap is a horizontal flow design. It is aerated to avoid odor. Based on the influent characteristics, our calculation shows that approximately 15% of the influent TSS is inorganic. The horizontal flow sand trap efficiency is 90% for suspended inorganic solids.

Denomination	Value	Unit
Inorganic suspended solids removal ratio	0.9	-
Mass flow of influent inorganic TSS	318	kg/d
Mass flow of removed inorganic TSS	286	kg/d
Density of sand	2,000	kg/m ³
Sand trap waste	143	l/d

Chemical dosage

Increasing alkalinity (optional)

Low influent alkalinity concentration can slow down, and in some cases completely inhibit nitrification. If pH drops below 6, nitrification is significantly slowed. Denitrification can help to alleviate this effect to some extent. To avoid this process it may optionally be required to raise the alkalinity of the influent. In case the alkalinity is too low to maintain the nitrification efficiency, we recommend a 30 m/m% Ca(OH)₂ solution to be dosed after the sand trap.

VFA dosage (optional)

With the current design and influent parameters, the plant will be able to meet the effluent discharge limits safely. However, the process is near to a carbon limited state, thus, the installation of a carbon dosing system at the anaerobic tanks is advised to allow safe operation of biological phosphorus removal. We propose using VFA as a carbon source (e.g. acetic-acid or equivalent).

Chemical Phosphorus Removal (optional)

Chemical precipitation is advised as a spare process to achieve the effluent TP limit, in case of difficulties with biological phosphorus removal. This is executed by dosing hydrous FeCl₃ in a static mixer before the microfiltration units.

Biological Treatment

The proposed solution consists of two parallel hybrid MNR cascade lines, each consisting of 7 reactors, for each line a total reactor volume of 3,465 m³, and a total reactor volume of 6,930 m³ for the entire plant. This design is operated with biofilm growing on the installed media and 600 mg MLSS/l in the liquid phase of the anaerobic, anoxic and aerobic reactors.

Further staging can be applied by non-concrete dividers within the reactors, providing a more sophisticated substrate gradient. The segmented construction ensures operational efficiency by creating the ideal environment in each compartment for the different processes. The reactors should be equipped with piping to bypass any single reactor for easy and safe maintenance without shutting down the entire treatment plant.

All reactors are designed to have a water depth of 6 m. For mixing, the anaerobic and anoxic reactors should be equipped with high efficiency propeller mixers. Meanwhile in the aerobic reactors, the right numbered and positioned tube-type fine bubble diffusers ensure the effective aeration and mixing.

In order to achieve a sufficient concentration of biomass, the anoxic and aerobic reactors should be equipped with the patented biofilm carrier media inserts, with 53.4% volumetric fill ratio in the anoxic tanks, and 51.5% fill ratio in the aerobic tanks. The artificial media developed by Biopolus – called Biopolus Artificial Root Package (ARP) – is designed for use in anoxic and aerobic tanks as well, in different setup to ensure the effectiveness and durability.

A split portion of the influent should be distributed to the 6th reactor at each cascade, with a volumetric flow of 1,375 m³/d. This distributes the carbon source for the anoxic zones more evenly, making denitrification more effective and requiring a lower flow rate of internal nitrate recycle.

Anaerobic reactors

At each line the 1st reactor is designed as an anaerobic space with a volume of 165 m³. In this reactor, negligible oxygen and nitrate concentration is required to enable the anaerobic fermentation and phosphorus release.

Sludge recirculation is a key parameter to keep a constant 600 mg MLSS concentration in the liquid phase of the reactors. Recycled sludge is led back from the DAF units to the anaerobic reactors. The calculated RAS flow rate is 116.5 m³/d at each line.

These reactors should be covered with a planted biofilter to ensure removal and neutralization of volatile organic compounds (VOC) thus preventing odors. Mixing should be executed with two high efficiency propeller mixers. Each mixer has a built-in electric power of 1.9 kW.

Anoxic reactors

At each reactor cascade, the 2nd and 6th reactors are designed as anoxic spaces with proper mixing and a volume of 450 m³, with staging into two compartments by divider walls. These reactors should be

covered with a planted biofilter to ensure removal and neutralization of volatile organic compounds (VOC), thus preventing odors.

The mixing should be managed with two high efficiency propeller mixers in each anoxic reactor. Each mixer has a built-in electric power of 1.9 kW.

The media design in these reactors is the Biopolus ARP Model 2 type with a total height of 5 m to ensure the proper mixing.

Aerobic reactors

At each MNR cascade the 3rd-5th and 7th tanks are prepared for aerobic processes to implement nitrification, and the degradation of organic compounds. Each reactor is designed with a volume of 600 m³, and further staged into three compartments by non-concrete divider walls. These reactors could be opened or covered with plants on top, thus providing more surface and interaction to establish more effective biofilm growth.

These reactors are mixed by the intensive aeration. This mixing method allows to generate upwards streams with higher dissolved oxygen content throughout the media. The media set up for these reactors is the ARP Model 1 type.

From the last reactor, there is an internal Nitrate recirculation flow back to the first anoxic reactor to ensure denitrification. The calculated recirculation flow rate is 9,000 m³/d at each line; and is 18,000 m³/d in total for the entire treatment plant.

The effluent water dissolved oxygen concentration is between 1.5-3.0 mg O₂/l.

The summarized reactor volumes are the following:

Denomination	Design	Unit
Anaerobic reactor volume (per line)	165	m ³
Anaerobic reactor volume (entire plant)	330	m ³
Anoxic reactor volume (per line)	900	m ³
Anoxic reactor volume (entire plant)	1,800	m ³
Aerobic reactor volume (per line)	2,400	m ³
Aerobic reactor volume (entire plant)	4,800	m ³
Total reactor volume	6,930	m³

Phase Separation

The hybrid MNR reactors are designed to operate with a relatively low concentration of suspended solids (600 g/m³), the largest part of the biomass is attached to the biofiber media. To safely reach the effluent TSS limit, we propose a two-step phase separation solution with Dissolved Air Flotation and an additional Microfiltration.

Dissolved Air Flotation Unit

Biopolus recommends to use two parallel DAF units. The DAF effluent TSS concentration is below 100 mg/l. The calculated removed sludge flow is 459 m³/d. At higher hydraulic load the DAF efficiency will be lower but the output TSS concentration will be handled by the polishing effect of the microfilter.

Our calculation shows that this set up provides the required separation capacity. The sludge dry material content is between 0.5 and 1%. Partially, the separated sludge is recycled back to the anaerobic tank in each line.

The DAF units also provide oil and grease removal by skimming, which pollutants can safely be removed after the biological treatment since they can no longer be utilised as a source of organic carbon.

Microfiltration

We recommend two parallel drum-type microfiltration units for secondary effluent polishing. The provided effluent water TSS concentration will be below 10 mg/l. At a low TSS effluent value, the other effluent parameters, such as COD, BOD, TN or TP will be lower as well. The calculated sludge flow removed from the filter units is 57 m³/d.

UV disinfection (optional)

The low solids concentration of the effluent creates optimal conditions for disinfection by UV light.

Sludge Treatment

The sludge from phase separation should be thickened and dewatered on-site, then transported for disposal. For thickening the wasted sludge, we suggest installing gravity belt thickeners. The thickened sludge should be forwarded to an aerated sludge storage tank before dewatering. After the dewatering the sludge is temporarily stored in closed and odor free containers. For the sludge amount calculation we took into consideration the sludge dewatering belt filter-press, assuming 25% dry solids content for the amount of 6.8 m³/d.

Technical and Operational Parameters

The most important technical and operational parameters of the plant, calculated based on dynamic modelling, are summarized below:

Biofilm Carrier Media

Based on Biopolus ARP Model 2 type media in anoxic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	53.4	%
Total filled volume	960	m ³

Based on Biopolus ARP Model 1 type media in aerobic reactors:

Denomination	Design	Unit
Media length	5	m
Fill ratio (volume)	51.5	%
Total filled volume	2,470	m ³

Aeration

The aeration requirement is calculated for the worst-case situation such as high influent flow and high water temperature.

Denomination	Design	Unit
Required aeration capacity	3,226	m ³ /h
Required aeration capacity	77,424	m ³ /d

The following airflows, and number of diffusers are required at the aerobic basins at each line:

MNR Aerobic A02 and B02	Design	Unit
Average air flow	525	m ³ /h
Number of diffuser tubes (2 per carrier)	126	
MNR Aerobic A03 and B03	Design	Unit
Average air flow	425	m ³ /h
Number of diffuser tubes (1 per carrier)	126	
MNR Aerobic A04 and B04	Design	Unit
Average air flow	225	m ³ /h
Number of diffuser tubes (1 per carrier)	126	
MNR Aerobic A06 and B06	Design	Unit
Average air flow	438	m ³ /h
Number of diffuser tubes (1 per carrier)	126	

Blowers

We calculated with the blower set up of 1+1+1 configuration. At each line, the running blower should be powered through a variable frequency drive to help to cover the required air flow range. The plus one is a common hot spare.

Diffusers

We suggest installing tube diffusers with the following properties:

Denomination	Design	Unit
Diffuser type		tube
SOTE (Standard Oxygen Transfer Efficiency)	7	%/m
Diffuser membrane diameter	63	mm
Diffuser length	0.7	m/pc
Required average air flow rate per tube	4.9	m ³ /h/pc
Required maximum air flow rate per tube	8.4	m ³ /h/pc
Diffuser amount	1,008	pc
Installed aeration capacity	8,600	m ³ /h

Hydraulic Parameters

We designed two parallel hybrid MNR cascade reactor systems, each containing 7 reactors, with further internal staging in the anoxic and aerobic tanks, effectively applying 16 biofilm reactor compartments in total.

The influent wastewater is pumped to the screen and from there the water flows through the technology units driven by gravity.

The summarized hydraulic parameters are the following:

Denomination	Design	Unit
Plant input flow	8,000	m ³ /d
Split flow to 6 th MNR reactors (per line)	1,375	m ³ /d
Split flow to 6 th MNR reactors	2,750	m ³ /d
Internal recirculation (per line)	9,000	m ³ /d
Internal recirculation (entire plant)	18,000	m ³ /d
RAS flow (per line)	116.5	m ³ /d
RAS flow (entire plant)	233	m ³ /d
TSS mass flow entering the DAF units		kg TSS/d
TSS concentration entering the DAF units	600	g TSS/m ³
Sludge production of DAF units	459	m ³ /d
TSS mass flow of DAF sludge	3,534	kg/d
TSS concentration of DAF sludge	7.7	kg TSS/m ³
Sludge production of microfiltration units	57	m ³ /d
TSS concentration of microfiltration sludge	4.8	kg TSS/m ³
TSS mass flow of microfiltration sludge	278	kg/d
TSS mass flow entering the thickener unit	1,753	kg/d
Sludge production of the thickener unit	31.6	m ³ /d
TSS mass flow of thickener sludge	1,578	kg/d
TSS concentration of thickener sludge	50	kg TSS/m ³
Dewatered sludge production	6.0	m ³ /d
Dry matter content of dewatered sludge	25	%
TSS mass flow of dewatered sludge	1,499	kg/d
Biological sludge mass flow	1,499	kg/d
Biological sludge production	0.556	kg TSS/kg BOD
Chemical sludge mass flow	0	kg/d
Chemical sludge production	0	kg TSS/kg BOD
Total sludge production	0.556	kg TSS/kg BOD

Chemical Dosing

Polymer dosage

We recommend polyelectrolyte solution to be dosed prior to the sludge dewatering unit. Dosing before the primary phase separation process should be avoided due to the sludge recirculation. The proper amount can be defined during the detailed design.

Denomination	Design	Unit
Specific polyelectrolyte dosage	5	g PE/kg TSS
Polyelectrolyte dosage of thickener	8.8	kg/d
Polyelectrolyte dosage of dewatering unit	7.9	kg/d
Daily polymer dosing (entire plant)	16.7	kg/d


Effluent Characteristics

Based on the dynamic computer simulation this process can produce the following effluent water quality at 8°C in a stable and safe manner:

Denomination	Maximum	Unit
COD	<60	mg O ₂ /l
BOD ₅	<7	mg O ₂ /l
NH ₄ -N	<1	mg N/l
TN	<10	mg N/l
TP	<2	mg P/l
TSS	<30	mg TSS/l

BIJLAGE 4

ONTWERPEN ORGANICA VRIESCHELOO




SITE PLAN

1:200

Scale:




- GENERAL NOTES:**
- No proposed slope shall exceed three(3) horizontal to one (1) vertical. U.N.O.
 - All utilities (manholes, valve covers etc) shall be adjusted to final grade prior to the final lift of asphalt.
 - All landscape islands shall have a crown of clean native soils prior to landscaping.
 - Construction shall comply with all applicable governing codes and be constructed to same.
 - Traffic should be divided for trucks and cars/pedestrians.
 - There should be proper location of pedestrian circulation facilities as required in the project.



Project ID: NL01256L	Type of Design: Concept Design	Issued By: OT
Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)	Design Title: Site Plan	Drawing No.: A2
Location: Netherlands	Designed By: Anubhav Agarwal	Approved By: Nicolas Rizo
Scale: 1:200	Date: 17.02.2017	Revision: 1


Revised or updated documents supersede previous documents that were issued under the previous design. This document is intended for Organica Water Inc. internal use only. It is prohibited to photocopy or otherwise reproduce this document without permission from Organica Water Inc. This document is controlled under the classification and documentation system of Organica Water Inc. All rights reserved. Organica Water Inc. reserves the right to change the design at any time without notice. Organica Water Inc. does not accept responsibility for any damage or loss resulting from the use of this document. Organica Water Inc. retains the copyright to this document. All correspondence to original Organica Water Inc. shall be addressed to the Organica Water Inc. office in the Netherlands. All correspondence to original Organica Water Inc. shall be addressed to the Organica Water Inc. office in the Netherlands. All correspondence to original Organica Water Inc. shall be addressed to the Organica Water Inc. office in the Netherlands.

Organica Water Inc.
61 Princeton-Hightstown Road, Suite 3A
Princeton Junction, NJ 08550 USA
Phone: +1(609)6188855
Fax: +1(609)6188919
www.organicawater.com



GENERAL NOTES:

1. Building position : considered to provide to the maximum extent possible a zero balance earthwork.
2. Scope of material shall be verified by contractor prior to the onset of work at site.
3. Exact location of walls, windows and doors shall be verified with project manager.
- 4 . Construction shall comply with all applicable governing codes and be constructed to same.
5. All dimensions are from the face of finished wall to face of finished wall U.N.O.
- 6 . All equipments should be installed in accordance with the manufacturer's specifications.



TYPICAL PART PLAN OF FCR REACTORS TOP (SCALE 1:50)




Scale: 1:200

REUSE OF DOCUMENTS: Present design document has been prepared by Organica Water, Inc. and/or its
(OT) - Organica. This document including its ideas and design concepts belong to Organica. Such documents are the sole property of Organica and are confidential. They may not be reproduced, copied, distributed or disclosed without the prior written consent of Organica. All rights reserved.
Organica is a registered trademark of Organica Water, Inc. and/or its (OT) - Organica.
PDF format, native formats are issued exclusively for design support purposes. Only English language versions of the Documents shall be considered as original. Organica reserves the right to make any changes to the English language version of the Documents. All versions shall be considered as official Documents. Only the English language version of the Documents shall have no liability for any translation of the English language version of the Documents. All trademarks displayed are registered marks of Organica, protected by the relevant law.
© Organica Water, Inc. 2017



Project ID:	NL01256L	Project Name:	STOWA Study - Plant 1 WWTP (2.8 MLD)
Type of Design:	Concept Design	Issued by:	OT
Designed by:	Anubhav Agarwal	Approved by:	Nicolas Rizo
Checked by:			
Drawing Title:	Floor Plan - Upper Level	Drawing Number:	NL01256L-A-011-003
Scale:	1:200	Drawing Size:	A3
Date:	17.02.2017	Revision:	1






REUSE OF DOCUMENTS: Present design document has been prepared by Organica Water, Inc. and/or its subsidiaries, including any controlled subsidiaries thereof (including, but not limited to Organica Technologie Zt. (CT), (Organica). This document including the ideas and design incorporated herein and any derivative document, not to be copied, reproduced, or distributed without the expressed written permission of Organica Water, Inc. and/or its subsidiaries, shall not be reproduced, stored in retrieval systems, or transmitted, in whole or in part, without prior written authorization of Organica. In addition to the above, no part of this document may be reproduced, stored in retrieval systems, or transmitted, in whole or in part, without prior written authorization of Organica. Organica documents are transmitted in native and PDF format, native formats and usage exclusively for design support purposes. Only the English language version of the documents shall be considered official. Organica shall never be liable for any damages resulting from the use of any version other than the English language version of the documents. All rights reserved. Organica Water, Inc. and/or its subsidiaries are registered trademarks of Organica Water, Inc., prepared by the relevant offices in accordance with applicable law. Organica is a registered trademark of Organica Water, Inc. 2017. © Organica Water, Inc.		Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)	Scale: N.T.S.
		Drawing Title: Renders	Drawing Size: A3
Designed by: Anubhav Aggarwal	Approved by: Nicolas Rizo	Issued by: OT	Date: 17.02.2017
			Revision: 1
			Drawing Number: NL01256L-A-019-001



LEGEND


INFLUENT	—
SLUDGE	- - - - -
EFFLUENT	—
CLEANWATER	—
FILTRATE	—
CHEMICALS	-----
SOLID WASTE	++
GAS	+
AIR	++
PUMP	○○○○
SLUDGE PUMP	○○○○



Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)		
Drawing Scheme		Date
Organic	13.02.2017	Expedited Drawing
Project Number: P-011-001	13.02.2017	As Per Design
Drawing Scale: A1	1:1	Scale
Author: Jörg Röhl	Changer by: Jörg Röhl	Type of Drawing:
Reviewer: Jörg Röhl	Approver: Jörg Röhl	Project Manager:
Revision: Revision 1	Review Date: 13.02.2017	Issue to Client
Reason: Basic Design	Description: Revised drawing	Responsible

REINHOLD OTTERHOFF
Engineering

Print: 10/02/2017 10:24:41 | Page: 10 | Version: 2.0 | Page No.: 10 | Project: STOWA Study - Plant 1 WWTP (2.8 MLD) | Process Scheme 01





Technical Description

Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)

Document Number: NL01256L-P-091-001

Revision: 2

Contents

1	Introduction.....	3
2	General Introduction to Organica FCR	3
2.1	Advantages of the FCR Solution	3
2.1.1	Lower suspended solids concentration (MLSS) offers phase separation alternatives	4
2.1.2	Lower suspended solids concentration (MLSS) improves energy efficiency	4
2.1.3	Increased biomass concentration	4
2.1.4	Eliminated requirement for sludge recirculation (RAS)	4
2.1.5	Longer effective solids retention time (SRT).....	4
2.1.6	Elimination of sludge “bulking” and “washout”	4
2.1.7	Compact facility consumes less space	5
2.1.8	Plant roots provide are ideal biofilm carriers.....	5
3	Design Basis	5
4	Preliminary Design – Unit Operations	6
	Process overview	6
4.1	Pre-Treatment Units	7
	Fine Screen	7
	Grit Removal	7
4.2	Secondary Biological Treatment – Organica FCR	7
	FCR Reactors.....	7
	Process Aeration	8
4.3	Phase Separation	8
	Chemical Phosphorus Removal/Coagulation.....	8
	Secondary Clarification	8
4.4	Disinfection	8
	UV Disinfection	8
4.5	Solids Management	9
	Sludge storage Tank	9
	Combined Thickening/Dewatering Unit.....	9
	Polymer System.....	9
5	Control system	10
5.1	Instrumentation and Control	10



5.2	Display Panel, Event Log.....	10
5.3	Control and Variables	10
5.4	Remote Access	10
5.5	Main Intervention Points.....	10

1 Introduction

This technical description outlines the proposed Organica solution for the **STOWA Study - Plant 1** wastewater treatment facility (WWTF) in **Amsterdam, the Netherlands**. As outlined below, average design capacity of the proposed facility is **2,800 m³/d**.

Organica solutions utilize a Food Chain Reactor (FCR) configuration, consisting of biological treatment in successive reactor zones utilizing fixed biomass on a combination of natural plant roots and Organica's engineered biofiber media, along with a limited amount of suspended biomass.

This document is structured as follows:

- Organica FCR general introduction
- Design basis - influent flow and characterization with treated effluent requirements
- Preliminary design information by unit process
- Description of the control system

2 General Introduction to Organica FCR

Organica FCR solutions consist of a series of biological treatment zones simultaneously utilizing both fixed biofilm and suspended biomass in the reactors. Biodegradation of influent contaminants is accomplished by the combination of fixed and suspended biological cultures. Biomass in the Organica FCR is primarily fixed-film, utilizing natural plant roots along with additional engineered (biofiber) media as biofilm carriers. As a standard feature of the solution, the basins may be covered by an attractive enclosure to protect the "botanical garden" as needed.

As influent travels through the FCR zones, the available organics and nutrients (various carbon, nitrogen, and phosphorus fractions) are consumed and/or transformed. As a result, the composition of the ecosystem fixed in the biofilm changes from zone to zone, gradually adapting to localized conditions as the organic and nutrient concentrations vary, as well as dissolved oxygen content. The end result is a specially-adapted ecosystem in each zone, acclimatized to the specific conditions to maximize treatment efficiency.

2.1 Advantages of the FCR Solution

A significant fraction of microorganisms responsible for biodegradation is in fixed-film form (attached growth). Benefits of fixed-film solutions include:

- Mixed liquor suspended solids (MLSS) concentrations significantly lower than conventional activated sludge systems; resulting in:
 - Improved aeration & mixing efficiency (reducing energy requirements)
 - Flexible phase-separation alternatives, including option of direct filtration (without clarifiers) to conserve space
- Increased concentration of active biomass in the treatment zones
- Eliminated requirement for sludge recirculation (RAS)
- Longer effective SRT (sludge age); resulting in more complex organisms with longer lifecycles (unicellular cilia, larvae, arthropods) establishing themselves on the biofilm
- Eliminated potential for biomass "washout"
- Significant reduction in biological reactor space requirements

These benefits are described in further detail below.

2.1.1 Lower suspended solids concentration (MLSS) offers phase separation alternatives

With the primary biomass in fixed-film form, solids concentration in suspended form (MLSS) is reduced. While conventional secondary clarification designs can also be utilized effectively, lower MLSS solids concentrations allow the option of direct filtration of the FCR effluent with a Disc Filter. Disc Filters offer drastically reduced space requirements, in addition to a positive barrier for solids capture and thus more reliable effluent quality.

2.1.2 Lower suspended solids concentration (MLSS) improves energy efficiency

Lower suspended solids concentrations (MLSS) reduce viscosity of the reactor liquid, requiring less mixing energy. Further, lower viscosity fluids have enhanced diffusion properties resulting in a higher oxygen mass transfer coefficient ("alpha" value), significantly improving aeration efficiency. The combination of reduced mixing demand and improved aeration efficiency results in significantly less energy consumption.

2.1.3 Increased biomass concentration

Due to the properties of the plant roots and the biofilm carrier arrangement, a special biofilm structure develops on both the natural and engineered media. This improved biofilm structure provides a higher concentration of biomass compared to other biofilm-based technologies. Depending upon project specifics, a total biomass concentration of 8 to 15 kg/m³ can be achieved, three to five times higher than conventional activated sludge systems. As a result, reactor volume can be drastically reduced.

2.1.4 Eliminated requirement for sludge recirculation (RAS)

Another advantage of Organica's fixed-film solution is elimination of the requirement for sludge recirculation (RAS). The excess biosolids removed in secondary phase separation are forwarded directly to the sludge handling system. Elimination of the RAS simplifies the process, while also eliminating the capital and operating costs of the pumping system and associated piping.

2.1.5 Longer effective solids retention time (SRT)

With the vast majority of the biomass in fixed form and without sludge (RAS) recirculation, the biomass can reach effectively higher sludge ages (SRT's) in a limited reactor volume. Higher SRT's provide significant advantages with respect to nitrification as they enable better retention of slow-growing autotrophic bacteria (nitrifiers) in the system, with reduced risk of "washout" in peak flow events. Additionally, higher SRT's enable complex organisms with longer lifecycles (unicellular cilia, worms, arthropods, etc.) to establish themselves in the biofilm. The more complex organisms are generally slower growing and also tend to be "predatory" (consuming more basic organisms resident in the system), resulting in lower net sludge production. Further, many of these species have demonstrated the ability to break down a wider range of substrates and more complex compounds (such as pharmaceuticals).

2.1.6 Elimination of sludge "bulking" and "washout"

Conventional activated sludge systems commonly see filamentous sludge "bulking" as a result of various specific operating conditions. Filamentous bacteria are the main cause of sludge bulking and proliferate mainly in suspended growth conditions. In FCR reactors, suspended growth accounts for only a small fraction of the total biomass, thus significantly reducing the growth opportunity for filamentous organisms and the potential for sludge bulking. Further, biomass "washout" from the system during high flow conditions is impossible with the majority of biomass attached to the carriers.

2.1.7 Compact facility consumes less space

Higher biomass concentrations result in significantly reduced reactor volumes and space requirements. In addition, the lower suspended solids concentration allows the potential of direct filtration for phase separation, without the use of clarifiers, thus providing further opportunity to reduce the overall space requirements for the facility.

2.1.8 Plant roots provide are ideal biofilm carriers

- Plant root specific surface area is an order of magnitude higher than most artificial carrier media, resulting in higher concentrations of active biomass.
- Plant roots are not susceptible to clogging, thus reducing operational risk.
- Plants excrete small amounts of organic acids from their root surfaces which act as a food source for the biofilm. This is of high importance when the influent organic load is low. This symbiotic relationship helps bacteria to survive starvation periods, resulting in a larger and more diverse population of bacteria in the system when the wastewater load is re-established. As a result, FCR facilities have far greater flexibility compared to conventional activated sludge systems.
- Utilization of marsh plants (reeds, sedges, bulrushes, etc.) transport oxygen to their roots and increase biofilm activity.
- Plant roots provide a better habitat for slow-growing species, such as nitrifiers and eukaryotic organisms, resulting in improved nutrient removal performance over conventional processes.

3 Design Basis

Based on the information provided to Organica and certain assumptions made by Organica, Table 1 below shows the influent characteristics and effluent limits used as the design basis.

Table 1. Influent characteristics and effluent limits used as design basis

Parameters	Influent Characteristics	Units	Effluent Limits	Units
Design average flow ($Q_{Average}$)	2,800	m ³ /d	-	m ³ /d
Design rainy weather peak flow (Q_{RWA})	470	m ³ /h	-	m ³ /h
Design peak to Biology ($Q_{Peak to Biology}$)	350	m ³ /h	-	m ³ /h
COD	623	mg/l	< 125	mg/l
BOD ₅	260	mg/l	< 20	mg/l
Total Suspended Solids (TSS)	197	mg/l	< 30	mg/l
Total Kjeldahl Nitrogen (TKN)	68	mg/l	-	mg/l
Total Nitrogen (TN)	-	mg/l	< 15	mg/l
Total Phosphorus (TP)	10	mg/l	< 2	mg/l
Design minimum wastewater temperature (T_{min})	10.1	°C	-	°C
Design maximum wastewater temperature (T_{max})	25	°C	-	°C

For process design considerations, it is assumed that all effluent compliance requirements are absolute (not monthly or annual averages). If monthly or annual average/median are reported or other deviations are allowed, potential savings are possible. Please contact Organica for further refinement of the design if needed.

4 Preliminary Design – Unit Operations

This section provides preliminary design information for the proposed treatment unit processes.

The main unit processes are:

- Pre-Treatment
 - Fine screen and grit removal - designed to treat Q_{RWA} ($470 \text{ m}^3/\text{h}$)
- Biological Treatment
 - FCR multi-zone reactor with 6 zones in each reactor train
- Secondary Phase Separation
 - Coagulation
 - Secondary clarifier
- Disinfection
 - UV disinfection - designed to treat Q_{RWA} ($470 \text{ m}^3/\text{h}$)
- Solids Management
 - Sludge storage tank
 - Sludge thickening and dewatering

Process overview

The Process Scheme accompanying this document provides a schematic of the above unit processes as well as the flow connectivity between them.

As shown in the process scheme, influent flows to the fine screen and aerated grit chamber (pre-treatment) where solids removal takes place. After pre-treatment, flow is directed to the FCR reactors for biological treatment. The FCR is capable to treat flows up to $350 \text{ m}^3/\text{h}$. Peak flows above the limit will be bypassed.

A biological treatment facility with one FCR train is proposed.

To provide biological nitrogen removal, varying degrees of aeration are used through the reactor zones to create both anoxic and aerobic microbe environments. Anoxic zones are the primary location for denitrification where conversion of nitrate into nitrogen gas occurs – nitrate is used as the electron acceptor for organic matter degradation in this zone. Denitrification takes place both in the suspended phase and in the fixed-film, particularly the “deeper” layers of the biofilm where anoxic conditions are present.

Following the anoxic stages, aerobic zones provide organic matter degraders, nitrifiers and higher organisms in both suspended and attached phases to provide degradation of organic compounds and conversion of ammonia to nitrate. To complete the denitrification process, a recycle of aerobic zone fluids to the anoxic zones is required to provide nitrates to the anoxic zones. Throughout both the anoxic and aerobic zones, fine-bubble aeration is used to provide mass transfer (oxygen) and mixing to keep any free solids in suspension.

Wastewater flows from the FCR reactor zones to a coagulation tank, where polyaluminum-chloride (PAC) is added to achieve the required effluent phosphorus limit via solids removal.

Wastewater flows from the coagulation tank to the secondary clarifier unit which gravity-settles the suspended biomass and inert solids to achieve the required effluent TSS limits.

Elimination of pathogens by UV-radiation takes place before discharge. The UV chamber is designed to be able to handle 470 m³/h peak flow.

The excess sludge from the clarifier is pumped to a sludge storage tank where air is introduced to avoid anaerobic, septic conditions. From the tank the sludge is directed to a combined thickening/dewatering unit where poly-electrolyte is introduced to improve dewatering processes. The dewatered sludge will be put in containers for further processing. The filtrate from the unit will be sent back to the biology.

4.1 Pre-Treatment Units

Fine Screen

Fine screening is utilized to remove objects prior to the treatment process. These objects are generally inert plastics and other debris that cannot be broken down in biological treatment.

Table 2.Techical Specification of Fine Screens

Item/Parameter	Value	Unit
Opening size	3	mm
Total screenings volume	241	l/d

Grit Removal

Grit removal captures sand, grit, and other fine material that is non-biodegradable prior to biological treatment.

Table 3.Techical Specification of Grit Removal

Item/Parameter	Value	Unit
Number of grit removal basins	1	-
Volume of one basin	24	m ³
Grit removal basin type	Aerated	-
Total air requirement	250	Nm ³ /h
Total grit quantity	140	l/d
Total grease quantity	18	l/d

4.2 Secondary Biological Treatment – Organica FCR

As described above, biological treatment will occur through a series of FCR reactor zones.

FCR Reactors

To provide sufficient habitat for the fixed-film process utilized in FCR solutions, sufficient retention time and surface area will be provided.

Table 4.Techical Specification of Organica FCR reactors

Item/Parameter	Value	Unit
Total volume of reaction zones per train	1,898	m ³
Number of reaction zones per train	6	-
Numbers of trains	1	-
Total Biofiber Media area per train	35,280	m ²
Plant racks per train	95.6	m ²

Process Aeration

Aeration is provided in the FCR zones to maintain mixing and provide sufficient oxygen in the anoxic and aerobic process described previously.

Table 5.Process Aeration Technical Specification

Item/Parameter	Value	Unit
Process air demand (min)	990	Nm ³ /h
Process air demand (average)	1,100	Nm ³ /h
Process air demand (max)	1,190	Nm ³ /h

4.3 Phase Separation

Chemical Phosphorus Removal/Coagulation

Prior to solids separation, chemical coagulation with PAC addition will be utilized for efficient removal of suspended particles, as well as phosphorus precipitation where required.

Table 6.Techical Specification of Chemical Phosphorus Removal/Coagulation

Item/Parameter	Value	Unit
Total PAC usage	280	l/d
Total volume of coagulation tank	3	m ³

Secondary Clarification

Clarification is provided to allow a quiescent settling zone where suspended solids are gravity-settled to the bottom of the clarifier. Settled solids are then pumped directly to the solids handling and dewatering processes.

Table 7. Basic Secondary Clarification Information

Item/Parameter	Value	Unit
Number of units	1	pcs
Side Water Depth	4	m
Surface of one clarifier	175	m ²

4.4 Disinfection

UV Disinfection

Through passage of UV light into the water, inactivation of bacteria, viruses, and protozoa is accomplished.

4.5 Solids Management

Sludge storage Tank

A sludge storage tank is provided as a buffer to allow intermittent operation of the downstream dewatering equipment.

Table 8. Technical Specification of sludge storage tank

Parameters	Value	Unit
Total Volume of Sludge storage tank	52	m ³
Mixing air requirement	26	Nm ³ /h

Combined Thickening/Dewatering Unit

Sludge flow from the sludge storage tank is directed to the combined thickening and dewatering unit.

Table 9. Technical Specification of combined thickening and dewatering unit

Item/Parameter	Value	Unit
Sludge flow from thickening and dewatering	2.7	m ³ /d
Dry solids content	20	%w/w

Polymer System

Polyelectrolyte is added through various unit processes to optimize solids separation performance.

Table 10. Minimum Design Capacities of Polymer Systems

Item/Parameter	Value	Unit
Sludge thickening and dewatering	4.6	kg/d

5 Control system

The wastewater treatment facility utilizes a PC-PLC based process control system with custom-engineered control software. It integrates the acquisition, display, and storage of operational data, as well as the input and application of operational variables.

5.1 Instrumentation and Control

The design provides appropriate instruments and sensors, as required, for proper operation and control of the system. In general, flow is measured by electromagnetic meters and/or derived from level sensors. Dissolved oxygen probes are provided for monitoring of dissolved oxygen at appropriate locations. Other additional sensors such as instrumentation for online measurement of ammonia, nitrate, or phosphorus may be included in the design as needed depending on the effluent requirements and operational needs. Variable Frequency Drives (VFDs) are provided for pump or blower speed control where necessary. Electromagnetic or pneumatic actuators are provided for valve operation or modulation where necessary. Key equipment is controlled by one or more PLCs, which monitor their status through feedback channels and display on the control application program.

5.2 Display Panel, Event Log

The application program that runs on the PC is adapted and customized to the technology. Its function is to gather, display, print and store information in addition to the implementation of operator commands and settings. The program provides all stored information in a processed and readable format, readily accessible to operators.

The real-time technical parameters (status of equipment, measured values) are displayed on the flowchart of the application program. These values are stored in a central database, which is accessible through charts and summary tables. Changes of technological settings, failures, alarms, and equipment status are stored in the event log.

5.3 Control and Variables


The PLC supervisory program controls the automatic operation of equipment. The automatic operation can be altered by using the commands of the application program or modifying the control parameters. Initial values for these parameters are set during the design of each facility. However, a high level of flexibility is provided for modification of these parameters in the event that actual operating conditions or the influent characteristics differ from those used in the original design.

5.4 Remote Access

Internet and mobile technologies play an essential role in the operation of the facility. Remote access to the control panel and logged data enables technologists to observe and intervene in the treatment process when necessary.


5.5 Main Intervention Points

The most important intervention point is aeration control in the cascade reactors - the PC-PLC system controls the blowers by variable frequency drives thus enabling it to maintain a range from 0.2 – 5 mg/L dissolved oxygen level in the FCR reactors to optimize kinetics of the biological process, while balancing energy consumption. This control logic is based upon measurement of dissolved oxygen through probes installed in the FCR reactors.



GENERAL NOTES:

- No proposed slope shall exceed three (3) horizontal to one (1) vertical. U.N.O.
- All utilities (manholes, valve, covers etc) shall be adjusted with all applicable governing codes and be constructed to final grade prior to the final lift of asphalt.
- All landscape islands shall have a crown or clean native soils prior to landscaping.
- Traffic should be divided for trucks and cars/pedestrians.
- There should be proper location of pedestrian circulation facilities as required in the project.



Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)	Drawing Title: Site Plan	Issued by: OT
Date: 02/03/2017	Revision: 1	Drawn by: Nicolsak
Reviewed by: Tamás Somssák	Approved by: Nicolsak	Designated by: OCS
Comments: None	Comments: None	Comments: None


NOTICE OF DOCUMENTS: This document is the intellectual property of Organica Water, Inc. All rights reserved. No part of this document may be reproduced without written permission from Organica Water, Inc. This document is intended for internal use only and is not to be distributed outside of Organica Water, Inc. Any unauthorized use, disclosure, copying, distribution, or modification of this document is strictly prohibited. Organica Water, Inc. reserves the right to pursue legal action against any individual or entity that violates the terms of this notice. All correspondence regarding this document should be directed to Organica Water, Inc., Attention: Legal Department, P.O. Box 21, Princeton-Hightstown Road, Suite 3A, Princeton Junction, NJ 08545 USA. Tel: +1(609)513-8885, Fax: +1(609)513-8889, E-mail: info@organicawater.com. Organica Water, Inc. is a registered trademark of Organica Water, Inc. All other trademarks and service marks are the property of their respective owners.



Comments: None

GENERAL NOTES:

1. Building position : considered to provide to the maximum extent possible a zero balance earthwork.
2. Scope of material shall be verified by contractor prior to the onset of work at site.
3. Organica FCR typical Layout shall be applicable for all design.
- 4 . All concrete structure shall be considered as waterproof concrete and shall be in accordance as per local available standards and codes
5. All dimensions are from the face of finished wall to face of finished wall U.N.O.
6. All equipments should be installed in accordance with the manufacturer's specifications.



TYPICAL PART PLAN OF FCR REACTOR'S BOTTOM SCALE 1:50

Scale: 1:200


RE-USE OF DOCUMENT: Present document has been prepared by Organica Water, Inc. and/or its subsidiaries including any controlled subsidiaries hereof (including, but not limited to Organica Technologies Zrt., Organica Water, Inc. and Organica Water, Inc. (Ottó)) (hereinafter referred to as "Organica"). This document contains the ideas and design incorporated therein and any derivative work thereon. All rights are reserved. Organica and its controlled subsidiaries are the sole owners of the intellectual property of this document. Such documents are confidential and may not be reproduced or disclosed without prior written authorization of Organica. In case documents are transmitted both in native and PDF format, native formats are issued exclusively for design purposes. Only English language version of the documents shall be considered as original. Organica shall have no liability for any translation of the English language version of the documents. Translations displayed are registered marks of Organica, protected by the relevant laws of the United States of America and/or other countries. © Organica Water, Inc. 2017.

Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)	Issued by: OT	Scale: 1:200
Drawing Title: Floor Plan - Lower Level		Drawing Size: ISO full bleed A3
Drawing Number: NL01256L-A-011-002	Approved by: Nicolás Rizo	Date: Revision: 02/03/2017 1
Designed by: OCS	Checked by: Tamás Somsák	



GENERAL NOTES:


1. Building position : considered to provide to the maximum extent possible a zero balance earthwork.
2. Scope of material shall be verified by contractor prior to the onset of work at site.
3. Exact location of walls, windows and doors shall be verified with project manager.
- 4 . Construction shall comply with all applicable governing codes and be constructed to same.
5. All dimensions are from the face of finished wall to face of finished wall U.N.O.
6. All equipments should be installed in accordance with the manufacturer's specifications.



TYPICAL PART PLAN OF FCR REACTOR'S TOP (SCALE 1:50)


RE-USE OF DOCUMENTS: Present design document has been prepared by Organica Water, Inc. and/or its subsidiaries including any controlled subsidiaries hereof (including, but not limited to Organica Technogalak Zrt., Organica Water, Inc., and Organica Water, Inc. (Organica) and its design incorporated herein and any derivative work or work based thereon). This document includes the design and specification of equipment, structures and facilities for the sole benefit of Organica. Such documents are the property of Organica and shall not be reproduced without written authorization from Organica.		Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)		Scale: 1:200
		Drawing Title: Floor Plan - Upper Level		Drawing Size: ISO full bleed A3
		Checked by: Tamás Somsák	Approved by: Nicolás Rizo	Date: 02/03/2017 Revision: 1
		Designed by: OCS	Issued by: OT	
		Location: Netherlands	Client: Aan de Stegge	
		Address: 61 Princeton-Hightown Road, Suite 3A, Princeton Junction, NJ 08550 USA	Address: 61 Princeton-Hightown Road, Suite 3A, Princeton Junction, NJ 08550 USA	
		Tel: +1 6096518885 Fax: +1 6096518889	Tel: +1 6096518885 Fax: +1 6096518889	
		E-mail: info@organicawater.com	E-mail: info@organicawater.com	
		Organica Water, Inc. © 2017	Organica Water, Inc. © 2017	
		ORGANICA	ORGANICA	


- GENERAL NOTES:**
1. External wall detail shall be typical for all building design.
 2. Coping profile shall be provided on building top as per the typical detail provided in this sheet.
 3. Organica FCR typical Layout shall be applicable for all design.
 - 4 . All concrete structure shall be considered as waterproof concrete and shall be in accordance as per local available standards and codes.
 5. All dimensions are from the face of finished wall to face of finished wall U.N.O.
 6. Greenhouse structure shall be of galvanised steel framework.



GREENHOUSE OVER BIO-MODULE DESIGN (SCALE 1:50)

Project Name:	STOWA Study - Plant 1 WWTP (2.8 MLD)	Drawing Title:	GREENHOUSE OVER BIO-MODULE DESIGN (SCALE 1:50)
Scale:	1:200	Drawing Size:	ISO full bleed A3
Issued by:	OT	Approved by:	Nicolas Rizo
Type of Design:	Concept Design	Designed by:	Tomas Somsak OCS
Client:	Organica Water, Inc.	Location:	61 Princeton-Hightown Road, Suite 3A, Princeton Junction, NJ 08550 USA Netherlands
DISCLAIMER: This document has been prepared by Organica Water, Inc. and/or its subsidiaries including Organica Water, Inc., without limitation to Organica Technologies, Zn, Inc. and/or its design incorporated herein and any derivative work or design based thereon. Organica Water, Inc. and/or its subsidiaries are not responsible for any errors or omissions in this document. Such documents are for information purposes only and are not intended to be relied upon as engineering designs or recommendations. They are not to be reproduced or distributed without prior written authorization of Organica Water, Inc. and/or its subsidiaries. This document is the sole property of Organica Water, Inc. and/or its subsidiaries and is not to be copied or distributed without prior written permission. Organica Water, Inc. and/or its subsidiaries are not responsible for any errors or omissions in this document. Such documents are for information purposes only and are not intended to be relied upon as engineering designs or recommendations. They are not to be reproduced or distributed without prior written authorization of Organica Water, Inc. and/or its subsidiaries. This document is the sole property of Organica Water, Inc. and/or its subsidiaries and is not to be copied or distributed without prior written permission.			
	ORGANICA	Copyright © Organica Water, Inc. 2017.	





Valve symbols	Pumps	Air Handling	Meters	Instrumentation Designation
	Centrifugal Pump		Vertical Staff Meter	
	Dosing Pump		Straightened Meter	
	Screw Pump		Static Meter	
	Propeller Pump			
Actuator symbols				
Tank/Vessel	Tank/Vessel	Filtration	Clarifier	Heating Equipment
Screening				Miscellaneous symbols
Filtration				
Clarifier				
Heating Equipment				

Project Name:	STOWA Study Plant 1 WWTP (2.8 MLD)		
Drawing Title:	Process and Instrumentation Diagram Legend		
Revision Number:	01	Issue to Client	01
Revision Date:	01/03/2017	Revised Description	Issued to
Printed By:	Client: Amt für Abwasser		
Designated by:	Project Manager: Alexander Schmid		
Starter Sheet:	Page 1 of 1	Page 1 of 1	Page 1 of 1
Printed On:	01/03/2017		
Scale:	1		



Technical Description

Project Name: STOWA Study - Plant 1 WWTP (2.8 MLD)

Document Number: NL01256L-P-091-002

Revision: 1

Contents

1	Introduction.....	2
2	General Introduction to Organica FCR	2
2.1	General overview of the proposed solution	2
2.2	Advantages of Hybrid (Attached + Suspended Growth) Systems.....	3
2.3	Advantages of Plant Roots as Biofilm Carriers	3
3	Design Basis.....	4
4	Preliminary Design – Unit Operations	4
	Process overview	5
4.1	Pre-Treatment Units	5
	Fine Screen	5
	Grit Removal	6
4.2	Secondary Biological Treatment – Organica FCR	6
	FCR Reactors.....	6
	Process Aeration	6
4.3	Phase Separation	7
	Secondary Clarification	7
4.4	Disinfection	7
	UV Disinfection.....	7
4.5	Solids Management	7
	Sludge storage Tank	7
	Combined Thickening/Dewatering Unit.....	7
	Polymer System	7
5	Control system	8
5.1	Instrumentation and Control	8
5.2	Display Panel, Event Log.....	8
5.3	Control and Variables	8
5.4	Remote Access	8
5.5	Main Intervention Points.....	8

1 Introduction

This technical description outlines the proposed Organica solution for the **STOWA Study - Plant 1** wastewater treatment facility (WWTF) in **Amsterdam, the Netherlands**. As outlined below, average design capacity of the proposed facility is **2,800 m³/d**.

Organica solutions utilize a Food Chain Reactor (FCR) configuration, consisting of biological treatment in successive reactor zones utilizing fixed biomass on a combination of natural plant roots and Organica's engineered biofiber media, along with a limited amount of suspended biomass.

This document is structured as follows:

- Organica FCR general introduction
- Design basis - influent flow and characterization with treated effluent requirements
- Preliminary design information by unit process
- Description of the control system

2 General Introduction to Organica FCR

2.1 General overview of the proposed solution

The proposed system is an implementation of the Organica Food Chain Reactor (FCR) Solution in a hybrid arrangement (i.e. suspended growth in coexistence with fixed film) which consists of biological wastewater treatment in successive reactors using both suspended biomass and fixed biomass on both natural (plant root) and artificial (patented biofibre media) root structures.

The system's main features are as follows:

- The solution provides organic matter and nutrient removal;
- The solution produces less excess sludge than conventional biological processes;
- The treatment plant extensively uses fixed biomass cultivated on both natural (plant root) and artificial (patented biofibre media) root structures i.e. it is a hybrid solution that exploits all the advantages of fixed film biomass and suspended growth.

In an Organica Hybrid FCR WWTP there is a series of biological reactors where suspended biomass is maintained in every stage of the process, fixed biofilm are used only in the aerated reactor zones. The suspended growth biomass is maintained by a RAS system (return activated sludge) from secondary clarifiers back to the FCRs.

Biodegradation of influent contaminants takes place mainly with the help of fixed and suspended biological cultures, where plant roots are used as biofilm carriers. Additional biofibre media is used in the reactors as artificial plant roots to provide more surface area for biofilm to form and grow on.

In a typical Organica FCR system, as the influent travels through the cascade, the available nutrient quantity is consumed and as a result, the composition of the ecosystem fixed in the biofilm changes from reactor to reactor, gradually adapting itself to the decreasing nutrient concentrations. In each cascade stage a specially adapted ecosystem will form, thus maximizing the decomposition of contaminants.

2.2 Advantages of Hybrid (Attached + Suspended Growth) Systems

- Attached growth in hybrid systems inherently have longer sludge ages than in purely suspended growth systems. Therefore, higher organisms with longer lifecycles (unicellular cilia, worms, arthropods) will establish themselves in hybrid systems. The formation of such a complex ecosystem enables a wider spectrum of organics to be broken down. This effect leads to the lower residual COD level in the effluent.
- Due to the multilevel food-chains that are present in complex ecosystems, the bacteria that process waste material are consumed by other organisms, which are in turn prey for higher predators within the food chain. As a final outcome the yield of the biomass, and consequently the amount of the waste sludge, is lower.
- Since in hybrid systems the majority of biomass responsible for treatment is in fixed form, the washout of microorganisms (e.g. in a snow melt) is only limited to the suspended portion of the biomass.

2.3 Advantages of Plant Roots as Biofilm Carriers

- The specific surface area of plant roots is higher by an order of magnitude when compared to most plastic carrier media. This results in higher equivalent biomass concentrations.
- Plant roots are not susceptible to clogging, thus operational safety is high.
- The plants naturally transport oxygen to their roots which increases biofilm activity.
- The plants excrete small amounts of organic acids on their root surfaces which act as a food source for the biofilm. This is of high importance when the influent load is low. In this case the plants help bacteria to survive starvation and results in a larger population of bacteria in the system when the wastewater load is re-established. As a result the Organica Hybrid FCR system has far greater flexibility and resiliency when compared to purely conventional activated sludge technologies.
- As plant roots are able to grow in the top 0.5 – 1 m of the water, in the lower depth artificial plant roots – Organica's patented biofibre media – are installed. This media is designed to provide very similar habitat for microorganisms as plant roots provide.
- One of the Organica Hybrid FCR Solution's advantages is providing an additional habitat (and a longer sludge age) for slow-growing species – e.g. the nitrifiers – in biofilms attached to plant roots and artificial biotextile media. Due to the significant mass of the biofilm and its biological diversity, higher degree of nutrient removal is possible in the hybrid system compared to purely suspended growth systems.

3 Design Basis

Based on the information provided to Organica and certain assumptions made by Organica, Table 1 below shows the influent characteristics and effluent limits used as the design basis.

Table 1. Influent characteristics and effluent limits used as design basis

Parameters	Influent Characteristics	Units	Effluent Limits	Units
Design average flow (Q_{Average})	2,800	m^3/d	-	m^3/d
Design rainy weather peak flow (Q_{RWA})	470	m^3/h	-	m^3/h
Design peak to Biology ($Q_{\text{Peak to Biology}}$)	350	m^3/h	-	m^3/h
COD	623	mg/l	< 125	mg/l
BOD ₅	260	mg/l	< 20	mg/l
Total Suspended Solids (TSS)	197	mg/l	< 30	mg/l
Total Kjeldahl Nitrogen (TKN)	68	mg/l	-	mg/l
Total Nitrogen (TN)	-	mg/l	< 15	mg/l
Total Phosphorus (TP)	10	mg/l	< 2	mg/l
Design minimum wastewater temperature (T_{\min})	10.1	$^{\circ}\text{C}$	-	$^{\circ}\text{C}$
Design maximum wastewater temperature (T_{\max})	25	$^{\circ}\text{C}$	-	$^{\circ}\text{C}$

4 Preliminary Design – Unit Operations

This section provides preliminary design information for the proposed treatment unit processes.

The main unit processes are:

- Pre-Treatment
 - Fine screen and grit removal - designed to treat Q_{RWA} ($470 \text{ m}^3/\text{h}$)
- Biological Treatment
 - FCR multi-zone reactor with 7 zones in each reactor train
- Secondary Phase Separation
 - Secondary clarifier
- Disinfection
 - UV disinfection - designed to treat Q_{RWA} ($470 \text{ m}^3/\text{h}$)
- Solids Management
 - Sludge storage tank
 - Sludge thickening and dewatering

Process overview

The proposed system is an implementation of the Organica Food Chain Reactor (FCR) Solution in a hybrid arrangement (ie. suspended growth in coexistence with fixed film) which consists of biological wastewater treatment in successive reactors using both suspended biomass and fixed biomass on both natural (plant root) and artificial (patented biofibre media) root structures.

In an Organica Hybrid FCR WWTP there is a series of biological reactors where suspended biomass is maintained in every stage of the process, fixed biofilm are used only in the aerated reactor zones. The suspended growth biomass is maintained by a RAS system (return activated sludge) from secondary clarifiers back to the FCRs.

The Process Scheme accompanying this document provides a schematic of the above unit processes as well as the flow connectivity between them. As shown in the process scheme, influent flows to the fine screen and aerated grit chamber (pre-treatment) where solids removal takes place. After pre-treatment, flow is directed to the FCR reactors for biological treatment. The FCR is capable to treat flows up to 350 m³/h. Peak flows above the limit will be bypassed.

A biological treatment facility with one FCR train is proposed.

To provide biological nitrogen removal, varying degrees of aeration are used through the aerated reactor zones to create aerobic microbe environments for carbon removal and nitrification.

To complete the denitrification process, a recycle of aerobic zone fluids to the anoxic zones is required to provide nitrates to the anoxic zones. Biomass is maintained in suspension via mixers.

Anoxic zones are the primary location for denitrification where conversion of nitrate into nitrogen gas occurs – nitrate is used as the electron acceptor for organic matter degradation in this zone. Denitrification also takes place in the fixed-film of the aerobic zone, particularly the “deeper” layers of the biofilm where anoxic conditions are present.

Wastewater flows from the FCR to the secondary clarifier unit which gravity-settles the suspended biomass and inert solids to achieve the required effluent TSS limits.

Elimination of pathogens by UV-radiation takes place before discharge. The UV chamber is designed to be able to handle 470 m³/h peak flow.

The excess sludge from the clarifier is pumped to a sludge storage tank where air is introduced to avoid anaerobic, septic conditions. From the tank the sludge is directed to a combined thickening/dewatering unit where poly-electrolyte is introduced to improve dewatering processes. The dewatered sludge will be put in containers for further processing. The filtrate from the unit will be sent back to the biology.

4.1 Pre-Treatment Units

Fine Screen

Fine screening is utilized to remove objects prior to the treatment process. These objects are generally inert plastics and other debris that cannot be broken down in biological treatment.

Table 2.Techical Specification of Fine Screens

Item/Parameter	Value	Unit
Opening size	3	mm
Total screenings volume	241	l/d

Grit Removal

Grit removal captures sand, grit, and other fine material that is non-biodegradable prior to biological treatment.

Table 3.Techical Specification of Grit Removal

Item/Parameter	Value	Unit
Number of grit removal basins	1	-
Volume of one basin	24	m ³
Grit removal basin type	Aerated	-
Total air requirement	250	Nm ³ /h
Total grit quantity	140	l/d
Total grease quantity	18	l/d

4.2 Secondary Biological Treatment – Organica FCR

As described above, biological treatment will occur through a series of FCR reactor zones.

FCR Reactors

To provide sufficient habitat for the fixed-film process utilized in FCR solutions, sufficient retention time and surface area will be provided.

Table 4.Techical Specification of Organica FCR reactors

Item/Parameter	Value	Unit
Total volume of reaction zones per train	2,176	m ³
Number of reaction zones per train	6	-
Numbers of trains	1	-
Total Biofiber Media area per train	18,248	m ²
Plant racks per train	108	m ²

Process Aeration

Aeration is provided in the FCR zones to maintain mixing and provide sufficient oxygen in the anoxic and aerobic process described previously.

Table 5.Process Aeration Technical Specification

Item/Parameter	Value	Unit
Process air demand (min)	1,250	Nm ³ /h
Process air demand (average)	1,520	Nm ³ /h
Process air demand (max)	1,750	Nm ³ /h

4.3 Phase Separation

Secondary Clarification

Clarification is provided to allow a quiescent settling zone where suspended solids are gravity-settled to the bottom of the clarifier. Settled solids are then pumped directly to the solids handling and dewatering processes.

Table 6. Basic Secondary Clarification Information

Item/Parameter	Value	Unit
Number of units	1	pcs
Side Water Depth	4	m
Surface of one clarifier	175	m ²
RAS flowrate	1,400 – 4,200	m ³ /d

4.4 Disinfection

UV Disinfection

Through passage of UV light into the water, inactivation of bacteria, viruses, and protozoa is accomplished.

4.5 Solids Management

Sludge storage Tank

A sludge storage tank is provided as a buffer to allow intermittent operation of the downstream dewatering equipment.

Table 7. Technical Specification of sludge storage tank

Parameters	Value	Unit
Total Volume of Sludge storage tank	51	m ³
Mixing air requirement	26	Nm ³ /h

Combined Thickening/Dewatering Unit

Sludge flow from the sludge storage tank is directed to the combined thickening and dewatering unit.

Table 8. Technical Specification of combined thickening and dewatering unit

Item/Parameter	Value	Unit
Sludge flow from thickening and dewatering	2.6	m ³ /d
Dry solids content	20	%w/w

Polymer System

Polyelectrolyte is added through various unit processes to optimize solids separation performance.

Table 9. Minimum Design Capacities of Polymer Systems

Item/Parameter	Value	Unit
Sludge thickening and dewatering	4.6	kg/d

5 Control system

The wastewater treatment facility utilizes a PC-PLC based process control system with custom-engineered control software. It integrates the acquisition, display, and storage of operational data, as well as the input and application of operational variables.

5.1 Instrumentation and Control

The design provides appropriate instruments and sensors, as required, for proper operation and control of the system. In general, flow is measured by electromagnetic meters and/or derived from level sensors. Dissolved oxygen probes are provided for monitoring of dissolved oxygen at appropriate locations. Other additional sensors such as instrumentation for online measurement of ammonia, nitrate, or phosphorus may be included in the design as needed depending on the effluent requirements and operational needs. Variable Frequency Drives (VFDs) are provided for pump or blower speed control where necessary. Electromagnetic or pneumatic actuators are provided for valve operation or modulation where necessary. Key equipment is controlled by one or more PLCs, which monitor their status through feedback channels and display on the control application program.

5.2 Display Panel, Event Log

The application program that runs on the PC is adapted and customized to the technology. Its function is to gather, display, print and store information in addition to the implementation of operator commands and settings. The program provides all stored information in a processed and readable format, readily accessible to operators.

The real-time technical parameters (status of equipment, measured values) are displayed on the flowchart of the application program. These values are stored in a central database, which is accessible through charts and summary tables. Changes of technological settings, failures, alarms, and equipment status are stored in the event log.

5.3 Control and Variables

The PLC supervisory program controls the automatic operation of equipment. The automatic operation can be altered by using the commands of the application program or modifying the control parameters. Initial values for these parameters are set during the design of each facility. However, a high level of flexibility is provided for modification of these parameters in the event that actual operating conditions or the influent characteristics differ from those used in the original design.

5.4 Remote Access



Internet and mobile technologies play an essential role in the operation of the facility. Remote access to the control panel and logged data enables technologists to observe and intervene in the treatment process when necessary.

5.5 Main Intervention Points

The most important intervention point is aeration control in the cascade reactors - the PC-PLC system controls the blowers by variable frequency drives thus enabling it to maintain a range from 2 – 4 mg/L dissolved oxygen level in the FCR reactors to optimize kinetics of the biological process, while balancing energy consumption. This control logic is based upon measurement of dissolved oxygen through probes installed in the FCR reactors.

BIJLAGE 5

ONTWERPEN ORGANICA EPE



Project ID: NL01257L
 Drawing Title: Site Plan - Plant 2 WTP (8 MLD)
 Drawing Date: 21/12/2017
 Revision: A1
 Author:

Based by: OT
 Drawn by: Natasja Rizo
 Checked by: Natasja Rizo
 Approved by: Natasja Rizo

Project Name: STOWA Plant 2 WTP (8 MLD)
 Drawing Date: 21/12/2017
 Revision: A1
 Author:

Project ID: NL01257L-A-011-001
 Drawing Title: Site Plan - Plant 2 WTP (8 MLD)
 Drawing Date: 21/12/2017
 Revision: A1
 Author:

Project ID: NL01257L
 Drawing Title: Site Plan - Plant 2 WTP (8 MLD)
 Drawing Date: 21/12/2017
 Revision: A1
 Author:


Project Name: STOWA Plant 2 WTP (8 MLD)
 Drawing Date: 21/12/2017
 Revision: A1
 Author:

Project ID: NL01257L-A-011-001
 Drawing Title: Site Plan - Plant 2 WTP (8 MLD)
 Drawing Date: 21/12/2017
 Revision: A1
 Author:

SITE PLAN

Scale: 1:200

ORGANICA






GENERAL NOTES:

- External wall shall be applicable for all building design.
- Coping profile shall be provided on building top as per the typical detail provided in this sheet.
- Organica FCR lyrical layout shall be applicable for all building design.
- All concrete structure shall be provided on building top as per the typical detail provided in this sheet.
- All dimensions are from the face of finished wall to face of finished wall U.N.O.
- Greenhouse structure shall be of galvanized steel framework.

Steel framework shall be in accordance as per local available standards and codes.




Some of the benefits of designing and building Organica Greenhouse:

- Use of tempered glass covering that has the highest light transmission and comes in rigid panels that are especially made for greenhouse. The glass has better transluence UV characteristics.
- Efficient rain water drainage system where the rainwater is collected in internal gutters, and internal downspout system takes the rainwater besides the walls to external connection points. The internal gutters consist of additional gutter heating to avoid winter-time freezing.
- Hot-dip Galvanized steel framework is specified for its superior corrosion protection, especially in harsh environments and mainly used in most of Organica designs. Though corrosion resistance is inherent, and time galvanizing is utilized, more and more specifies select hot-dip galvanized steel for other reasons, including initial cost, durability, longevity, versatility, aesthetics, and sustainability.
- Convertible window are provided to protect against overheating in the summer which are thereby controlled by temperature, light and wind velocity measurements.
- The treated water which is generated from the Treatment plant can be utilized as the best source for watering plants kept in boxes or pots, because its costless, and its nutrient concentration is higher, negating the necessity of fertilizers.



Project ID: NL01257L	Client: Organica Water, Inc.	Issued By: Aan de Stegge	Project Name: STOWA Study - Plant 2 WWTP (8 MLD)
Type of Design: Concept Design	Location: Netherlands	Drawing No.: OT	Drawing Size: A2
Designed By: Anubhai Agarwalla	Checked By: Nicolas Rizo	Approved By: Nicolas Rizo	Date: 21.02.2017
Drawings Number: NL01257L-A-013-001			Revision: 1





Project Name: STOWA Study - Plant 2 WWTP (8 MLD)
Drawing Name: A1
Rendering Date: 21/02/2017
Issued by: OT
Approved by: Natasja Rizzo
Architect: Arup
Designer: Natasja Rizzo
Comments: None


Project Name: Water Inc.
Drawing Name: A1
Rendering Date: 21/02/2017
Issued by: OT
Approved by: Natasja Rizzo
Architect: Arup
Designer: Natasja Rizzo
Comments: None

Project Name: STOWA Study - Plant 2 WWTP (8 MLD)
Drawing Name: A1
Rendering Date: 21/02/2017
Issued by: OT
Approved by: Natasja Rizzo
Architect: Arup
Designer: Natasja Rizzo
Comments: None



LEGEND


INFLUENT	- - - - -
SUDBOE	- - - - -
EFFLUENT/CLEANWATER	- - - - -
FILTRATE	- - - - -
CHEMICAL	- - - - -
SOLVENT/WASTE	-----
GAS	****
AIR	++
PUMP	oo
SUDBOE/AIR	o



Project Name:	STOWA Study - Plant 2 WWTP (8 MLD)	GT	AS
Drawing No.:			
Drawing Title:			
Design No.:			
Design Date:			
Checked by:			
Approved by:			
Accepted by:			
Issued to:			
Reviewed by:			
Revised by:			
Comments:			


Project Name:	STOWA Study - Plant 2 WWTP (8 MLD)	GT	AS
Drawing No.:			
Drawing Title:			
Design No.:			
Design Date:			
Checked by:			
Approved by:			
Accepted by:			
Issued to:			
Reviewed by:			
Revised by:			
Comments:			

Project Name:	STOWA Study - Plant 2 WWTP (8 MLD)	GT	AS
Drawing No.:			
Drawing Title:			
Design No.:			
Design Date:			
Checked by:			
Approved by:			
Accepted by:			
Issued to:			
Reviewed by:			
Revised by:			
Comments:			



Influent wastewater	
Parameter name	Desire value
COO	675 mg/L
BOD ₅	275 mg/L
TSS	265 mg/L
TP	mg/L
Temperature	
T _{eff,raw}	10.1 °C
T _{eff,raw}	25 °C
Flow Data	
Q _{raw}	8,000 m ³ /d
Q _{raw}	1,500 m ³ /h
Q _{raw,max-hr}	1,000 m ³ /h

1	2/13/2017	Issue to Client
Revision Number	P-013-001	Version Description
OT		Revised by
Project Name: STOWA Study - Plant 2 WWTP (8 MLD)		Date: 2/13/2017
Owner Name: Process and Instrumentation Diagram - 1.		Client:
Organics West Inc.		Auto Scope
Design by: P-011-2002		Scale: 1
Date: 2/13/2017		PC Level:
Comments: This document contains sensitive information and is controlled by the U.S. Environmental Protection Agency (EPA) under Executive Order 13526. Distribution and copying are subject to the terms of the Inter-Agency Security Agreement (IASA). It is illegal to copy or distribute this document outside EPA without prior written permission from the owner. If you have received this document in error, please return it to the owner. If you have questions about this notice, please contact the owner.		AS



Project Name: STOWA Study - Plant 2 WWTP (8 MLD)
 Drawing No.: P-013-001
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - I.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A1
 Drawing Number: P-013-002
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - II.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A2
 Drawing Number: P-013-003
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - III.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A3
 Drawing Number: P-013-004
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - IV.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A4
 Drawing Number: P-013-005
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - V.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A5
 Drawing Number: P-013-006
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - VI.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A6
 Drawing Number: P-013-007
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - VII.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A7
 Drawing Number: P-013-008
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - VIII.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A8
 Drawing Number: P-013-009
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - IX.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A9
 Drawing Number: P-013-010
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - X.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A10
 Drawing Number: P-013-011
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XI.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A11
 Drawing Number: P-013-012
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XII.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A12
 Drawing Number: P-013-013
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XIII.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A13
 Drawing Number: P-013-014
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XIV.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A14
 Drawing Number: P-013-015
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XV.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A15
 Drawing Number: P-013-016
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XVI.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A16
 Drawing Number: P-013-017
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XVII.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A17
 Drawing Number: P-013-018
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XVIII.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A18
 Drawing Number: P-013-019
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XIX.
 Issued to: Client: Anon Source:
 Basic Design
 Scale: 1
 Project Number: NUG257L
 Drawing Name: A19
 Drawing Number: P-013-020
 Date: 21.02.2017
 Revision No.: 1
 Revision Date: 21.02.2017
 Revision Description: Process and Instrumentation Diagram - XX.

Valve symbols		Pumps	Air Handling	Filters	Equipment Designation
	Ball Valve				X050
	Butterfly Valve				Type of Equipment
	Check Valve				Instrument Number
	Diaphragm Valve				
	Gate Valve				
	Globe Valve				
	Magnetic Valve				
	Pressure Reducer				
	Flow Meter				
	Chimney Gate				
Actuator symbols					
T	Manual Actuator				
	Controlled Actuator				
	Pneumatic Actuator				
Tank/Vessel		Filtration	Screening	Chiller	Miscellaneous symbols
	Open/Enclosed Tank				
	Pressurized Tank				
	Open/Enclosed Tank				
	Aeration/Gas Transfer				
	Pressurized Tank				
	Open/Enclosed Tank				
Sludge Dewatering					
	Conical Filter				
	Membrane Filter Diffuser				
	Conical Filter				
	Hydrofilter				

IMPLEMENTATION DOCUMENTS
Drawing No.:

Project Name: STOWA Study - Plant 2 WWTP (8 MLD)
Drawing No.: P-019-001
Project Number: NUG257L
Drawing Date: 21.02.2017
Drawing Legend: Basic Design
Scale: 1:100
P.D.:

Date: 21.02.2017
Revised by: _____
Issued to: _____
Client: _____
Aut. Scope: _____



Technical Description

Project Name: STOWA Study - Plant 2 WWTP (8 MLD)

Document Number: NL01257L-P-091-001

Revision: 1

Contents

1	Introduction	3
2	General Introduction to Organica FCR	3
2.1	Advantages of the FCR Solution	3
2.1.1	Lower suspended solids concentration (MLSS) offers phase separation alternatives.....	4
2.1.2	Lower suspended solids concentration (MLSS) improves energy efficiency	4
2.1.3	Increased biomass concentration.....	4
2.1.4	Eliminated requirement for sludge recirculation (RAS)	4
2.1.5	Longer effective solids retention time (SRT)	4
2.1.6	Elimination of sludge "bulking" and "washout".....	4
2.1.7	Compact facility consumes less space.....	4
3	Design Basis.....	5
4	Preliminary Design – Unit Operations	6
	Process overview	6
4.1	Pre-Treatment Units.....	7
	Fine Screen	7
	Grit Removal.....	7
4.2	Secondary Biological Treatment – Organica FCR	7
	FCR Reactors	7
	Process Aeration.....	8
4.3	Phase Separation.....	8
	Chemical Phosphorus Removal/Coagulation	8
	Secondary Clarification.....	8
4.4	Disinfection	8
	UV Disinfection	8
4.5	Solids Management.....	9
	Sludge storage Tank.....	9
	Combined Thickening/Dewatering Unit	9
	Polymer System.....	9
5	Control system.....	10
5.1	Instrumentation and Control	10
5.2	Display Panel, Event Log	10



5.3	Control and Variables.....	10
5.4	Remote Access	10
5.5	Main Intervention Points	10

1 Introduction

This technical description outlines the proposed Organica solution for the **STOWA Study - Plant 2** wastewater treatment facility (WWTF) in **Amsterdam, the Netherlands**. As outlined below, average design capacity of the proposed facility is **8,000 m³/d**.

Organica solutions utilize a Food Chain Reactor (FCR) configuration, consisting of biological treatment in successive reactor zones utilizing fixed biomass on a combination of natural plant roots and Organica's engineered biofiber media, along with a limited amount of suspended biomass.

This document is structured as follows:

- Organica FCR general introduction
- Design basis - influent flow and characterization with treated effluent requirements
- Preliminary design information by unit process
- Description of the control system

2 General Introduction to Organica FCR

Organica FCR solutions consist of a series of biological treatment zones simultaneously utilizing both fixed biofilm and suspended biomass in the reactors. Biodegradation of influent contaminants is accomplished by the combination of fixed and suspended biological cultures. Biomass in the Organica FCR is primarily fixed-film, utilizing natural plant roots along with additional engineered (biofiber) media as biofilm carriers. As a standard feature of the solution, the basins may be covered by an attractive enclosure to protect the "botanical garden" as needed.

As influent travels through the FCR zones, the available organics and nutrients (various carbon, nitrogen, and phosphorus fractions) are consumed and/or transformed. As a result, the composition of the ecosystem fixed in the biofilm changes from zone to zone, gradually adapting to localized conditions as the organic and nutrient concentrations vary, as well as dissolved oxygen content. The end result is a specially-adapted ecosystem in each zone, acclimatized to the specific conditions to maximize treatment efficiency.

2.1 Advantages of the FCR Solution

A significant fraction of microorganisms responsible for biodegradation is in fixed-film form (attached growth). Benefits of fixed-film solutions include:

- Mixed liquor suspended solids (MLSS) concentrations significantly lower than conventional activated sludge systems; resulting in:
 - Improved aeration & mixing efficiency (reducing energy requirements)
 - Flexible phase-separation alternatives, including option of direct filtration (without clarifiers) to conserve space
- Increased concentration of active biomass in the treatment zones
- Eliminated requirement for sludge recirculation (RAS)
- Longer effective SRT (sludge age); resulting in more complex organisms with longer lifecycles (unicellular cilia, larvae, arthropods) establishing themselves on the biofilm
- Eliminated potential for biomass "washout"
- Significant reduction in biological reactor space requirements

These benefits are described in further detail below.

2.1.1 Lower suspended solids concentration (MLSS) offers phase separation alternatives

With the primary biomass in fixed-film form, solids concentration in suspended form (MLSS) is reduced. While conventional secondary clarification designs can also be utilized effectively, lower MLSS solids concentrations allow the option of direct filtration of the FCR effluent with a Disc Filter. Disc Filters offer drastically reduced space requirements, in addition to a positive barrier for solids capture and thus more reliable effluent quality.

2.1.2 Lower suspended solids concentration (MLSS) improves energy efficiency

Lower suspended solids concentrations (MLSS) reduce viscosity of the reactor liquid, requiring less mixing energy. Further, lower viscosity fluids have enhanced diffusion properties resulting in a higher oxygen mass transfer coefficient ("alpha" value), significantly improving aeration efficiency. The combination of reduced mixing demand and improved aeration efficiency results in significantly less energy consumption.

2.1.3 Increased biomass concentration

Due to the properties of the plant roots and the biofilm carrier arrangement, a special biofilm structure develops on both the natural and engineered media. This improved biofilm structure provides a higher concentration of biomass compared to other biofilm-based technologies. Depending upon project specifics, a total biomass concentration of 8 to 15 kg/m³ can be achieved, three to five times higher than conventional activated sludge systems. As a result, reactor volume can be drastically reduced.

2.1.4 Eliminated requirement for sludge recirculation (RAS)

Another advantage of Organica's fixed-film solution is elimination of the requirement for sludge recirculation (RAS). The excess biosolids removed in secondary phase separation are forwarded directly to the sludge handling system. Elimination of the RAS simplifies the process, while also eliminating the capital and operating costs of the pumping system and associated piping.

2.1.5 Longer effective solids retention time (SRT)

With the vast majority of the biomass in fixed form and without sludge (RAS) recirculation, the biomass can reach effectively higher sludge ages (SRT's) in a limited reactor volume. Higher SRT's provide significant advantages with respect to nitrification as they enable better retention of slow-growing autotrophic bacteria (nitrifiers) in the system, with reduced risk of "washout" in peak flow events. Additionally, higher SRT's enable complex organisms with longer lifecycles (unicellular cilia, worms, arthropods, etc.) to establish themselves in the biofilm. The more complex organisms are generally slower growing and also tend to be "predatory" (consuming more basic organisms resident in the system), resulting in lower net sludge production. Further, many of these species have demonstrated the ability to break down a wider range of substrates and more complex compounds (such as pharmaceuticals).

2.1.6 Elimination of sludge "bulking" and "washout"

Conventional activated sludge systems commonly see filamentous sludge "bulking" as a result of various specific operating conditions. Filamentous bacteria are the main cause of sludge bulking and proliferate mainly in suspended growth conditions. In FCR reactors, suspended growth accounts for only a small fraction of the total biomass, thus significantly reducing the growth opportunity for filamentous organisms and the potential for sludge bulking. Further, biomass "washout" from the system during high flow conditions is impossible with the majority of biomass attached to the carriers.

2.1.7 Compact facility consumes less space

Higher biomass concentrations result in significantly reduced reactor volumes and space requirements. In addition, the lower suspended solids concentration allows the potential of direct filtration for phase separation, without the use of

clarifiers, thus providing further opportunity to reduce the overall space requirements for the facility. Plant roots provide are ideal biofilm carriers

- Plant root specific surface area is an order of magnitude higher than most artificial carrier media, resulting in higher concentrations of active biomass.
- Plant roots are not susceptible to clogging, thus reducing operational risk.
- Plants excrete small amounts of organic acids from their root surfaces which act as a food source for the biofilm. This is of high importance when the influent organic load is low. This symbiotic relationship helps bacteria to survive starvation periods, resulting in a larger and more diverse population of bacteria in the system when the wastewater load is re-established. As a result, FCR facilities have far greater flexibility compared to conventional activated sludge systems.
- Utilization of marsh plants (reeds, sedges, bulrushes, etc.) transport oxygen to their roots and increase biofilm activity.
- Plant roots provide a better habitat for slow-growing species, such as nitrifiers and eukaryotic organisms, resulting in improved nutrient removal performance over conventional processes.

3 Design Basis

Based on the information provided to Organica and certain assumptions made by Organica, Table 1 below shows the influent characteristics and effluent limits used as the design basis.

Table 1. Influent characteristics and effluent limits used as design basis

Parameters	Influent Characteristics	Units	Effluent Limits	Units
Design average flow ($Q_{Average}$)	8,000	m ³ /d	-	m ³ /d
Design rainy weather peak flow (Q_{RWA})	1,500	m ³ /h	-	m ³ /h
Design peak to Biology ($Q_{Peak to Biology}$)	1,000	m ³ /h	-	m ³ /h
COD	678	mg/l	< 125	mg/l
BOD ₅	279	mg/l	< 20	mg/l
Total Suspended Solids (TSS)	265	mg/l	< 30	mg/l
Total Kjeldahl Nitrogen (TKN)	71	mg/l	-	mg/l
Total Nitrogen (TN)	-	mg/l	< 10	mg/l
Total Phosphorus (TP)	8	mg/l	< 2	mg/l
Design minimum wastewater temperature (T_{min})	10.1	°C	-	°C
Design maximum wastewater temperature (T_{max})	25	°C	-	°C

4 Preliminary Design – Unit Operations

This section provides preliminary design information for the proposed treatment unit processes.

The main unit processes are:

- Pre-Treatment
 - Fine screen and grit removal - designed to treat Q_{RWA} ($1,500 \text{ m}^3/\text{h}$)
- Biological Treatment
 - FCR multi-zone reactor with 7 zones in each reactor train
- Secondary Phase Separation
 - Coagulation
 - Secondary clarifier
- Disinfection
 - UV disinfection - designed to treat Q_{RWA} ($1,500 \text{ m}^3/\text{h}$)
- Solids Management
 - Sludge storage tank
 - Sludge thickening and dewatering

Process overview

The Process Scheme accompanying this document provides a schematic of the above unit processes as well as the flow connectivity between them.

As shown in the process scheme, influent flows to the fine screen and aerated grit chamber (pre-treatment) where solids removal takes place. After pre-treatment, flow is directed to the FCR reactors for biological treatment. The FCR is capable to treat flows up to $1,000 \text{ m}^3/\text{h}$. Peak flows above the limit will be bypassed.

A biological treatment facility with two FCR trains is proposed.

To provide biological nitrogen removal, varying degrees of aeration are used through the reactor zones to create both anoxic and aerobic microbe environments. Anoxic zones are the primary location for denitrification where conversion of nitrate into nitrogen gas occurs – nitrate is used as the electron acceptor for organic matter degradation in this zone. Denitrification takes place both in the suspended phase and in the fixed-film, particularly the “deeper” layers of the biofilm where anoxic conditions are present.

Following the anoxic stages, aerobic zones provide organic matter degraders, nitrifiers and higher organisms in both suspended and attached phases to provide degradation of organic compounds and conversion of ammonia to nitrate. To complete the denitrification process, a recycle of aerobic zone fluids to the anoxic zones is required to provide nitrates to the anoxic zones. Throughout both the anoxic and aerobic zones, fine-bubble aeration is used to provide mass transfer (oxygen) and mixing to keep any free solids in suspension. After the aerobic zones post-anoxic zone is placed and methanol is added to ensure proper denitrification.

Wastewater flows from the FCR reactor zones to a coagulation tank, where polyaluminum-chloride (PAC) is added to achieve the required effluent phosphorus limit via solids removal.

Wastewater flows from the coagulation tank to the secondary clarifier unit which gravity-settles the suspended biomass and inert solids to achieve the required effluent TSS limits.

Elimination of pathogens by UV-radiation takes place before discharge. The UV chamber is designed to be able to handle 1,500 m³/h peak flow.

The excess sludge from the clarifier is pumped to a sludge storage tank where air is introduced to avoid anaerobic, septic conditions. From the tank the sludge is directed to a combined thickening/dewatering unit where poly-electrolyte is introduced to improve dewatering processes. The dewatered sludge will be put in containers for further processing. The filtrate from the unit will be sent back to the biology.

4.1 Pre-Treatment Units

Fine Screen

Fine screening is utilized to remove objects prior to the treatment process. These objects are generally inert plastics and other debris that cannot be broken down in biological treatment.

Table 2.Techical Specification of Fine Screens

Item/Parameter	Value	Unit
Opening size	3	mm
Total screenings volume	688	l/d

Grit Removal

Grit removal captures sand, grit, and other fine material that is non-biodegradable prior to biological treatment.

Table 3.Techical Specification of Grit Removal

Item/Parameter	Value	Unit
Number of grit removal basins	1	-
Volume of one basin	74	m ³
Grit removal basin type	Aerated	-
Total air requirement	366	Nm ³ /h
Total grit quantity	400	l/d
Total grease quantity	57	l/d

4.2 Secondary Biological Treatment – Organica FCR

As described above, biological treatment will occur through a series of FCR reactor zones.

FCR Reactors

To provide sufficient habitat for the fixed-film process utilized in FCR solutions, sufficient retention time and surface area will be provided.

Table 4.Techical Specification of Organica FCR reactors

Item/Parameter	Value	Unit
Total volume of reaction zones per train	3,291	m ³
Number of reaction zones per train	6	-
Numbers of trains	2	-
Total Biofiber Media area per train	59,709	m ²
Plant racks per train	162.2	m ²
Total Methanol usage	0.26 – 0.5	m ³ /d

Process Aeration

Aeration is provided in the FCR zones to maintain mixing and provide sufficient oxygen in the anoxic and aerobic process described previously.

Table 5.Process Aeration Technical Specification

Item/Parameter	Value	Unit
Process air demand (min)	3,075	Nm ³ /h
Process air demand (average)	3,810	Nm ³ /h
Process air demand (max)	4,440	Nm ³ /h

4.3 Phase Separation

Chemical Phosphorus Removal/Coagulation

Prior to solids separation, chemical coagulation with PAC addition will be utilized for efficient removal of suspended particles, as well as phosphorus precipitation where required.

Table 6.Techincal Specification of Chemical Phosphorus Removal/Coagulation

Item/Parameter	Value	Unit
Total PAC usage	140	l/d
Total volume of coagulation tank	8.5	m ³

Secondary Clarification

Clarification is provided to allow a quiescent settling zone where suspended solids are gravity-settled to the bottom of the clarifier. Settled solids are then pumped directly to the solids handling and dewatering processes.

Table 7. Basic Secondary Clarification Information

Item/Parameter	Value	Unit
Number of units	1	pcs
Side Water Depth	4	m
Surface of one clarifier	500	m ²

4.4 Disinfection

UV Disinfection

Through passage of UV light into the water, inactivation of bacteria, viruses, and protozoa is accomplished.

4.5 Solids Management

Sludge storage Tank

A sludge storage tank is provided as a buffer to allow intermittent operation of the downstream dewatering equipment.

Table 8. Technical Specification of sludge storage tank

Parameters	Value	Unit
Total Volume of Sludge storage tank	183	m ³
Mixing air requirement	92	Nm ³ /h

Combined Thickening/Dewatering Unit

Sludge flow from the sludge storage tank is directed to the combined thickening and dewatering unit.

Table 9. Technical Specification of combined thickening and dewatering unit

Item/Parameter	Value	Unit
Sludge flow from thickening and dewatering	9.4	m ³ /d
Dry solids content	20	%w/w

Polymer System

Polyelectrolyte is added through various unit processes to optimize solids separation performance.

Table 10. Minimum Design Capacities of Polymer Systems

Item/Parameter	Value	Unit
Sludge thickening and dewatering	16.5	kg/d

5 Control system

The wastewater treatment facility utilizes a PC-PLC based process control system with custom-engineered control software. It integrates the acquisition, display, and storage of operational data, as well as the input and application of operational variables.

5.1 Instrumentation and Control

The design provides appropriate instruments and sensors, as required, for proper operation and control of the system. In general, flow is measured by electromagnetic meters and/or derived from level sensors. Dissolved oxygen probes are provided for monitoring of dissolved oxygen at appropriate locations. Other additional sensors such as instrumentation for online measurement of ammonia, nitrate, or phosphorus may be included in the design as needed depending on the effluent requirements and operational needs. Variable Frequency Drives (VFDs) are provided for pump or blower speed control where necessary. Electromagnetic or pneumatic actuators are provided for valve operation or modulation where necessary. Key equipment is controlled by one or more PLCs, which monitor their status through feedback channels and display on the control application program.

5.2 Display Panel, Event Log

The application program that runs on the PC is adapted and customized to the technology. Its function is to gather, display, print and store information in addition to the implementation of operator commands and settings. The program provides all stored information in a processed and readable format, readily accessible to operators.

The real-time technical parameters (status of equipment, measured values) are displayed on the flowchart of the application program. These values are stored in a central database, which is accessible through charts and summary tables. Changes of technological settings, failures, alarms, and equipment status are stored in the event log.

5.3 Control and Variables

The PLC supervisory program controls the automatic operation of equipment. The automatic operation can be altered by using the commands of the application program or modifying the control parameters. Initial values for these parameters are set during the design of each facility. However, a high level of flexibility is provided for modification of these parameters in the event that actual operating conditions or the influent characteristics differ from those used in the original design.

5.4 Remote Access


Internet and mobile technologies play an essential role in the operation of the facility. Remote access to the control panel and logged data enables technologists to observe and intervene in the treatment process when necessary.

5.5 Main Intervention Points


The most important intervention point is aeration control in the cascade reactors - the PC-PLC system controls the blowers by variable frequency drives thus enabling it to maintain a range from 0.2 – 5 mg/L dissolved oxygen level in the FCR reactors to optimize kinetics of the biological process, while balancing energy consumption. This control logic is based upon measurement of dissolved oxygen through probes installed in the FCR reactors.

SITE PLAN

1:200



- GENERAL NOTES:**
1. No proceed slope shall exceed three(3) horizontal to one (1) vertical U.M.C.
 2. All utilities (manholes, valve, 4. Construction shall comply covers etc.) shall be adjusted with all applicable governing codes to final grade prior to the final fill of asphalt.
 3. All landscape islands shall have a crown of clean native soils prior to landscaping.
 4. Construction shall comply with all applicable governing codes to final grade prior to the final fill of asphalt.
 5. Traffic should be divided for trucks and cars/pedestrians.
 6. There should be proper location of pedestrian circulation facilities as required in the project.




Project Name: STOWA Study - Plant 2 WWTP (8 MLD)	Drawing File: Site Plan	Scale: 1:200
Client: CH2M HILL	Prepared by: OT	Checked by: CH2M HILL
Location: Europe	Approved by: CH2M HILL	Revised by: CH2M HILL



Revised Date: 03/2017
Drawing No.: NL01257L-A-011-004

GENERAL NOTES:

- Bulking position - considered to provide to the maximum extent possible a zero balance earthwork.
- Scope of material shall be verified by contractor prior to the onset of work at site.
- Organica FCR typical layout shall be applicable for all design.
- All concrete structure shall be considered as waterproof concrete and shall be in accordance with the manufacturer's specifications.
- All dimensions are from the face of finished wall to face of finished wall U.I.N.C.
- All equipments should be installed in accordance with the manufacturer's specifications as per local available standards and codes



TYPICAL PART PLAN OF FCR REACTOR'S BOTTOM SCALE 1:50




LOWER LEVEL +1,00 m

1:200

Scale:



Project ID: NL01257L	Type of Design: Concept Design	Issued by: OT	Drawing Ref.: Drawing File: Floor Plan - Lower Level
Client: Organica Water, Inc.	Designed by: Andras Czobor	Approved by: Monika Dandia	Location: Kanal de Siegge
61 Pittsfield Highway, Suite 21, Franklin Junction, NJ 08650 USA Phone: +1(908)518-8885 Fax: +1(908)518-8889 www.organicawater.com	Document Number: NL01257L-A-011-005	Date: 03/03/2017	Revision: 1



GENERAL NOTES:


- Building position : considered to provide to the maximum extent verified with project manager a zero balance earthwork.
- Scope of material shall be verified by contractor prior to the onset of work at site.
- Exact location of walls, windows and doors shall be verified with project manager.
- Construction shall comply with all applicable governing codes and be constructed to same.
- All dimensions are from the face of finished wall to face of finished wall U.N.O.
- All equipments should be installed in accordance with the manufacturer's specifications.

Project ID: NL01257L-A-011-006	Project Name: STOWA Study - Plant 2 WWTP (8 MLD)	Scale: 1:200
Drawing Ref: A-204	Concept Design	Drawing Ref: A-204
Revision: 1	Issued by: OT	Revision: 1
Date: 20/03/2017	Designed by: Andras Czabok	Date: 20/03/2017

Comments: This drawing is to be considered valid only when it is stamped with the official stamp of Organica Water, Inc. or its authorized representative. It is the responsibility of the user to verify that this stamp is present. Any changes made to this drawing without the written consent of the authorizer shall void this stamp and make the drawing invalid.

GENERAL NOTES:


- External wall detail shall be typical for all building design.
- Coping profile shall be provided on building top as per the typical detail provided in this sheet.
- Organica FCR typical Layout shall be applicable for all design.
- All concrete structure shall be considered as water proof concrete and shall be in accordance as per local available standards and codes.
- All dimensions are from the face of finished wall to face of finished wall U.N.O.
- Greenhouse structure shall be galvanised steel framework.



GREENHOUSE OVER BIO-MODULE DESIGN (SCALE 1:50)


Some of the benefits of designing and building Organica Greenhouse:

- Use of tempered glass covering that has the highest light transmission and comes in rigid panels that are especially made for greenhouse. The glass has better transluence UV characteristics.
- Efficient rain water drainage system where the rainwater is collected in internal gutters, and internal downpipe system takes the rainwater besides the walls to external connection points. The internal gutters consist of additional gutter-heating to avoid winter-time freezing.
- Ho-dip Galvanized Steel Framework is specified for its superior corrosion protection, especially in harsh environments and mainly used in most of Organica designs. Through corrosion resistance it inherit a life time galvanization which is utilized, make more specifiers select hot-dip galvanised steel for other reasons, including initial cost, durability, longevity, versatility, aesthetics, and sustainability.
- Convertible window are provided to protect against overheating in the summer which are thereby controlled by temperature, light and wind velocity/meas. elements.
- The treated water which is generated from the Treatment plant can be utilized as the best source for watering plants kept in boxes or pots, because its costless, and its nutrient concentration is higher, negating the necessity of fertilizers.



SECTION B-B

Scale: 1:200



SECTION A-A

Scale: 1:200

Project ID: NL01257L	Type of Design: Concept Design	Issued by: OT	Drawing Title: STOWA Study - Plant 2 WWTP (8 MLD)	Project Name: STOWA Study - Plant 2 WWTP (8 MLD)
Client: Organica Water, Inc.	Location: Ad Stegge	Drawings Size: 1:200	Designers: Andras Czobok	Revision: 1

6a. Pittsburgh-Hightstown, Road Suite 3A, Pennsylvania, United States 08540 USA
Phone: +1 6096518885 Fax: +1 6096518889
Email: info@organicawater.com
Organica Water, Inc. is a wholly owned subsidiary of Organica Water, Inc. All documents contained in this document are the sole property of Organica Water, Inc. Any disclosure, reproduction, distribution or use of the information contained herein without the express written consent of Organica Water, Inc. is prohibited. Organica Water, Inc. reserves the right to pursue legal action against any individual or entity that violates this copyright notice.
Organica Water, Inc. is a registered trademark of Organica Water, Inc. and is used with the consent of Organica Water, Inc. © Organica Water, Inc. 2013.



Project Name:	STOWA Study - Plant 2 WWTP (8 MLD)	Issued By:	N.T.S.
Drawing Title:	C1	Approved by:	Concept Design
Drawing Date:	01/04/2017	Designed by:	An de Stegge
Revision:	1	Checked by:	Monika Darda
Client:	Organica Water, Inc.	Location:	ORGANICA Europe
Location:	61 Principio-Highland Business Park, Suite 3A, Ft. Lauderdale, FL 33309, USA	Approved by:	Nicolas Rizo
Phone:	+1 609 651 8885	Render:	Andras Szabok
Fax:	+1 609 651 8889	Drawn by:	
www.organicawater.com		Reviewed by:	
RELEASING OR DISCLOSING PARTS OF THIS DOCUMENT IS PROHIBITED BY ORGANICA WATER, INC., UNLESS INDIVIDUALLY APPROVED IN WRITING. THIS DOCUMENT IS MADE FOR THE USE AND INFORMATION OF ORGANICA WATER, INC. AND IS NOT TO BE COPIED, REPRODUCED, OR USED IN WHOLE OR IN PART, WITHOUT THE AUTHORIZATION OF ORGANICA WATER, INC. ANYONE RECEIVING THIS DOCUMENT IS ADVISED THAT IT IS THE PROPERTY OF ORGANICA WATER, INC. AND IS TO BE RETURNED TO ORGANICA WATER, INC. UPON REQUEST. ORGANICA WATER, INC. RESERVES THE RIGHT TO MONITOR USE OF THIS DOCUMENT. ANYONE RECEIVING THIS DOCUMENT IS ADVISED THAT IT IS THE PROPERTY OF ORGANICA WATER, INC. AND IS TO BE RETURNED TO ORGANICA WATER, INC. UPON REQUEST. ORGANICA WATER, INC. RESERVES THE RIGHT TO MONITOR USE OF THIS DOCUMENT.			


LEGEND


— INFLUENT
— SLUDGE
- - - - - EFFLUENT CLEANWATER
- - - - - - FILTRATE
+ + + + + CHEMICALS
+ + + + + - SOLID WASTE
GS AIR
SLOGUE PUMP




ByPass

SLOGUE PUMP







Project Name: STOWA Study - Plant 2 WWTF (8 MLD)		Drawing No.: P-013-004	
Revision:		Revision Date:	24.03.2017
Revisions:		Drawing Scale:	A1
Comments:		Drawing Number:	P-013-004
Project Manager:	N.L. 257L	Comments:	
Design:		Scale:	1
Basic Design		Date:	24.03.2017
Design:		Project Level:	n.t.s.
Organic Water Inc.		Client:	Aeris Stowage
Orbital		Address:	1000 Rockville Pike, Suite 100, Bethesda, MD 20814, USA
Project Name:	STOWA Study - Plant 2 WWTF (8 MLD)	Comments:	
Reference Drawing S		Comments:	
Drawings:		Comments:	
Comments:		Comments:	

Instrument Designation	Equipment Designation
	x000
	Equipment Number
Centrifugal Pump	Meters
Dosing Pump	Air Handling
Globe Valve	Roots Blower
Diaphragm Valve	Vertical Sheet Meter
Globe Valve	Submersible Meter
Three-Way Valve	Statue Meter
Solenoid Valve	
Magnetic Valve	
Knife Gate Valve	
Pressure Relief Valve	
Flow Meter	
Compressor	
Air Drier	
Diverter Valve	
Control Actuator	
Motor Actuator	
Pneumatic Actuator	
Tank/Vessel	
Open Atmospheric Tank	Filtration
Pressurized Tank	Screening
Open Atmospheric Tank Cleaning	Classifier
Aeration Gas Transfer	Heating Equipment
Pressure Line	Miscellaneous Symbols
Centrifugal Pump	Gas Heater
Dosing Pump	Case Engine
Globe Valve	Heat Exchanger
Diaphragm Valve	Boiler
Solenoid Valve	
Magnetic Valve	
Knife Gate Valve	
Pressure Relief Valve	
Flow Meter	
Needle Valve	
Orifice Valve	
Screwed Valve	
Natural Actuator	H
Motor Actuator	M
Pneumatic Actuator	P
Butterfly Valve	VH
Check Valve	VC
Air Release Valve	VA
Three-way Valve	VE
Diaphragm Valve	VD
Cage Valve	VG
Pressure Release Valve	VP
Ball Valve	VL
Needle Valve	VN
Channel Valve	VT
Knife Gate Valve	VK
Screwed Valve	VS
Pressure	P
Flow	F
Temperature	T
Chlorine	Cl
Dissolved Oxygen	DO
pH Level	H
Solids Concentration	S
COD Level	C
Indicator	I
Transmitter	T
Switch	S

1	26.03.2017	Internachi Client	OT
Revolution Number	Revolution Date	Revision Description	OT Frequency
Project Number: NL2557L	Drawing No.: A1		AS
Office Name:			Inspection
Project Manager: Oleg Slobodko, Russia			Client:
Project Address: 12, Tverskaya ul. 10, Moscow, Russia			As-is Stage
Project Type: STOWA Study - Plant 2 WWTF (8 MLD)			PCP Level:
Process and Instrumentation Diagram Legend			1



Technical Description

Project Name: STOWA Study - Plant 2 WWTP (8 MLD)

Document Number: NL01257L-P-091-002

Revision: 1

Contents

1	Introduction.....	2
2	General Introduction to Organica FCR	2
2.1	General overview of the proposed solution	2
2.2	Advantages of Hybrid (Attached + Suspended Growth) Systems.....	3
2.3	Advantages of Plant Roots as Biofilm Carriers	3
3	Design Basis.....	4
4	Preliminary Design – Unit Operations	4
	Process overview	5
4.1	Pre-Treatment Units	5
	Fine Screen.....	5
	Grit Removal	6
4.2	Secondary Biological Treatment – Organica FCR	6
	FCR Reactors.....	6
	Process Aeration	6
4.3	Phase Separation	6
	Secondary Clarification	6
4.4	Disinfection	7
	UV Disinfection.....	7
4.5	Solids Management	7
	Sludge storage Tank	7
	Combined Thickening/Dewatering Unit.....	7
	Polymer System	7
5	Control system	8
5.1	Instrumentation and Control	8
5.2	Display Panel, Event Log.....	8
5.3	Control and Variables	8
5.4	Remote Access	8
5.5	Main Intervention Points	8

1 Introduction

This technical description outlines the proposed Organica solution for the **STOWA Study - Plant 2** wastewater treatment facility (WWTF) in **Amsterdam, the Netherlands**. As outlined below, average design capacity of the proposed facility is **8,000 m³/d**.

Organica solutions utilize a Food Chain Reactor (FCR) configuration, consisting of biological treatment in successive reactor zones utilizing fixed biomass on a combination of natural plant roots and Organica's engineered biofiber media, along with a limited amount of suspended biomass.

This document is structured as follows:

- Organica FCR general introduction
- Design basis - influent flow and characterization with treated effluent requirements
- Preliminary design information by unit process
- Description of the control system

2 General Introduction to Organica FCR

2.1 General overview of the proposed solution

The proposed system is an implementation of the Organica Food Chain Reactor (FCR) Solution in a hybrid arrangement (i.e. suspended growth in coexistence with fixed film) which consists of biological wastewater treatment in successive reactors using both suspended biomass and fixed biomass on both natural (plant root) and artificial (patented biofibre media) root structures.

The system's main features are as follows:

- The solution provides organic matter and nutrient removal;
- The solution produces less excess sludge than conventional biological processes;
- The treatment plant extensively uses fixed biomass cultivated on both natural (plant root) and artificial (patented biofibre media) root structures i.e. it is a hybrid solution that exploits all the advantages of fixed film biomass and suspended growth.

In an Organica Hybrid FCR WWTP there is a series of biological reactors where suspended biomass is maintained in every stage of the process, fixed biofilm are used only in the aerated reactor zones. The suspended growth biomass is maintained by a RAS system (return activated sludge) from secondary clarifiers back to the FCRs.

Biodegradation of influent contaminants takes place mainly with the help of fixed and suspended biological cultures, where plant roots are used as biofilm carriers. Additional biofibre media is used in the reactors as artificial plant roots to provide more surface area for biofilm to form and grow on.

In a typical Organica FCR system, as the influent travels through the cascade, the available nutrient quantity is consumed and as a result, the composition of the ecosystem fixed in the biofilm changes from reactor to reactor, gradually adapting itself to the decreasing nutrient concentrations. In each cascade stage a specially adapted ecosystem will form, thus maximizing the decomposition of contaminants.

2.2 Advantages of Hybrid (Attached + Suspended Growth) Systems

- Attached growth in hybrid systems inherently have longer sludge ages than in purely suspended growth systems. Therefore, higher organisms with longer lifecycles (unicellular cilia, worms, arthropods) will establish themselves in hybrid systems. The formation of such a complex ecosystem enables a wider spectrum of organics to be broken down. This effect leads to the lower residual COD level in the effluent.
- Due to the multilevel food-chains that are present in complex ecosystems, the bacteria that process waste material are consumed by other organisms, which are in turn prey for higher predators within the food chain. As a final outcome the yield of the biomass, and consequently the amount of the waste sludge, is lower.
- Since in hybrid systems the majority of biomass responsible for treatment is in fixed form, the washout of microorganisms (e.g. in a snow melt) is only limited to the suspended portion of the biomass.

2.3 Advantages of Plant Roots as Biofilm Carriers

- The specific surface area of plant roots is higher by an order of magnitude when compared to most plastic carrier media. This results in higher equivalent biomass concentrations.
- Plant roots are not susceptible to clogging, thus operational safety is high.
- The plants naturally transport oxygen to their roots which increases biofilm activity.
- The plants excrete small amounts of organic acids on their root surfaces which act as a food source for the biofilm. This is of high importance when the influent load is low. In this case the plants help bacteria to survive starvation and results in a larger population of bacteria in the system when the wastewater load is re-established. As a result the Organica Hybrid FCR system has far greater flexibility and resiliency when compared to purely conventional activated sludge technologies.
- As plant roots are able to grow in the top 0.5 – 1 m of the water, in the lower depth artificial plant roots – Organica's patented biofibre media – are installed. This media is designed to provide very similar habitat for microorganisms as plant roots provide.
- One of the Organica Hybrid FCR Solution's advantages is providing an additional habitat (and a longer sludge age) for slow-growing species – e.g. the nitrifiers – in biofilms attached to plant roots and artificial biotextile media. Due to the significant mass of the biofilm and its biological diversity, higher degree of nutrient removal is possible in the hybrid system compared to purely suspended growth systems.

3 Design Basis

Based on the information provided to Organica and certain assumptions made by Organica, Table 1 below shows the influent characteristics and effluent limits used as the design basis.

Table 1. Influent characteristics and effluent limits used as design basis

Parameters	Influent Characteristics	Units	Effluent Limits	Units
Design average flow (Q_{Average})	8,000	m^3/d	-	m^3/d
Design rainy weather peak flow (Q_{RWA})	1,500	m^3/h	-	m^3/h
Design peak to Biology ($Q_{\text{Peak to Biology}}$)	1,000	m^3/h	-	m^3/h
COD	678	mg/l	< 125	mg/l
BOD ₅	279	mg/l	< 20	mg/l
Total Suspended Solids (TSS)	265	mg/l	< 30	mg/l
Total Kjeldahl Nitrogen (TKN)	71	mg/l	-	mg/l
Total Nitrogen (TN)	-	mg/l	< 10	mg/l
Total Phosphorus (TP)	8	mg/l	< 2	mg/l
Design minimum wastewater temperature (T_{\min})	10.1	$^{\circ}\text{C}$	-	$^{\circ}\text{C}$
Design maximum wastewater temperature (T_{\max})	25	$^{\circ}\text{C}$	-	$^{\circ}\text{C}$

4 Preliminary Design – Unit Operations

This section provides preliminary design information for the proposed treatment unit processes.

The main unit processes are:

- Pre-Treatment
 - Fine screen and grit removal - designed to treat Q_{RWA} ($1,500 \text{ m}^3/\text{h}$)
- Biological Treatment
 - FCR multi-zone reactor with 8 zones in each reactor train
- Secondary Phase Separation
 - Secondary clarifier
- Disinfection
 - UV disinfection - designed to treat Q_{RWA} ($1,500 \text{ m}^3/\text{h}$)
- Solids Management
 - Sludge storage tank
 - Sludge thickening and dewatering

Process overview

The proposed system is an implementation of the Organica Food Chain Reactor (FCR) Solution in a hybrid arrangement (ie. suspended growth in coexistence with fixed film) which consists of biological wastewater treatment in successive reactors using both suspended biomass and fixed biomass on both natural (plant root) and artificial (patented biofibre media) root structures.

In an Organica Hybrid FCR WWTP there is a series of biological reactors where suspended biomass is maintained in every stage of the process, fixed biofilm are used only in the aerated reactor zones. The suspended growth biomass is maintained by a RAS system (return activated sludge) from secondary clarifiers back to the FCRs.

The Process Scheme accompanying this document provides a schematic of the above unit processes as well as the flow connectivity between them. As shown in the process scheme, influent flows to the fine screen and aerated grit chamber (pre-treatment) where solids removal takes place. After pre-treatment, flow is directed to the FCR reactors for biological treatment. The FCR is capable to treat flows up to 1,000 m³/h. Peak flows above the limit will be bypassed.

A biological treatment facility with one FCR train is proposed.

To provide biological nitrogen removal, varying degrees of aeration are used through the aerated reactor zones to create aerobic microbe environments for carbon removal and nitrification.

To complete the denitrification process, a recycle of aerobic zone fluids to the first anoxic zone is required to provide nitrates to the anoxic zone. Biomass is maintained in suspension via mixers. Methanol is dosed to second anoxic zone to improve the denitrification process.

Anoxic zones are the primary location for denitrification where conversion of nitrate into nitrogen gas occurs – nitrate is used as the electron acceptor for organic matter degradation in this zone. Denitrification also takes place in the fixed-film of the aerobic zone, particularly the “deeper” layers of the biofilm where anoxic conditions are present.

Wastewater flows from the FCR to the secondary clarifier unit which gravity-settles the suspended biomass and inert solids to achieve the required effluent TSS limits.

Elimination of pathogens by UV-radiation takes place before discharge. The UV chamber is designed to be able to handle 1,500 m³/h peak flow.

The excess sludge from the clarifier is pumped to a sludge storage tank where air is introduced to avoid anaerobic, septic conditions. From the tank the sludge is directed to a combined thickening/dewatering unit where poly-electrolyte is introduced to improve dewatering processes. The dewatered sludge will be put in containers for further processing. The filtrate from the unit will be sent back to the biology.

4.1 Pre-Treatment Units

Fine Screen

Fine screening is utilized to remove objects prior to the treatment process. These objects are generally inert plastics and other debris that cannot be broken down in biological treatment.

Table 2.Techical Specification of Fine Screens

Item/Parameter	Value	Unit
Opening size	3	mm
Total screenings volume	688	l/d

Grit Removal

Grit removal captures sand, grit, and other fine material that is non-biodegradable prior to biological treatment.

Table 3.Techical Specification of Grit Removal

Item/Parameter	Value	Unit
Number of grit removal basins	1	-
Volume of one basin	74	m ³
Grit removal basin type	Aerated	-
Total air requirement	366	Nm ³ /h
Total grit quantity	400	l/d
Total grease quantity	57	l/d

4.2 Secondary Biological Treatment – Organica FCR

As described above, biological treatment will occur through a series of FCR reactor zones.

FCR Reactors

To provide sufficient habitat for the fixed-film process utilized in FCR solutions, sufficient retention time and surface area will be provided.

Table 4.Techical Specification of Organica FCR reactors

Item/Parameter	Value	Unit
Total volume of reaction zones per train	4,067	m ³
Number of reaction zones per train	8	-
Numbers of trains	2	-
Total Biofiber Media area per train	35,176	m ²
Plant racks per train	201.2	m ²
Total methanol dosage	0 – 1.4	m ³ /d

Process Aeration

Aeration is provided in the FCR zones to maintain mixing and provide sufficient oxygen in the anoxic and aerobic process described previously.

Table 5.Process Aeration Technical Specification

Item/Parameter	Value	Unit
Process air demand (min)	4,350	Nm ³ /h
Process air demand (average)	5,250	Nm ³ /h
Process air demand (max)	6,400	Nm ³ /h

4.3 Phase Separation

Secondary Clarification

Clarification is provided to allow a quiescent settling zone where suspended solids are gravity-settled to the bottom of the clarifier. Settled solids are then pumped directly to the solids handling and dewatering processes.

Table 6. Basic Secondary Clarification Information

Item/Parameter	Value	Unit
Number of units	1	pcs
Side Water Depth	4	m
Surface of one clarifier	500	m ²
RAS flowrate	4,000 – 12,000	m ³ /d

4.4 Disinfection

UV Disinfection

Through passage of UV light into the water, inactivation of bacteria, viruses, and protozoa is accomplished.

4.5 Solids Management

Sludge storage Tank

A sludge storage tank is provided as a buffer to allow intermittent operation of the downstream dewatering equipment.

Table 7. Technical Specification of sludge storage tank

Parameters	Value	Unit
Total Volume of Sludge storage tank	170	m ³
Mixing air requirement	85	Nm ³ /h

Combined Thickening/Dewatering Unit

Sludge flow from the sludge storage tank is directed to the combined thickening and dewatering unit.

Table 8. Technical Specification of combined thickening and dewatering unit

Item/Parameter	Value	Unit
Sludge flow from thickening and dewatering	8.7	m ³ /d
Dry solids content	20	%w/w

Polymer System

Polyelectrolyte is added through various unit processes to optimize solids separation performance.

Table 9. Minimum Design Capacities of Polymer Systems

Item/Parameter	Value	Unit
Sludge thickening and dewatering	15.3	kg/d

5 Control system

The wastewater treatment facility utilizes a PC-PLC based process control system with custom-engineered control software. It integrates the acquisition, display, and storage of operational data, as well as the input and application of operational variables.

5.1 Instrumentation and Control

The design provides appropriate instruments and sensors, as required, for proper operation and control of the system. In general, flow is measured by electromagnetic meters and/or derived from level sensors. Dissolved oxygen probes are provided for monitoring of dissolved oxygen at appropriate locations. Other additional sensors such as instrumentation for online measurement of ammonia, nitrate, or phosphorus may be included in the design as needed depending on the effluent requirements and operational needs. Variable Frequency Drives (VFDs) are provided for pump or blower speed control where necessary. Electromagnetic or pneumatic actuators are provided for valve operation or modulation where necessary. Key equipment is controlled by one or more PLCs, which monitor their status through feedback channels and display on the control application program.

5.2 Display Panel, Event Log

The application program that runs on the PC is adapted and customized to the technology. Its function is to gather, display, print and store information in addition to the implementation of operator commands and settings. The program provides all stored information in a processed and readable format, readily accessible to operators.

The real-time technical parameters (status of equipment, measured values) are displayed on the flowchart of the application program. These values are stored in a central database, which is accessible through charts and summary tables. Changes of technological settings, failures, alarms, and equipment status are stored in the event log.

5.3 Control and Variables

The PLC supervisory program controls the automatic operation of equipment. The automatic operation can be altered by using the commands of the application program or modifying the control parameters. Initial values for these parameters are set during the design of each facility. However, a high level of flexibility is provided for modification of these parameters in the event that actual operating conditions or the influent characteristics differ from those used in the original design.

5.4 Remote Access

Internet and mobile technologies play an essential role in the operation of the facility. Remote access to the control panel and logged data enables technologists to observe and intervene in the treatment process when necessary.

5.5 Main Intervention Points

The most important intervention point is aeration control in the cascade reactors - the PC-PLC system controls the blowers by variable frequency drives thus enabling it to maintain a range from 2 – 4 mg/L dissolved oxygen level in the FCR reactors to optimize kinetics of the biological process, while balancing energy consumption. This control logic is based upon measurement of dissolved oxygen through probes installed in the FCR reactors.